

MONROE TOWNSHIP MUNICIPAL WELLS #4 & #5
#4 - WASHINGTON AVENUE & BLACK HORSE PIKE
#5 - CHESTNUT & WATER STREET
MONROE TOWNSHIP, GLOUCESTER COUNTY
NEW JERSEY
EPA ID# NJD980769699

GENERAL INFORMATION AND SITE HISTORY

The Monroe Township Municipal Wells (MTMW) #4 & #5 are located on two separate parcels of land in Williamstown, Monroe Township, Gloucester County. This area of Monroe Township is considered residential, with an average of 550 people per square mile. These wells are owned by the Township of Monroe and are operated by the Monroe Township Municipal Utilities Authority (MUA). Well #4 was installed on November 15, 1951 and Well #5 on February 4, 1967. These wells were utilized quite extensively until a mercury contamination problem was discovered on June 21, 1976. Well #4 is currently retained only for emergency purposes, while #5 is still on-line.

SITE OPERATIONS CONCERN

The MTMW's #4, #5 and #6 were utilized as the main production wells for the public water supply system of Monroe Township. In 1976, a state instituted program for sampling raw water sources throughout the state had disclosed an inorganic mercury contamination as high as 6.4 PPB in Well #4. Wells #4 and #5 are located respectively on Washington Avenue and Chestnut Streets, with an intervening distance of 1200 feet. At that time, only three wells (#4, #5 & #6) supplied all the potable water for the system. And, the New Jersey Potable Water Standards did not include a maximum contaminant level for mercury, however, a "rule of thumb" maximum of 2.0 PPB was recognized. The National Interim Primary Drinking Water Regulations became effective June 1977 which implemented 2.0 PPB as the maximum contaminant level for mercury. An inspection of the Monroe Township MUA system was conducted on October 5, 1976 but no determination could be made for an immediate source of the mercury. The mercury found in the ground water was in the inorganic form which is slightly less toxic than the alkyl (organic) form. In 1976, sample collection and analysis of ground water from Wells #4 and #5 revealed a maximum mercury content of 6.4 and 2.8 PPB respectively. Also, at that time, system samples revealed mercury values as high as 10.8 PPB. Since then, the levels of mercury have steadily dropped to within the limits of acceptability for potable water. A 1986 analysis of a private potable well at the limit of the MUA water supply system revealed total mercury as high as 3.6 PPB.

The NJDEP/Bureau of Planning and Assessment prepared a preliminary assessment on April 14, 1987 which designated this site a medium priority in need of further investigation. This report revealed several probable sources of the contamination, however, an inactive gravel pit is recognized as the most likely candidate as the source of the mercury contamination. This parcel of land is approximately 10.24 acres and is located adjacent to Clayton Road, upgradient of MTMW's #4 and #5. The pit itself had unauthorized dumping of assorted solid waste over many years. A large



portion of the gravel pit is devoid of vegetation, and is currently used by the neighbors for recreational "all-terrain-vehicles." The solid waste is mostly concrete, asphalt, soil, landscape debris and household trash.

GROUND WATER ROUTE

➤The MTMW site is situated approximately 2000 feet above the Raritan Formation, the bedrock and the parent material of the overlying formations. Starting at the surface, the soil is characterized by Downer Sandy Loam (DsA) and Aura-Sassafras Sandy Loam (AuB) for Well #4 and Well #5 locations respectively. Both of these soils are well drained and have a slope of less than five percent. These soils are characteristic of the Quarternary Bridgeton Formation and extend to a depth of approximately 17 feet. The static ground water level encountered in this area is approximately 12 feet deep and extends into the Cohansey Formation below.

The Cohansey Formation is a major water bearing unit with a total thickness of approximately 100 to 250 feet deep. Locally, there may be more than one water bearing zone present with several clay beds and semiconfined conditions existing, however, the formation is generally regarded as a hydrologic unit. Underlying the Cohansey Sand is the Kirkwood Formation which is a minor aquifer and hydraulically connected to the above formation.

There is only one monitoring well for observing ground water quality in this area. This well is located approximately 0.6 miles southeast of Well #4 on Avery Drive (Newberry Farms) which is screened in the Cohansey Sand Formation with a total depth of 120 feet. The sampling and analysis of this well over time has never resulted in elevated levels of mercury which exceeded the drinking water standards.

The population presently served by ground water is approximately 28,000 people, of which 18,240 people are on public water supply and 9760 people are on private wells. Currently there are four public wells (#4, #5, #6 & #7) which are operated by the MUA. At present, Well #4 is retained only for emergency situations due to elevated levels of mercury detected in the past. The private potable wells and the public supply wells are all screened in the Cohansey Formation. A July 17, 1986 sampling and analysis of a private potable well by the Gloucester County Health Department revealed a mercury contamination of 3.6 PPB. This well is located 0.75 miles West of Well #4, and is hydraulically upgradient of that well. A potential exists for population exposure/injury through mercury contamination of potable wells in this area.

SURFACE WATER ROUTE

There are several surface water routes within a four mile radius of MTMW's #4 and #5. The closest downslope surface water is the Squankum Branch of the Great Egg Harbor River. This surface water is located approximately 0.10 miles from Well #4 and continues in a southeasterly direction toward the Great Egg Harbor River. The Hospitality Branch of the Great Egg Harbor River has its headwaters located 1.3 miles southwest of Well #4. And, the Four Mile Branch of the Great Egg Harbor River is 1.5 miles North of Well #4. There have not been any sampling of these surface waters to document

if contamination has occurred. The potential for surface water contamination via runoff, does not exist. Additionally, the subsurface location of the mercury contaminated ground water precludes the possibility of the contaminants entering the surface water.

The primary use of these surface waters are for recreation. There are no known surface water intakes for potable use or irrigation within the area.

There are several sensitive areas located within the vicinity of the site. Approximately 0.8 miles southeast of Well #4 is a federally designated freshwater wetland. This area is also suspected habitat for the endangered Bog Turtle (Clemmys muhlenbergi) which has precise semiaquatic requirements for this species to survive.

AIR ROUTE

The subsurface location of mercury contaminated ground water precludes any potential for air contamination. In addition, there has not been any air sampling conducted in relation to this site.

SOIL

The Monroe Township Municipal Well site is a confirmed ground water contamination problem. The source of the contamination has not been identified at present, however, it is reasonable to assume that a potential for soil contamination does exist at the source and throughout the Cohansey Sand Formation within the region of the mercury contaminated plume. There has not been any soil sampling conducted in relation to this site, thus qualitative evidence for soil contamination does not exist. A 10.24 acre abandoned gravel pit located off Clayton Road is suspected of being the source of the ground water contamination.

DIRECT CONTACT

The potential for direct contact with the mercury contaminated ground water does not exist due to its subsurface location. The source of the contamination, once identified, may provide a potential pathway for direct contact and population exposure or injury.

FIRE AND EXPLOSION

The potential for fire and explosion at the Monroe Township Municipal Wells do not exist. The subsurface location and the waste characteristics of inorganic mercury precludes this possibility.

ADDITIONAL CONSIDERATIONS

The subsurface location of the mercury contaminated ground water precludes the potential for damage to flora and fauna. Mercury is a lipophilic compound which has the waste characteristics to contaminate the food chain, however, this is not considered possible due to its environmental inaccessibility. An additional consideration of importance is the potential damage to off-site property. The 1986 discovery of 3.8 PPB mercury in a potable well at a Williamstown High School Building may be evidence of damage to offsite property through contamination of this potable well.

ENFORCEMENT ACTIONS

On November 3, 1976 the NJDEP/Bureau of Flood Plain Management Element advised the MUA to immediately undertake the construction of new wells to replace Wells #4 and #5 and, in the interim, use Well #6 as the main production well, augmented as necessary by Well #5 to meet daily water demands. It was also suggested that Well #4 be taken out of service and retained only for standby purposes to meet a dire emergency such as a major fire. Additionally, an inspection of the Monroe Township MUA system was conducted on October 5, 1976, however, no determination could be made for any probable source of the mercury contamination. A total of 24 public water supply wells in the area surrounding Monroe Township were sampled, all with negative results for mercury. On July 17, 1986 the Gloucester County Health Department conducted an investigation into the mercury contamination of a potable well. Subsequent sampling and analysis revealed 3.6 PPB mercury in this well. The County recommended the use of bottled water until a permanent alternate supply can be provided. A preliminary assessment was conducted by the NJDEP/Bureau of Planning and Assessment on April 14, 1987. This investigation has designated this a medium priority site with a potential for population exposure/injury through the use of the residential potable wells.

PRIORITY DESIGNATION

This site is designated a medium priority site due to the confirmed ground water contamination that currently exists. Since no remediation has occurred, a potential exists for population exposure/injury through potable well contamination.

SUMMARY OF SAMPLING DATA

1.

A. Sampling date: 6/21/76
B. Sampled by: NJDEP
C. Samples: 3 - public supply wells (4,5 & 6)
D. Laboratory: NJDEP
E. Parameters: Potable water standards and heavy metals.
F. Sample description: 3 - aqueous samples of ground water
G. Contaminants detected: Inorganic mercury
H. QA/QC: There were no samples collected and analyzed for QA/QC results. The laboratory that did the analysis was a state organization. It is not known whether a Chain of Custody was implemented. A formal NJDEP QA review was not conducted for this sampling episode.
I. File locations: Gloucester County Health Department

2.

A. Sampling date: 7/19/76
B. Sampled by: NJDEP
C. Samples: 2 - public supply wells (4 & 5)
D. Laboratory: NJDEP
E. Parameters: Potable Water Standards and heavy metals
F. Sample description: 2 - aqueous samples of ground water
G. Contaminants detected: Inorganic mercury
H. QA/QC: There were no samples collected and analyzed for QA/QC results. The laboratory that did the analysis was a state organization. It is not known whether a Chain of Custody was implemented. A formal NJDEP QA review was not conducted for this sampling episode.
I. File location: Gloucester County Health Department

3.

A. Sampling date: 8/18/76
B. Sampled by: NJDEP
C. Samples: 2 - public supply wells (#4 & #5)
1 - public supply system
D. Laboratory: NJDEP
E. Parameters: Potable Water Standards and heavy metals.
F. Sample description: 3 aqueous samples
G. Contaminants detected: Inorganic mercury
H. QA/QC: There were no samples collected and analyzed for QA/QC results. The laboratory that did the analysis was a state organization. It is not known whether a Chain of Custody was implemented. A formal NJDEP QA review was not conducted for this sampling episode.
I. File locations: Gloucester County Health Department

4.

A. Sampling date: 1/29/88
B. Sampled by: P & P Laboratories, Inc.
C. Samples: 4 - public supply wells
1 - monitoring well
D. Laboratory: P & P Laboratories, Inc.,
Woodlynne, New Jersey
E. Parameters: Mercury
F. Sample description: 5 - aqueous samples of ground water
G. Contaminants detected: None
H. QA/QC: Neither trip blank, field blank, or duplicate was collected and analyzed for QA/QC results. This laboratory was certified for metals and inorganics at the time of this analysis. A formal Chain of Custody was not implemented from the time of sample collection until the analysis was performed. A formal NJDEP QA review was not conducted for the sampling episode.
I. File locations: Gloucester County Health Department
Monroe Township Municipal Utilities Authority.

RECOMMENDATIONS

The Monroe Township Municipal Well contamination by inorganic mercury no longer exists. The elevated levels of mercury which exceeded the federal drinking water standards have decreased over time and are now within the acceptable limits for potable water.

The 1986 discovery of inorganic mercury in a residential potable well may be evidence that the contaminated ground water plume has migrated. A referral will be made through the DWR/Bureau of Safe Drinking Water to the Southern Bureau of Regional Enforcement to determine the vertical and horizontal extent of the ground water contamination in this area. This Bureau will also conduct an investigation of the area to assess probable sources of the mercury contamination.

Hours Worked: 85

Submitted by:



Frank Faranca, HSMS IV
NJDEP/DHWM/BPA



Site Inspection Report


MONROE TOWNSHIP MUNICIPAL WELLS #4 & #5
#4 - Washington Avenue & Black Horse Pike
#5 - Chestnut & Water Street
Monroe Township / Gloucester County
New Jersey
EPA ID# NJD980769699



01 SITE NAME (Legal, common, or descriptive name of site) Monroe Twp. Municipal Wells #4 & #5			02 STREET, ROUTE NO., OR SPECIFIC LOCATION IDENTIFIER Washington Avenue; Chestnut Street					
03 CITY Monroe Township			04 STATE NJ	05 ZIP CODE 08094	06 COUNTY Gloucester		07 COUNTY CODE	08 CONG DIST
09 COORDINATES LATITUDE -39 41 03--		LONGITUDE -74 59 25--		10 TYPE OF OWNERSHIP (Check one) <input type="checkbox"/> A. PRIVATE <input type="checkbox"/> B. FEDERAL <input type="checkbox"/> C. STATE <input type="checkbox"/> D. COUNTY <input checked="" type="checkbox"/> E. MUNICIPAL <input type="checkbox"/> F. OTHER <input type="checkbox"/> G. UNKNOWN				

01 DATE OF INSPECTION <div style="text-align: center;"> <u> </u> / <u> </u> / <u> </u> MONTH DAY YEAR </div>	02 SITE STATUS <input checked="" type="checkbox"/> ACTIVE <input type="checkbox"/> INACTIVE	03 YEARS OF OPERATION <div style="text-align: center;"> <u>11/15/51</u> <u>Present</u> <u> </u> UNKNOWN⁰³ BEGINNING YEAR ENDING YEAR </div>
04 AGENCY PERFORMING INSPECTION (Check all that apply)		
<input type="checkbox"/> A. EPA <input type="checkbox"/> B. EPA CONTRACTOR _____ (Name of firm) <input type="checkbox"/> C. MUNICIPAL <input type="checkbox"/> D. MUNICIPAL CONTRACTOR _____ (Name of firm)		
<input checked="" type="checkbox"/> E. STATE <input type="checkbox"/> F. STATE CONTRACTOR _____ (Name of firm) <input type="checkbox"/> G. OTHER _____ (Specify)		

IV. INFORMATION AVAILABLE FROM			
01 CONTACT		02 OF (Agency/Organization)	
George Cassabone, Superintendent		Monroe Twp. MUA	
04 PERSON RESPONSIBLE FOR SITE INSPECTION FORM		05 AGENCY	06 ORGANIZATION
Frank Faranca, HSMS III		NJDEP	DHWM/BPA
		07 TELEPHONE NO.	08 DATE
		(609) 292-1418	04 15 88 MONTH DAY YEAR



<input type="checkbox"/> A. TOXIC	<input type="checkbox"/> E. SOLUBLE	<input checked="" type="checkbox"/> I. HIGHLY VOLATILE
<input type="checkbox"/> B. CORROSIVE	<input type="checkbox"/> F. INFECTIOUS	<input type="checkbox"/> J. EXPLOSIVE
<input type="checkbox"/> C. RADIOACTIVE	<input type="checkbox"/> G. FLAMMABLE	<input type="checkbox"/> K. REACTIVE
<input type="checkbox"/> D. PERSISTENT	<input type="checkbox"/> H. IGNITABLE	<input type="checkbox"/> L. INCOMPATIBLE
		<input type="checkbox"/> M. NOT APPLICABLE

EPA FORM 2070-13 (7-81)



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

L IDENTIFICATION

01 STATE 02 SITE NUMBER
NJ 0980769699

II. HAZARDOUS CONDITIONS AND INCIDENTS

01 ☒ A. GROUNDWATER CONTAMINATION
03 POPULATION POTENTIALLY AFFECTED: _____

02 ☒ OBSERVED (DATE: 6/31/76)
04 NARRATIVE DESCRIPTION

☐ POTENTIAL ☐ ALLEGED

A state program for sampling raw water sources revealed a mercury contamination problem in excess of the National Safe Drinking Water Standards. Well sample analysis revealed mercury as high as 6.4 ppb in well #4 and 2.8 ppb in well #5. (Att. B4)

01 ☐ B. SURFACE WATER CONTAMINATION
03 POPULATION POTENTIALLY AFFECTED: _____

02 ☐ OBSERVED (DATE: _____)
04 NARRATIVE DESCRIPTION

☐ POTENTIAL ☐ ALLEGED

The Squankum Branch of the Great Egg Harbor River is located .10 miles from well #4. The subsurface location of the mercury contaminated groundwater precludes the possibility of surface water contamination. (Att. 1 & 2)

01 ☐ C. CONTAMINATION OF AIR
03 POPULATION POTENTIALLY AFFECTED: _____

02 ☐ OBSERVED (DATE: _____)
04 NARRATIVE DESCRIPTION

☐ POTENTIAL ☐ ALLEGED

The subsurface location of the contaminants precludes the possibility of air contamination.

01 ☐ D. FIRE EXPLOSIVE CONDITIONS
03 POPULATION POTENTIALLY AFFECTED: _____

02 ☐ OBSERVED (DATE: _____)
04 NARRATIVE DESCRIPTION

☐ POTENTIAL ☐ ALLEGED

The waste characteristics of inorganic mercury does not include any potential for fire or explosion.

01 ☐ E. DIRECT CONTACT
03 POPULATION POTENTIALLY AFFECTED: _____

02 ☐ OBSERVED (DATE: _____)
04 NARRATIVE DESCRIPTION

☐ POTENTIAL ☐ ALLEGED

The potential for direct contact does not exist due to the subsurface location of the mercury.

01 ☒ F. CONTAMINATION OF SOIL
03 AREA POTENTIALLY AFFECTED: _____ (Acres)

02 ☐ OBSERVED (DATE: _____)
04 NARRATIVE DESCRIPTION

☒ POTENTIAL ☐ ALLEGED

The observation of mercury in public and private wells within Monroe Township may be the result of surface soil contamination.

01 ☒ G. DRINKING WATER CONTAMINATION
03 POPULATION POTENTIALLY AFFECTED: _____

02 ☒ OBSERVED (DATE: 6/21/76)
04 NARRATIVE DESCRIPTION

☐ POTENTIAL ☐ ALLEGED

The levels of mercury found in wells #4 & 5 have decreased since its discovery, however, additional residential potable wells may be in danger of contamination through migration of this plume. (Att. A, B)

01 ☐ H. WORKER EXPOSURE/INJURY
03 WORKERS POTENTIALLY AFFECTED: _____

02 ☐ OBSERVED (DATE: _____)
04 NARRATIVE DESCRIPTION

☐ POTENTIAL ☐ ALLEGED

The potential for worker exposure/injury does not exist. The levels of mercury within wells #4 & 5 have decreased to acceptable tolerances, precluding the possibility of MUA employee exposure. (Att. A)

01 ☒ I. POPULATION EXPOSURE/INJURY
03 POPULATION POTENTIALLY AFFECTED: 9800

02 ☐ OBSERVED (DATE: _____)
04 NARRATIVE DESCRIPTION

☒ POTENTIAL ☐ ALLEGED

The current population of Monroe Township is approximately 28,000 people, of which 9800 people (35%) are not on public water supply and may be potentially at risk. (Att. G)



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
NJ D980759699

II. HAZARDOUS CONDITIONS AND INCIDENTS (Continued)

01 ☐ J. DAMAGE TO FLORA 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
04 NARRATIVE DESCRIPTION

The potential for damage to flora does not exist due to the subsurface location of the contaminants.

01 ☐ K. DAMAGE TO FAUNA 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
04 NARRATIVE DESCRIPTION (include name(s) of species)

The Squankum and Hospitality Branch of the Great Egg Harbor River are confirmed waterways supporting anadromous herring species, however, the subsurface location of the contaminants precludes the possibility of damage to the aquatic and terrestrial fauna. (Att. H)

01 ☐ L. CONTAMINATION OF FOOD CHAIN 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
04 NARRATIVE DESCRIPTION

Mercury is a lipophilic compound which has the potential to contaminate the food chain, however, the location of the contaminants precludes this possibility.

01 ☒ M. UNSTABLE CONTAINMENT OF WASTES 02 ☒ OBSERVED (DATE: 6/21/76) ☐ POTENTIAL ☐ ALLEGED
(Spills, Runoff, Standing liquids, Leaking drums)

03 POPULATION POTENTIALLY AFFECTED: 8200 04 NARRATIVE DESCRIPTION

An unknown source of mercury waste has contaminated the groundwater in Monroe Township. (Att. B)

01 ☒ N. DAMAGE TO OFFSITE PROPERTY 02 ☐ OBSERVED (DATE: _____) ☒ POTENTIAL ☐ ALLEGED
04 NARRATIVE DESCRIPTION

The 1986 discovery of 3.8 ppb mercury in a potable well at Williamstown High School may be evidence of damage to offsite property through potable well contamination. (Att. B)

01 ☐ O. CONTAMINATION OF SEWERS, STORM DRAINS, WWTPs 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
04 NARRATIVE DESCRIPTION

The sampling and analysis of standing water in a storm sewer culvert which accepts well #4 overflow revealed mercury at levels below detectable limits. (Att. B30)

01 ☒ P. ILLEGAL/UNAUTHORIZED DUMPING 02 ☐ OBSERVED (DATE: _____) ☒ POTENTIAL ☐ ALLEGED
04 NARRATIVE DESCRIPTION

A potential exists for the illegal/unauthorized dumping of waste to be contributing to the groundwater contamination.

05 DESCRIPTION OF ANY OTHER KNOWN, POTENTIAL, OR ALLEGED HAZARDS

Approximately 9760 people are not hooked up to the Municipal Water Supply and are at risk of being exposed to the contaminated groundwater through the use of their domestic wells.

III. TOTAL POPULATION POTENTIALLY AFFECTED: 9760

IV. COMMENTS

A referral will be sent to Southern Regional Enforcement through the Bureau of Safe Drinking Water to determine the extent of groundwater contamination in residential potable wells.

V. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)

Attachment 1: USGS Topographic Map
2: State Atlas Map
A: Monroe MUA - Water Potability Analysis
B: Site History 6/21/76 to 9/3/86
G: Memo to File
H: Technical Manual for Stream Enforcement



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION
PART 4 - PERMIT AND DESCRIPTIVE INFORMATION

I. IDENTIFICATION

01 STATE NJ 02 SITE NUMBER D980769699

II. PERMIT INFORMATION

01 TYPE OF PERMIT ISSUED (Check all that apply)	02 PERMIT NUMBER	03 DATE ISSUED	04 EXPIRATION DATE	05 COMMENTS
<input type="checkbox"/> A. NPDES				
<input type="checkbox"/> B. UIC				
<input type="checkbox"/> C. AIR				
<input type="checkbox"/> D. RCRA				
<input type="checkbox"/> E. RCRA INTERIM STATUS				
<input type="checkbox"/> F. SPCC PLAN				
<input type="checkbox"/> G. STATE (Specify) Well # 4	31-361	11/15/51	None	Emergency use only
<input type="checkbox"/> H. LOCAL (Specify)				
<input type="checkbox"/> I. OTHER (Specify) Well # 5	31-5035	2/4/67	None	Currently in use
<input type="checkbox"/> J. NONE				

III. SITE DESCRIPTION

01 STORAGE/ DISPOSAL (Check all that apply)	02 AMOUNT	03 UNIT OF MEASURE	04 TREATMENT (Check all that apply)	05 OTHER
<input type="checkbox"/> A. SURFACE IMPOUNDMENT			<input type="checkbox"/> A. INCENERATION	<input checked="" type="checkbox"/> A. BUILDINGS ON SITE
<input type="checkbox"/> B. PILES			<input type="checkbox"/> B. UNDERGROUND INJECTION	Pump House
<input type="checkbox"/> C. DRUMS, ABOVE GROUND			<input type="checkbox"/> C. CHEMICAL/PHYSICAL	06 AREA OF SITE
<input type="checkbox"/> D. TANK, ABOVE GROUND			<input type="checkbox"/> D. BIOLOGICAL	Unknown (Acres)
<input type="checkbox"/> E. TANK, BELOW GROUND			<input type="checkbox"/> E. WASTE OIL PROCESSING	
<input type="checkbox"/> F. LANDFILL			<input type="checkbox"/> F. SOLVENT RECOVERY	
<input type="checkbox"/> G. LANDFARM			<input type="checkbox"/> G. OTHER RECYCLING/RECOVERY	
<input type="checkbox"/> H. OPEN DUMP			<input checked="" type="checkbox"/> H. OTHER None (Specify)	
<input checked="" type="checkbox"/> I. OTHER Unknown (Specify)	Unknown			

07 COMMENTS

The Monroe Township Municipal wells #4 & 5 are located in a residential area of Williamstown. These wells have experienced elevated levels of mercury as high as 6.4 ppb in July 1976. Since that time the levels of mercury has decreased to acceptable tolerances. The source of the groundwater contamination has not been determined and residential potable wells may be at risk. (Att. B)

IV. CONTAINMENT

01 CONTAINMENT OF WASTES (Check one)
☐ A. ADEQUATE, SECURE ☐ B. MODERATE ☐ C. INADEQUATE, POOR ☒ D. INSECURE, UNSOUND, DANGEROUS

02 DESCRIPTION OF DRUMS, DIKING, LINERS, BARRIERS, ETC.

The source of the mercury contamination is not known at the present time. It is suspected that illegal/unauthorized dumping of mercury associated waste within the vicinity has created the present groundwater contamination.

(Att. F)

V. ACCESSIBILITY

01 WASTE EASILY ACCESSIBLE: ☐ YES ☒ NO

02 COMMENTS

The subsurface location of the mercury contaminated groundwater precludes the possibility of accessibility to the general public. (Att. B)

VI. SOURCES OF INFORMATION (Cite specific references, e.g. state files, sample analysis, reports)

Attachment B: Site History 6/21/76 to 9/3/86
C: NJDEP Well Record Information
F: Memo to File



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 5 - WATER, DEMOGRAPHIC, AND ENVIRONMENTAL DATA

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
NJ D980759699

II. DRINKING WATER SUPPLY

01 TYPE OF DRINKING SUPPLY
(Check as applicable)

SURFACE WELL
COMMUNITY A. ☐ B. ☒
NON-COMMUNITY C. ☐ D. ☒

02 STATUS

ENDANGERED AFFECTED MONITORED
A. ☐ B. ☒ C. ☐
D. ☐ E. ☒ F. ☐

03 DISTANCE TO SITE

A. 0.0 (mi)
B. 0.5 (mi)

III. GROUNDWATER

01 GROUNDWATER USE IN VICINITY (Check one)

☒ A. ONLY SOURCE FOR DRINKING
☐ B. DRINKING (Other sources available)
COMMERCIAL, INDUSTRIAL, IRRIGATION (No other water sources available)
☐ C. COMMERCIAL, INDUSTRIAL, IRRIGATION (Limited other sources available)
☐ D. NOT USED, UNUSEABLE

02 POPULATION SERVED BY GROUND WATER 28,000

03 DISTANCE TO NEAREST DRINKING WATER WELL on site (mi)

04 DEPTH TO GROUNDWATER

12 (ft)

05 DIRECTION OF GROUNDWATER FLOW

SE

06 DEPTH TO AQUIFER OF CONCERN

17 (ft)

07 POTENTIAL YIELD OF AQUIFER

(gpd)

08 SOLE SOURCE AQUIFER

☐ YES ☒ NO

09 DESCRIPTION OF WELLS (including usage, depth, and location relative to population and buildings)

The Monroe Township wells #4 & 5 tap the Cohansey aquifer for public supply usage. The total depth and yield of these wells are: 106', 800 GPM and 160', 510 GPM respectively. These wells are located within Williamstown and have an intervening distance of 1200 feet.

10 RECHARGE AREA

☐ YES
☐ NO

COMMENTS

11 DISCHARGE AREA

☐ YES
☐ NO

COMMENTS

IV. SURFACE WATER

01 SURFACE WATER USE (Check one)

☒ A. RESERVOIR, RECREATION, DRINKING WATER SOURCE
☐ B. IRRIGATION, ECONOMICALLY IMPORTANT RESOURCES
☐ C. COMMERCIAL, INDUSTRIAL
☐ D. NOT CURRENTLY USED

02 AFFECTED/POTENTIALLY AFFECTED BODIES OF WATER

NAME:

AFFECTED

DISTANCE TO SITE

Squankum Branch of Great Egg Harbor River ☐ 0.1 (mi)
Hospitality Branch of Great Egg Harbor River ☐ 1.3 (mi)
Four Mile Branch of Great Egg Harbor River ☐ 1.5 (mi)

V. DEMOGRAPHIC AND PROPERTY INFORMATION

01 TOTAL POPULATION WITHIN

ONE (1) MILE OF SITE
A. 1700
NO. OF PERSONS

TWO (2) MILES OF SITE
B. 6900
NO. OF PERSONS

THREE (3) MILES OF SITE
C. 15543
NO. OF PERSONS

02 DISTANCE TO NEAREST POPULATION

0.1 (mi)

03 NUMBER OF BUILDINGS WITHIN TWO (2) MILES OF SITE

1800

04 DISTANCE TO NEAREST OFF-SITE BUILDING

0.1 (mi)

05 POPULATION WITHIN VICINITY OF SITE (Provide narrative description of nature of population within vicinity of site, e.g., rural, village, densely populated urban area)

The population within the vicinity is residential, with an average of 550 people per square mile. This figure is an average for all of Monroe Township, with slightly higher population density within Williamstown proper, and sparsely populated at its outskirts.

(Att. G)



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 5 - WATER, DEMOGRAPHIC, AND ENVIRONMENTAL DATA

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
NJ D980769699

VI. ENVIRONMENTAL INFORMATION

01 PERMEABILITY OF UNSATURATED ZONE (Check one)

☐ A. $10^{-6} - 10^{-8}$ cm/sec ☐ B. $10^{-4} - 10^{-6}$ cm/sec ☒ C. $10^{-4} - 10^{-3}$ cm/sec ☐ D. GREATER THAN 10^{-3} cm/sec

02 PERMEABILITY OF BEDROCK (Check one)

☒ A. IMPERMEABLE
(Less than 10^{-6} cm/sec) ☐ B. RELATIVELY IMPERMEABLE
($10^{-4} - 10^{-6}$ cm/sec) ☐ C. RELATIVELY PERMEABLE
($10^{-2} - 10^{-4}$ cm/sec) ☐ D. VERY PERMEABLE
(Greater than 10^{-2} cm/sec)

03 DEPTH TO BEDROCK

2000 (ft)

04 DEPTH OF CONTAMINATED SOIL ZONE

106 (ft)

05 SOIL pH

06 NET PRECIPITATION

12 (in)

07 ONE YEAR 24 HOUR RAINFALL

2.75 (in)

08 SLOPE

SITE SLOPE
< 5 %

DIRECTION OF SITE SLOPE
SE

TERRAIN AVERAGE SLOPE
< 5 %

09 FLOOD POTENTIAL

SITE IS IN 500 YEAR FLOODPLAIN

10

☐ SITE IS ON BARRIER ISLAND, COASTAL HIGH HAZARD AREA, RIVERINE FLOODWAY

11 DISTANCE TO WETLANDS (5 acre minimum)

ESTUARINE

OTHER

A. > 5 (mi)

B. 0.8 (mi)

12 DISTANCE TO CRITICAL HABITAT (of endangered species)

0.8 (mi)

ENDANGERED SPECIES: Bog Turtle

13 LAND USE IN VICINITY

DISTANCE TO:

COMMERCIAL/INDUSTRIAL

RESIDENTIAL AREAS, NATIONAL/STATE PARKS,
FORESTS, OR WILDLIFE RESERVES

AGRICULTURAL LANDS
PRIME AG LAND AG LAND

A. < .1 (mi)

B. < .1 (mi)

C. .5 (mi)

D. .5 (mi)

14 DESCRIPTION OF SITE IN RELATION TO SURROUNDING TOPOGRAPHY

The Monroe Township Municipal Wells are located in a relatively level area with an average site slope of less than 5 percent. In general, the elevations range from 120 to 170 feet. Surface water drainage is typically toward the south east and the Great Egg Harbor River. A fresh water wetland is also located .8 miles to the south east following the floodplain of the Squankum Branch of the Great Egg Harbor River. Approximately 55 percent of the area has been cleared and is used mainly for general crops, vegetables and fruits.

VII. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)

Attachment: Map 1 USGS Wuadrangle Map
Map 11 Flood Insurance Rate Map
D Geologic Information
E Endangered & Threatened Species
G Memo to File



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 6 - SAMPLE AND FIELD INFORMATION

I. IDENTIFICATION

01 STATE 02 SITE NUMBER

NJ

D980769699

II. SAMPLES TAKEN

SAMPLE TYPE	01 NUMBER OF SAMPLES TAKEN	02 SAMPLES SENT TO	03 ESTIMATED DATE RESULTS AVAILABLE
GROUNDWATER	13	P + P Laboratories, Inc.; NJDEP	Presently Available
SURFACE WATER			
WASTE			
AIR			
RUNOFF			
SPILL			
SOIL			
VEGETATION			
OTHER			

III. FIELD MEASUREMENTS TAKEN

01 TYPE	02 COMMENTS

IV. PHOTOGRAPHS AND MAPS

01 TYPE <input type="checkbox"/> GROUND <input type="checkbox"/> AERIAL	02 IN CUSTODY OF _____ <small>(Name of organization or individual)</small>
03 MAPS <input type="checkbox"/> YES <input type="checkbox"/> NO	04 LOCATION OF MAPS _____

V. OTHER FIELD DATA COLLECTED (Provide narrative description)

VI. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis reports)

Attachment A: Monroe MUA - Water Potability Analysis
B: Site History 6/21/76 to 9/3/86



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 7 - OWNER INFORMATION

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
NJ 0980769699

II. CURRENT OWNER(S)

PARENT COMPANY (if applicable)

01 NAME Monroe Township		02 D+B NUMBER		08 NAME NA		09 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.) 3 South Main Street		04 SIC CODE		10 STREET ADDRESS (P.O. Box, RFD #, etc.)		11 SIC CODE	
05 CITY Williamstown		06 STATE NJ	07 ZIP CODE 08094	12 CITY		13 STATE	14 ZIP CODE
01 NAME		02 D+B NUMBER		08 NAME		09 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE		10 STREET ADDRESS (P.O. Box, RFD #, etc.)		11 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	12 CITY		13 STATE	14 ZIP CODE
01 NAME		02 D+B NUMBER		08 NAME		09 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE		10 STREET ADDRESS (P.O. Box, RFD #, etc.)		11 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	12 CITY		13 STATE	14 ZIP CODE
01 NAME		02 D+B NUMBER		08 NAME		09 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE		10 STREET ADDRESS (P.O. Box, RFD #, etc.)		11 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	12 CITY		13 STATE	14 ZIP CODE

III. PREVIOUS OWNER(S) (List most recent first)

IV. REALTY OWNER(S) (if applicable; list most recent first)

01 NAME NA		02 D+B NUMBER		01 NAME NA		02 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE		03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	05 CITY		06 STATE	07 ZIP CODE
01 NAME		02 D+B NUMBER		01 NAME		02 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE		03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	05 CITY		06 STATE	07 ZIP CODE
01 NAME		02 D+B NUMBER		01 NAME		02 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE		03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	05 CITY		06 STATE	07 ZIP CODE

V. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 8 - OPERATOR INFORMATION

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
NJ D980769699

II. CURRENT OPERATOR (Provide if different from owner)

OPERATOR'S PARENT COMPANY (If applicable)

01 NAME Monroe Township MUA		02 D+B NUMBER		10 NAME NA		11 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.) 372 South Main Street		04 SIC CODE		12 STREET ADDRESS (P.O. Box, RFD #, etc.)		13 SIC CODE	
05 CITY Williamstown		06 STATE NJ	07 ZIP CODE 08094	14 CITY		15 STATE	16 ZIP CODE
08 YEARS OF OPERATION 1951 - Present		09 NAME OF OWNER Monroe Township					

III. PREVIOUS OPERATOR(S) (List most recent first; provide only if different from owner)

PREVIOUS OPERATORS' PARENT COMPANIES (If applicable)

01 NAME NA		02 D+B NUMBER		10 NAME NA		11 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE		12 STREET ADDRESS (P.O. Box, RFD #, etc.)		13 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	14 CITY		15 STATE	16 ZIP CODE
08 YEARS OF OPERATION		09 NAME OF OWNER DURING THIS PERIOD					

01 NAME		02 D+B NUMBER		10 NAME		11 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE		12 STREET ADDRESS (P.O. Box, RFD #, etc.)		13 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	14 CITY		15 STATE	16 ZIP CODE
08 YEARS OF OPERATION		09 NAME OF OWNER DURING THIS PERIOD					

01 NAME		02 D+B NUMBER		10 NAME		11 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE		12 STREET ADDRESS (P.O. Box, RFD #, etc.)		13 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	14 CITY		15 STATE	16 ZIP CODE
08 YEARS OF OPERATION		09 NAME OF OWNER DURING THIS PERIOD					

IV. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 9 - GENERATOR/TRANSPORTER INFORMATION

I. IDENTIFICATION

01 STATE NJ 02 SITE NUMBER D980769699

II. ON-SITE GENERATOR

01 NAME NA	02 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE	
05 CITY	06 STATE 07 ZIP CODE	

III. OFF-SITE GENERATOR(S)

01 NAME NA	02 D+B NUMBER	01 NAME	02 D+B NUMBER
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE
05 CITY	06 STATE 07 ZIP CODE	05 CITY	06 STATE 07 ZIP CODE
01 NAME	02 D+B NUMBER	01 NAME	02 D+B NUMBER
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE
05 CITY	06 STATE 07 ZIP CODE	05 CITY	06 STATE 07 ZIP CODE

IV. TRANSPORTER(S)

01 NAME NA	02 D+B NUMBER	01 NAME	02 D+B NUMBER
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE
05 CITY	06 STATE 07 ZIP CODE	05 CITY	06 STATE 07 ZIP CODE
01 NAME	02 D+B NUMBER	01 NAME	02 D+B NUMBER
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE
05 CITY	06 STATE 07 ZIP CODE	05 CITY	06 STATE 07 ZIP CODE

V. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 10 - PAST RESPONSE ACTIVITIES

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
NJ D980769699

II. PAST RESPONSE ACTIVITIES

01 <input checked="" type="checkbox"/> A. WATER SUPPLY CLOSED 04 DESCRIPTION	02 DATE 11/3/76	03 AGENCY MUA
Monroe Township MUA closed well #4 for daily water demands and is retained only for emergency situations. (Att. B)		
01 <input type="checkbox"/> B. TEMPORARY WATER SUPPLY PROVIDED 04 DESCRIPTION	02 DATE	03 AGENCY
01 <input type="checkbox"/> C. PERMANENT WATER SUPPLY PROVIDED 04 DESCRIPTION	02 DATE	03 AGENCY
01 <input type="checkbox"/> D. SPILLED MATERIAL REMOVED 04 DESCRIPTION	02 DATE	03 AGENCY
01 <input type="checkbox"/> E. CONTAMINATED SOIL REMOVED 04 DESCRIPTION	02 DATE	03 AGENCY
01 <input type="checkbox"/> F. WASTE REPACKAGED 04 DESCRIPTION	02 DATE	03 AGENCY
01 <input type="checkbox"/> G. WASTE DISPOSED ELSEWHERE 04 DESCRIPTION	02 DATE	03 AGENCY
01 <input type="checkbox"/> H. ON SITE BURIAL 04 DESCRIPTION	02 DATE	03 AGENCY
01 <input type="checkbox"/> I. IN SITU CHEMICAL TREATMENT 04 DESCRIPTION	02 DATE	03 AGENCY
01 <input type="checkbox"/> J. IN SITU BIOLOGICAL TREATMENT 04 DESCRIPTION	02 DATE	03 AGENCY
01 <input type="checkbox"/> K. IN SITU PHYSICAL TREATMENT 04 DESCRIPTION	02 DATE	03 AGENCY
01 <input type="checkbox"/> L. ENCAPSULATION 04 DESCRIPTION	02 DATE	03 AGENCY
01 <input type="checkbox"/> M. EMERGENCY WASTE TREATMENT 04 DESCRIPTION	02 DATE	03 AGENCY
01 <input type="checkbox"/> N. CUTOFF WALLS 04 DESCRIPTION	02 DATE	03 AGENCY
01 <input type="checkbox"/> O. EMERGENCY DIKING/SURFACE WATER DIVERSION 04 DESCRIPTION	02 DATE	03 AGENCY
01 <input type="checkbox"/> P. CUTOFF TRENCHES/SUMP 04 DESCRIPTION	02 DATE	03 AGENCY
01 <input type="checkbox"/> Q. SUBSURFACE CUTOFF WALL 04 DESCRIPTION	02 DATE	03 AGENCY



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 10 - PAST RESPONSE ACTIVITIES

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
NJ D980769699

II. PAST RESPONSE ACTIVITIES (Continued)

01 ☐ R. BARRIER WALLS CONSTRUCTED
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ S. CAPPING/COVERING
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ T. BULK TANKAGE REPAIRED
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ U. GROUT CURTAIN CONSTRUCTED
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ V. BOTTOM SEALED
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ W. GAS CONTROL
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ X. FIRE CONTROL
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ Y. LEACHATE TREATMENT
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ Z. AREA EVACUATED
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ 1. ACCESS TO SITE RESTRICTED
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ 2. POPULATION RELOCATED
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ 3. OTHER REMEDIAL ACTIVITIES
04 DESCRIPTION

02 DATE

03 AGENCY

III. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)

Attachment B: Site History 6/21/76 to 9/3/86



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 11 - ENFORCEMENT INFORMATION

I. IDENTIFICATION

01 STATE	02 SITE NUMBER
NJ	D980769699

II. ENFORCEMENT INFORMATION

01 PAST REGULATORY/ENFORCEMENT ACTION ☒ YES ☐ NO Well #4 - taken out of daily service.

02 DESCRIPTION OF FEDERAL, STATE, LOCAL REGULATORY/ENFORCEMENT ACTION

A state program instituted for sampling raw water sources throughout the state had disclosed a mercury contamination in two wells owned and operated by the Monroe Township Municipal Utilities Authority. Sample collection and analysis was conducted and revealed mercury contamination in Well #4 and Well #5 as high as 6.4 ppb and 2.8 ppb respectively. System samples were also collected and analyzed revealing mercury values as high as 10.8 ppb. A subsequent inspection was conducted, but no determination could be made for an immediate source of the mercury. Well #4 was subsequently taken out of service and was retained only for standby purposes to meet a dire emergency such as a major fire. On 7/17/86 an investigation was made by the Gloucester County Health Department into an alleged mercury contamination in a potable well. Subsequent sample analysis revealed 3.6 ppb mercury in the well. The county recommended the use of bottled water until a permanent alternate supply can be provided. A preliminary assessment was conducted by the NJDEP/Bureau of Planning and Assessment on 4/14/87. This investigation has designated this a medium priority site with a potential for population exposure/injury through the use of the residential potable wells.

III. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)

Attachment B: Site History 6/21/76 to 9/3/86
I: NJDEP/BPA - Preliminary Assessment 4/14/87

SI REVIEW SHEET

SITE: Monroe Twp. Municipal Wells #4 & 5

AKA: _____

CITY: Monroe Township

COUNTY: Gloucester

DATE SAMPLED: FROM 6/21/76 TO 1/29/88

EPA ID #: NJD980769699

SITE LEAD: Gloucester County Health Dept.

SITE CONTACT: Steve Webber

SAMPLE MATRIX (# SAMPLES)	BACKGROUND SAMPLE (Y,N)	*SAMPLE PARAMETERS	**QA/QC REVIEW (Y,N)
SOIL _____	OFF SITE _____	_____	_____
GW <u>13</u>	UPGRADIENT <u>N</u>	Potable water standards and metals	<u>N</u>
SW _____	UPSTREAM _____	_____	_____

COMMENTS: The most recent analysis of Monroe Township Municipal Wells reveal that the inorganic mercury contamination that once plagued these public wells has decreased to within the limits of acceptability for potable water.

REVIEWER: Faranca

DATE: 4/15/88

*SPECIFY SAMPLE PARAMETERS: PP+40, HSL, TCL VO SCAN, METALS, ETC.
 **FORMAL QA/QC REVIEW BY NJDEP

TABULATION OF ANALYTICAL DATA FROM PUBLIC WATER SUPPLY

Supply Monroe MUA County Gloucester
 Municipality Monroe Township Date Collected 6/21/76
 Collected by D. Bianco Memo # W-76 Project # W-

BACTERIOLOGICAL ANALYSES: Coliform organisms determined by the membrane filter technique are reported in colonies per 100 ml. Chlorine residuals are reported in ppm.

Sample Number	Point of Collection	Coliform Organisms		Chlorine Residual	
		Fecal	Total	Free	Total
279866	Well # 8, 4 Raw water, Start Washington Ave Williamstown		0	TR	.35
279876	Run 5 min.		0		
279886	Run 10 min.		0		

PHYSICAL - CHEMICAL ANALYSES: Determinations are in ppm except color, odor, turbidity, and pH. Figures in parentheses are from the N. J. Potable Water Standards.

Sample Number	27986					Sample Number	27986
Color (10)						Arsenic	NEG
Odor (III)						Barium	NEG
Turbidity (5)						Cadmium	NEG
pH	4.9					Chromium +6	NEG
Alkalinity to pH 4	7					Copper	0.14
Nitrate as NO ₃ (30)	24					Cyanide	NEG
Chloride (250)						Lead	0.02
Total Dis. Solids (500)	110					Mercury	2.0 ppb
ABS/LAS (0.5)	NEG					Selenium	NEG
Total Hardness (150)	26					Silver	NEG
Total Iron (0.3)						Zinc	0.07
Manganese (0.05)							NEG
Sodium (50)							
Sulphate (250)							
Fluoride (1.5)	NEG						

Remarks: 279868 5 No facilities for monitoring 6 No facilities for fluoride C Operator report 1 date

TABULATION OF ANALYTICAL DATA FROM PUBLIC WATER SUPPLY

Source Monroe MUA County Gloucester
 Locality Monroe Twp Date Collected 6/21/76
 Collected by OTB Memo # W-76 Project # W-

TERIOLOGICAL ANALYSES: Coliform organisms determined by the membrane filter technique are reported in colonies per 100 ml.
 Chlorine residuals are reported in ppm.

Sample Number	Point of Collection	Coliform Organisms		Chlorine Residual	
		Fecal	Total	Free	Total
27981	Well # 5 New Water Street Water St Williamstown		0	TR	.35
27982	Run for 5 min.		0		
27983	Run for 10 min.		0		

YSICAL - CHEMICAL ANALYSES: Determinations are in ppm except color, odor, turbidity, and pH. Figures in parentheses are from the N. J. Potable Water Standards.

Sample Number	27981					Sample Number	27981
Color (10)						Arsenic	ME
Odor (MTT)						Barium	ME
Turbidity (5)						Cadmium	ME
pH	5.1					Chromium +6	ME
Alkalinity to pH 4	7					Copper	0.062
Nitrate as NO ₃ (30)	24					Cyanide	ME
Fluoride (250)						Lead	0.006
Total Dis. Solids (500)	112					Mercury	1.8ppm
BS/LAS (0.5)	ME					Selenium	ME
Total Hardness (150)	32					Silver	ME
Total Iron (0.3)						Zinc	0.09
Manganese (0.05)						Phenols	ME
Sodium (50)							
Sulfate (250)							
Fluoride (1.5)							

Remarks: 4 PH 08 5 No facilities for iron manganese
 facilities for fluoride Cooperator reports received and
 up to date

State of New Jersey
Department of Environmental Protection
Division of Water Resources

MEMO

TO Mr. Richard Bellis, Assistant Director, Monitoring, Surveillance
and Enforcement Element

FROM Mr. John Wilford, Assistant Director, Water Supply
and Flood Plain Management Element DATE November 3, 1976

SUBJECT Mercury Contamination of Ground Water - Monroe Township, Gloucester County

Attached is a copy of a memorandum-report which discloses mercury contamination of the water derived from Wells #4 and #5 of the Monroe Township Municipal Utilities Authority, Gloucester County. As is noted therein, based upon an initial, cursory investigation, personnel of the Bureau of Potable Water have been unable to determine the origin of the mercury. No manometers, or other instruments utilizing mercury, are in use at either of the wells.

I have advised the M.U.A. to immediately undertake the construction of a new well or wells to replace Wells #4 and #5 and, in the interim, to use Well #6 as the main production well, augmented as necessary by Well #5 to meet daily water demands. I have suggested that Well #4 be taken out of service and be retained only for standby purposes to meet a dire emergency such as a major fire.

On the basis of a specific test made on October 5, 1976, the mercury is in the inorganic form. This, fortunately, has less toxic potential than the alkyl (organic) form. However, the National Interim Primary Drinking Water Regulations promulgated by EPA pursuant to the Safe Drinking Water Act, which will become effective in June 1977, impose a maximum contaminant level for total mercury (0.002 mg/l), and make no differentiation between the inorganic and organic forms.

On the basis of the findings by the Bureau of Potable Water, it is requested that you will refer the matter to your Office of Special Services and have them conduct an intensive survey to determine, if possible, the origin of the mercury.

JW:bn

Enclosure

cc: Mr. Zelikson

11/10
Dave
Frank
// ASAP
KSS

Mr. Bell

Mr. Wilford

Messrs. Laffey and Vora

November 3, 1976

Mercury Contamination, Monroe Township Municipal Utilities Authority

The recently instituted program for sampling raw water sources throughout the State has disclosed a mercury contamination in two wells owned and operated by the Monroe Township Municipal Utilities Authority, Gloucester County, New Jersey.

The three operating wells of this system were sampled on June 21, 1976. Wells #4 and #5 showed mercury values of 2.0 ppb and 1.8 ppb respectively, while Well #6 yielded a negative result. The mercury contamination in Wells #4 and #5 was confirmed by samples taken on July 19, August 18, August 24, and October 18, 1976 with results ranging from 1.4 ppb to 6.4 ppb in Well #4 and from 0.8 to 2.8 ppb in Well #5. On October 5 and October 15, 1976 the water from Well #5 was negative for mercury, but Well #4 showed values ranging between 1.4 ppb and 2 ppb. The October 5 sample from Well #4 showed that the mercury was all of the inorganic type. System samples taken on August 18, August 24, October 10 and October 18 showed mercury values ranging from 1.0 ppb to 10.8 ppb. A tabulation of the analytical results is attached.

An inspection of the Monroe Township M.U.A. system was conducted on October 5, but no determination could be made for an immediate source of the mercury. Wells Nos. 4 and 5 are located respectively in Washington Avenue and Chestnut Streets, with an intervening distance of 1,200 feet.

Well #4 is the main production well for the system, having a reported yield of 800 gpm. It was constructed in 1952, taps the Cohansey Aquifer, and is cased to its full depth of 106 feet. Our records do not indicate whether or not the annular space is sealed. The formation log shows a clay layer between 35 feet and 44 feet.

Well #5 was constructed in 1967 and has a reported yield of 500 gpm. It taps the Bridgeton Tertiary Cohansey aquifer, and is 160 feet deep. The annular space between the casing and the drill hole is sealed to a depth of 127 feet. The formation log shows the presence of a clay layer between 58 feet and 63 feet, and a layer of hardpan between 84 feet and 89 feet.

A tour of the area surrounding Wells Nos. 4 and 5 failed to indicate any probable sources of mercury contamination with the exception of the Violet Packing Company located 0.5 miles west of Well #5. This company is engaged in the production of tomato sauces. It operates seasonally during the summer months and, during operations, produces about 200,000 gallons of wastewater

per day which is treated by pH adjustment, aeration and settling, prior to disposal either to the sanitary sewer or on to adjacent farmland. During the 1976 season their wastes were disposed of to the ground.

There are several sewing factories located in various parts of the Township, engaged in the manufacture of clothing, but these are believed to be all dry industries. There is a sanitary landfill located approximately one mile north of wells #4 and #5, but this is not known to receive chemical wastes.

A total of 24 public water supply wells in the area surrounding Monroe Township was sampled, all with negative results for mercury. A tabulation of these wells is also attached.

The results of the various samples taken show, conclusively, that the water from Wells #4 and #5 contains mercury, and that this constituent is also present in the delivered water. Current New Jersey Potable Water Standards and the 1962 P.H.S. Drinking Water Standards do not include a maximum contaminant level for mercury, though there is a "rule of thumb" maximum of 2.0 ppb. The recently-promulgated National Interim Primary Drinking Water Regulations, however, which will become effective in June 1977, include a maximum contaminant level of 2.0 ppb, for mercury, and though inorganic mercury is considered to be of far less toxic potential than organic mercury, the imposed value is for total mercury.

The operator of the system has been informed of these findings but, to date, they have not been officially brought to the attention of the Monroe Township M.U.A. It is, therefore, our recommendation that they be apprised of the situation so they can take immediate steps to develop alternate sources of water prior to the effective date of the National Interim Primary Regulations and thus avoid the appropriate public reporting requirements and the necessity for applying for an exemption or waiver in accordance with the requirements of the federal Safe Drinking Water Act. It is further recommended that this matter be referred to the Office of Special Services with a request that they will conduct an intensive search of the area to determine if there is a local industry that is discharging mercury contaminated wastes.

Respectfully submitted,

William Laffey

Bhupendra Vora

WL&BV:JW:bn
Attachments

MONROE TWP. MIA, GLOUCESTER COUNTY
TABULATION OF MERCURY RESULTS

SAMPLING POINT

DATE	WELL #4		WELL #5		WELL #6		SYSTEM - 372 Main St.
	RAW	DELIVERED	RAW	DELIVERED	RAW	DELIVERED	

MERCURY CONTENT IN ppb

6-21-76 [W-76]	2.0		1.8		Neg.	
7-19-76 [Memo #312]	<u>6.4</u>		<u>2.8</u>			
8-18-76 [Memo #338]	4.2		1.4			<u>10.8</u>
8-24-76 [Memo #358]	4.2		1.6		Neg.	1.0
10-5-76 [Routine Insp]	1.4 [total] 1.4* Neg.		Neg.	Neg.	Neg.	
10-15-76 Well #4 Rins. Well #5 Rins. For 12 hours and then took samples At 0, 1, 2, 4, 5 Hours [Memo #338]	Hr. 0 -1.6 1 -1.6 2 -1.6 4 -2.0 5 -1.4		Neg. Neg. Neg. Neg. Neg.			1.2
10-18-76 Well #5 Rins. Well #4 Rins. For 12 hours and then took samples At 0, 1, 2 4, 5 Hours [Memo #438].	Hr. 0 -6.0 1 -4.0 2 -3.4 4 -3.8 5 -3.9		1.0 1.0 1.0 0.8 1.0			1.6

* Inorganic Mercury.

243 WHITE HORSE PIKE

AUDUBON, N.J. 08106



Date of collection Dec. 16, 19 76 . Hour of Collection 8-9-10-11-12 P.M. . Analysis No. 127616-344
 Company Monroe MTA Address _____ Phone _____
 Sample taken from _____ By Jim Davis
 Condition of sample when drawn S.T.P.
 Collector's Remarks _____
 Date Delivered to Laboratory 12/16, 19 76 Time _____
 Condition of Sample upon arrival at Laboratory _____

CHEMICAL

TEST	REQ?	PRES. ABS.	QUAN.	METH.	TECH. IN.	TEST	REQ?	PRES. ABS.	QUAN.	METH.	TECH. IN.
Id						Mercury		less	than 0.001 mg/l		
calinity						Nitrate					
uminum						Nitrite					
monia						Odor					
enic						Oil & Grease					
D.O.						Pesticides					
omides						pH		8.1			
rbon Dioxide						Phenols					
dmium						Phos. Ortho					
l. Hardness						Phos. Tot.					
O.D.						Residue Tot.					
lorides						Residue Filtr.					
lorides OTA						Residue Non-Filtr.					
lorides Total						Set. Material					
l. Hydrocarbons						Sodium					
romate						Solids					
xpper						Spec. Cond.					
s. Oxygen						Sulfate					
s. Solids						Sulfide					
luorides						Sulfite					
ardness						Sus. Matter		358	mg/l		
ydrogen Sulfide						Toxicants					
on (Ferric)						Turbidity					
on (Ferrous)						T.D.S.					
eldahl N						Total Solids					
ad						Zinc					
agnesium											
anganese											
ationic (ABS&LAS)						Cationic					
ationic (sulfated)						Nonionic					

BACTERIOLOGICAL

TEST	AGG PLATE	DIL CELLS	TOTAL	METH.	TECH. IN.	TEST	AGG PLATE	DIL CELLS	TOTAL	METH.	TECH. IN.
otal Cells											
iform											
ecal Strep.											

Remarks _____

STROKA SIPPEL MASTELLER

& ASSOC., INC.

ENGINEERING & SURVEYING

ROBERT J. SIPPEL, L.S. PP
EARL H. MASTELLER, PE
NELSON L. HOOVER, L.S.
JOHN E. LORENZ

338 ROUTE 70, MARLTON, NEW JERSEY 08053
609.983.7260

December 23, 1976

Mr. Gustav Mihlebach, Superintendent
Monroe Municipal Utilities Authority
372 S. Main Street
Williamstown, New Jersey 08094

Re: N.J.D.E.P. Special Services
Potable Water Well Survey

Dear Gus:

Pursuant to your request on December 21, 1976, a field crew ran the necessary levels to determine the elevations of wells 4, 5, 6 and the Violet Packing Co. well. The bench marks used were New Jersey Geodetic Control Survey monuments.

Well #4 - Washington Avenue

Well house finish floor elevation 139.25

Top of concrete pump motor base elevation 141.14

Well #5 - Chestnut Street & Water Street

Well house finish floor elevation 165.26

Well #6 - Lake Avenue & Ellen Terrace

Top of concrete pump motor base elevation 144.30

Violet Packing Co. Well - Railroad Avenue

Top of flange of submersible well discharge piping elevation 155.39

Mr. G. Mihlebach, Superintendent

Page 2

December 23, 1976

If you should request any additional information or have any questions,
please do not hesitate to call me.

Very truly yours,

A handwritten signature in cursive script, appearing to read "Bob", written in dark ink.

Robert G. Volk

RGV:nl

MONROE MUNICIPAL UTILITIES AUTHORITY

372 SOUTH MAIN STREET

WILLIAMSTOWN, NEW JERSEY 08094

Dave

GUSTAV MIHLEBACH, Superintendent
Phone: 629-4400

December 27, 1976

Amanda M. Miles
Administrative Clerk
Phone 629-4400

1976 DEC 30 PM 2 39

RECEIVED
DEPT. OF ENVIRONMENTAL PROTECTION
DIVISION OF WATER RESOURCES

State of New Jersey
Dept. of Environmental Protection
Division Water Resources
P. O. Box 2809
Trenton, N. J. 08625 *David Shantart*
Attn: Mr. David Longstreet
Supervision, Hazardous Material Program

Re: Mercury Contaminate
Wells # 4, and # 5

3-1415

Dear Dave:

Per your request, enclosed are logs on Wells # 5, #6, and Violet Packing Cannery; also a letter from our engineering firm stating the elevations of the four (4) wells.

An analysis for Mercury performed by Quality Control Lab on the sewage treatment plant effluent is also enclosed.

Very truly yours,

Monroe Municipal Utilities Authority

Gustav Mihlebach

Gustav Mihlebach
Superintendent

GM:am

encl: 4

cc: Mr. Volk
file

588 3400

Bic

Chem-25
Sept. 75

NEW JERSEY STATE DEPARTMENT OF HEALTH
STREAM OR WASTEWATER ANALYSIS

Time & Date Received _____
By Labs _____
Lab. No. _____

FIELD INFORMATION

PLEASE TYPE OR PRINT
WITH BALLPOINT PEN

Date of Collection 2-9-1977

Hour 12:00 A.M. P.M.

Sample No. 18582

Composite Period CRP Interval

Collected by W. J. ...

Residual Chlorine:
Immediate

Municipality W. J. ...

Plant VIOLET PACKING CO.

Developed

Stream

Flow Rate

Location RAILROAD AVE

Temperature

Description and Remarks: WELL

ITEMS CIRCLED BELOW ARE UNSATISFACTORY

Dilutions Requested
(Bacteriological)

10	1	10 ⁻¹	10 ⁻²	10 ⁻³	10 ⁻⁴	10 ⁻⁵	10 ⁻⁶

LABORATORY RESULTS
BACTERIOLOGICAL

Coliform MPN/100 ml. (Confirmed Test); Fecal Coliform MPN/100 ml.

Fecal Streptococci:MPN/100 ml. Other

CHEMICAL AND PHYSICAL ANALYSES (mgs./liter, unless otherwise noted)

Color (units)	Chloride	Sulfate	Other Determinations
Odor (cold)	Suspended Solids	Grease & Oil	<u>MERCURY NEG</u>
Turbidity (units)	Ash	Cyanide	
pH	Total Solids	Chromium Total	
Acidity to pH 4	Ash	Chromium Hex.	
Alkalinity to pH 4	Total PO ₄	Ortho - PO ₄	
Nitrite N	MBAS	Copper	
Nitrate N	Phenols	Lead	
Ammonia N	COD	Arsenic	
Total Kjel. N	Iron	Zinc	

BIOCHEMICAL OXYGEN DEMAND (mgs./liter)

Field D.O.		Lab. D.O.			Seed Required:								Yes	No		
Sample Conc. %	PLEASE CIRCLE	0.1	0.2	0.5	1.0	2.0	5.0	10	25	50	75	100				
BOD ₅																

NEW JERSEY STATE DEPARTMENT OF HEALTH
STREAM OR WASTEWATER ANALYSIS

12
Time & Date Received 8/11/77
By Labs Th386
Lab. No. FS

FIELD INFORMATION

PLEASE TYPE OR PRINT
WITH BALLPOINT PEN

Date of Collection 8-11- 1977

Hour 10:15 A.M. ☒ P.M.

Composite Period GRAB Interval

Collected by MENNEL & PATTERSON
Residual Chlorine:

Immediate

Developed

Flow Rate

Temperature

Sample No. 20636

Municipality MONROE TWP

Plant VIOLET PACKING

Stream

Location

Description and Remarks: POND

RECEIVED
SEP 16 1977

ITEMS CIRCLED BELOW ARE UNSATISFACTORY

Dilutions Requested
(Bacteriological)

10	1	10-1	10-2	10-3	10-4	10-5	10-6
----	---	------	------	------	------	------	------

LABORATORY RESULTS
BACTERIOLOGICAL

Coliform MPN/100 ml. 24000+ (Confirmed Test) Fecal Coliform MPN/100 ml. 3500.
Fecal Streptococci: MPN/100 ml. 2400+ Other

CHEMICAL AND PHYSICAL ANALYSES (mgs./liter, unless otherwise noted)

<input checked="" type="checkbox"/> Color (units) <u>ND</u>	<input checked="" type="checkbox"/> Chloride <u>64</u>	<input checked="" type="checkbox"/> Sulfate <u>42</u>	Other Determinations
<input checked="" type="checkbox"/> Odor (cold) <u>VD</u>	<input checked="" type="checkbox"/> Suspended Solids <u>66</u>	<input checked="" type="checkbox"/> Grease & Oil <u>104.0</u>	<input checked="" type="checkbox"/> Sodium <u>310.</u>
<input checked="" type="checkbox"/> Turbidity (units) <u>50</u>	<input checked="" type="checkbox"/> Ash <u>24</u>	<input checked="" type="checkbox"/> Cyanide	<input checked="" type="checkbox"/> Potassium <u>47.</u>
<input checked="" type="checkbox"/> pH <u>9.5</u>	<input checked="" type="checkbox"/> Total Solids <u>1180</u>	<input checked="" type="checkbox"/> Chromium Total <u>0.015</u>	<input checked="" type="checkbox"/> Cadmium
<input checked="" type="checkbox"/> Acidity to pH 4	<input checked="" type="checkbox"/> Ash <u>904</u>	<input checked="" type="checkbox"/> Chromium Hex. <u>ND</u>	<u>0.002</u>
<input checked="" type="checkbox"/> Alkalinity to pH 4	<input checked="" type="checkbox"/> Total PO ₄ <u>6.9</u>	<input checked="" type="checkbox"/> Ortho - PO ₄	
<input checked="" type="checkbox"/> Nitrite N <u>0.055</u>	<input checked="" type="checkbox"/> MBAS <u><0.3</u>	<input checked="" type="checkbox"/> Copper	
<input checked="" type="checkbox"/> Nitrate N <u>ND</u>	<input checked="" type="checkbox"/> Phenols	<input checked="" type="checkbox"/> Lead	
<input checked="" type="checkbox"/> Ammonia N <u>4.0</u>	<input checked="" type="checkbox"/> COD <u>360</u>	<input checked="" type="checkbox"/> Arsenic	
<input checked="" type="checkbox"/> Total Kjel. N <u>17.9</u>	<input checked="" type="checkbox"/> Iron <u>2.8</u>	<input checked="" type="checkbox"/> Zinc <u>0.48</u>	

DIVISION OF LABORATORIES
ANALYSIS COMPLETED
SEP 13 1977

BIOCHEMICAL OXYGEN DEMAND (mgs./liter)

REPORT SUBMITTED

Field D.O.		Lab. D.O. 0			Seed Required: Yes No							
Sample Conc. %	PLEASE CIRCLE	0.1	0.2	0.5	1.0	2.0	5.0	10	25	50	75	100
BOD5			<-		<-		137					

Chem-25
Sept. 75

JERSEY STATE DEPARTMENT OF HEALTH
STREAM OR WASTEWATER ANALYSIS

Time & Date Received 8/11/77
By Labs
Lab. No. TH 385

FIELD INFORMATION

PLEASE TYPE OR PRINT
WITH BALLPOINT PEN

Date of Collection 8-11 1977

Hour 11:10 A.M. X P.M.

Sample No. 20634

Composite Period GRAB Interval

Collected by MENNEL & PATTERSON

Residual Chlorine:

Immediate

Municipality MONROE TWP

Plant VIOLET PAVING

Developed

Stream

Flow Rate

Location

Temperature

Description and Remarks: PH ADJUSTED

AND SCREENED (EFFLUENT TO GC SA)

ITEMS CIRCLED BELOW ARE UNSATISFACTORY

Dilutions Requested
(Bacteriological)

10	1	10 ⁻¹	10 ⁻²	10 ⁻³	10 ⁻⁴	10 ⁻⁵	10 ⁻⁶

LABORATORY RESULTS
BACTERIOLOGICAL

Coliform MPN/100 ml. 24,000+ (Confirmed Test) (Fecal Coliform MPN/100 ml. 24,000+)

Fecal Streptococci: MPN/100 ml. 2400+ Other

SEP 16 1977

CHEMICAL AND PHYSICAL ANALYSES (mgs./liter, unless otherwise noted)

State of New Jersey
Dept. Environmental Protection
Division Water Resources

Color (units) <u>ND</u>	Chloride <u>15</u>	Sulfate <u>85</u>	Other Determinations
Odor (cold) <u>TV D</u>	Suspended Solids <u>520</u>	Grease & Oil <u>67.4</u>	Sodium <u>22.</u>
Turbidity (units) <u>200</u>	Ash <u>212</u>	Cyanide	Potassium <u>60</u>
pH <u>4.5</u>	Total Solids <u>1216</u>	Chromium Total <u>9.005</u>	Cadmium <u>0.003</u>
Acidity to pH 4	Ash <u>488</u>	Chromium Hex. <u>ND</u>	
Alkalinity to pH 4	Total PO ₄ <u>10.0</u>	Ortho - PO ₄	
Nitrite N <u>0.025</u>	MBAS <u>< 0.3</u>	Copper	DIVISION OF LABORATORIES
Nitrate N <u>3.5</u>	Phenols	Lead	ANALYSIS COMPLETED
Ammonia N <u>11.1</u>	COD <u>1240</u>	Arsenic	SEP 12 1977
Total Kj. N <u>39.8</u>	Iron <u>8.0</u>	Zinc <u>0.75</u>	REPORT SUBMITTED

BIOCHEMICAL OXYGEN DEMAND (mgs./liter)

Field D.O.		Lab. D.O.		Seed Required:							
		0		Yes No							
Sample Conc. %	PLEASE CIRCLE	0.1	0.2 0.5	1.0	2.0	5.0	10	25	50	75	100
BOD ₅			< -	651	> -						

Geraghty & Miller, Inc.

CONSULTING GROUND-WATER GEOLOGISTS AND HYDROLOGISTS

Executive Offices: Water Research Building
44 Sintsink Drive East
Port Washington, New York 11050
Phone 516 843-6760 Cable WATER

Mr. Gustav Mihlebach
Monroe Utilities Authority
372 S. Main Street
Williamstown, New Jersey


Dear Sir:

Enclosed are the water quality analyses of the samples collected from your wells in January. This work was done as a part of the Delaware Valley Regional Planning Commission study of ground- and surface-water contamination being conducted in Gloucester, Camden, Burlington and Mercer Counties.

Thank you for your cooperation.

Sincerely,

GERAGHTY & MILLER, INC.



Paul Roux

PR:am
Enclosure



PENN ENVIRONMENTAL CONSULTANTS, INC.
FORT PITT PROFESSIONAL BUILDING
1517 WOODRUFF STREET
PITTSBURGH, PA. 15220
412-381-1133

WATER ANALYSIS REPORT

CLIENT		PEC PROJECT NO.	
SAMPLE SOURCE TIME AND DATE		253-3338	
DATE RECEIVED	CHEMIST	SAMPLE NO.	
2-17-77	RM	25335	

BASIC PARAMETERS

NUTRIENTS

ORGANICS

pH-Units	4.9	NO ₂ -N mg/l		TOC mg/l	
ALK-TOT mg/l as CaCO ₃	12	NO ₃ -N mg/l	3.1	COD mg/l	
ACID mg/l as CaCO ₃		NH ₃ -N mg/l		BOD ₅ mg/l	
pH ₈ HOT mg/l as CaCO ₃		PO ₄ -P ortho mg/l		CN-TOT mg/l	
COLOR Pt-Co Units		PO ₄ -P total mg/l	.03	CN-AMENABLE mg/l	
TURBIDITY JTU		TKN mg/l		OILS-EXT mg/l	
SO ₄ mg/l	<1	METALS		PHENOL mg/l	
SP COND. μmhos/cm		Al mg/l		MBAS mg/l	
HARD-T mg/l		Cd mg/l	<.01	BACTERIOLOGICAL	
Ca mg/l	24	Cr mg/l	<.01	TOT-COLIFORM colonies/100 ml	
Mg mg/l	7.0	Cu mg/l	.17	FECAL-COLIFORM colonies/100 ml	
Cl mg/l	13	Fe-TOT mg/l	.16	FECAL STREP colonies/100 ml	
F mg/l		Fe-DISS mg/l		ADDITIONAL	
SOLIDS		K mg/l	2.0	Co mg/l	<.01
TOTAL mg/l @ 103°		Mn mg/l		Hg mg/l	.004
TOT VOL mg/l @ 550°		Na mg/l	7.1	As mg/l	<.03
SUSP mg/l @ 103°		Ni mg/l	<.03		
SUSP-VOL mg/l @ 550°		Pb mg/l	<.03		
DISS mg/l @ 180°	95	Si mg/l			
SETTLE ml/l		Zn mg/l	.20		

REMARKS:

B15



PENN ENVIRONMENTAL CONSULTANTS, INC.
FORT PITT PROFESSIONAL BUILDING
1517 WOODRUFF STREET
PITTSBURGH, PA. 15220
412-381-1133

WATER ANALYSIS REPORT

CLIENT												PEC PROJECT NO.																							
SAMPLE SOURCE TIME AND DATE												253-3338																							
DATE RECEIVED												SAMPLE NO.																							
2-17-77												25336																							
CHEMIST												NAME OF SAMPLE																							
RM																																			
BASIC PARAMETERS												NUTRIENTS												ORGANICS											
pH-Units												NO ₂ -N mg/l												TOC mg/l											
4.8																																			
ALK-TOT mg/l as CaCO ₃												NO ₃ -N mg/l												COD mg/l											
1.2												2.7																							
ACID mg/l as CaCO ₃												NH ₃ -N mg/l												BOD ₅ mg/l											
pH _s HOT mg/l as CaCO ₃												PO ₄ -P ortho mg/l												CN-TOT mg/l											
COLOR Pt-Co Units												PO ₄ -P total mg/l												CN-AMENABLE mg/l											
												0.2																							
TURBIDITY JTU												TKN mg/l												OILS-EXT mg/l											
SO ₄ mg/l												METALS												PHENOL mg/l											
1.2																																			
SP COND. μmhos/cm												Al mg/l												MBAS mg/l											
HARD-T mg/l												Cd mg/l												BACTERIOLOGICAL											
												<.01																							
Ca mg/l												Cr mg/l												TOT-COLIFORM colonies/100 ml											
3.3												<.01																							
Mg mg/l												Cu mg/l												FECAL-COLIFORM colonies/100 ml											
3.4												<.01																							
Cl mg/l												Fe-TOT mg/l												FECAL STREP colonies/100 ml											
16												1.3																							
F mg/l												Fe-DISS mg/l												ADDITIONAL											
SOLIDS												K mg/l												Co mg/l											
																								2.4											
TOTAL mg/l @ 103°												Mn mg/l												Mg mg/l											
																								1.0											
TOT VOL mg/l @ 550°												Na mg/l												9.8											
																								2.0											
SUSP mg/l @ 103°												Ni mg/l												<.03											
SUSP-VOL mg/l @ 550°												Pb mg/l												<.03											
DISS mg/l @ 180°												Si mg/l																							
76																																			
SETTLE ml/l												Zn mg/l												<.01											

REMARKS:

B11

Supply Gloucester Municipal County Gloucester
 Municipality Municipal Corp Date Collected 2/4/77
 Collected by Bruno Memo # 5601 Project # W-

BACTERIOLOGICAL ANALYSES: Coliform organisms determined by the membrane filter technique are reported in colonies per 100 ml. Chlorine residuals are reported in ppm.

Sample Number	Point of Collection	Coliform Organisms		Chlorine Residual	
		Fecal	Total	Free	Total
32003	Violet Jackson Co. Raw water 123 Railroad Ave				
32004	Well #5 - Raw water Water St				
32005	Well #4 - Raw water Washington Ave				

PHYSICAL - CHEMICAL ANALYSES: Determinations are in ppm except color, odor, turbidity, and pH. Figures in parentheses are from the N. J. Potable Water Standards and/or National Interim Primary Regulations.

Sample Number	32005	32004	Sample Number	32003
Color (10)			Arsenic (0.05)	
Odor (III)			Barium (1.0)	
Turbidity (5)			Cadmium (0.010)	
			Chromium ⁺⁶ (0.05)	
Alkalinity to pH 4			Copper (1.0)	
Nitrate as NO ₃ (45)			Cyanide (0.20)	
Fluoride (250)			Lead (0.05)	
Total Dis. Solids (500)			Mercury (0.002)	ND
SS/LAS (0.5)			Selenium (0.01)	
Total Hardness (150)			Silver (0.05)	
Total Iron (0.3)			Phenol (0.001)	
Manganese (0.05)			Endrin (0.0002)	
Aluminum (50)			Lindane (0.004)	
Phosphate (250)			Methoxychlor (0.1)	
Boride (1.5)			Toxaphene (0.005)	
Copper (5.0)			2,4-D (0.1)	
			Silvex (0.01)	

RECEIVED

MAR 24 1977

GLoucester CO
DEPT. OF HEALTH

MEMORANDUM

STATE OF NEW JERSEY
DEPARTMENT OF ENVIRONMENTAL PROTECTION

TO: Robert L. Vincent thru Joseph M. Mikulka

FROM: William J. Mendel, Jr. and Paul F. Tomkavage

SUBJECT: Violet Packing Company, Monroe Township
Gloucester County

DATE: March 15, 1977

On February 8, 1977 we conducted an investigation of the Violet Packing Company. During this investigation we met with Mr. James V. Sclafani, the President of the Company, who answered our questions and showed us around the Plant. He explained that their principal raw material is tomatoes. The tomatoes as they come in are washed and then cooked and processed into tomato sauce. The wash water and the process wastewater are treated in their pre-treatment plant before being discharged into the Monroe Township Sewerage System. The firm operates and discharges only during the months of July, August and September. The discharge is restricted to the hours of 12:00 a.m. to 4:00 a.m. The pre-treatment system consists of a bar screen, a tank for pH adjustment, a tank for the addition of alum, three primary settling lagoons, an aeration lagoon and a final settling lagoon. The primary settling lagoons have rubber liners but the liners are torn and have holes in numerous places. The aeration lagoon and final settling lagoon are unlined. Mr. Sclafani informed us that he is having problems with vandalism at the plant.

After our inspection of the Violet Packing Company we met with Mr. Gustav Mihlebach, Superintendent for the Monroe Municipal Utilities Authority. He informed us that although Violet Packing is tied into the Municipal System, they did not discharge into the system during the 1976 season, but had been discharging to a field behind their plant. This information was based on his knowledge of the Monroe M.U.A. treatment plant's flows. Mr. Sclafani, however, informed us that the only time he discharged to the field behind his plant, was when the pump motors burned out.

At the request of Richard Dalton, of Special Services, we took a sample of Violet Packing's well water. The requested parameter for this sample was for Mercury. The result of this analysis was negative.

A39:MC

MEMORANDUM

STATE OF NEW JERSEY
DEPARTMENT OF ENVIRONMENTAL PROTECTION

TO: Richard Dalton

FROM: Robert L. Vincent *RLV*

SUBJECT: Violet Packing Company, Monroe Township
Gloucester County

MAK 17 1977
DATE: _____

On February 8, 1977 Basin Personnel inspected the above referenced facility. This inspection revealed the existence of two unlined lagoons and three lined lagoons, which are in a state of disrepair, for the pretreatment of food processing wastewater prior to discharge into the municipal system. The plant is "down" now and use of these facilities is not expected to be resumed until processing starts again sometime early this summer.

I would appreciate comment from you concerning the use of the unlined lagoons for this type of wastewater.

A39:MC

M. M. U. A. Water Supply System

- 11-3-76 Ltr from N.J.D.E.P. Mr. Wilford
Re: Raw Water Tests on #4 and #5 Wells
Mercury levels
- 11-12-76 Meeting with Mr. Menore
Re: New Well, Mercury Content
- Meeting with Auditor Mr. Hightlinger
Re: Financial Condition of M.M.U.A.
General Fund
- 11-16-76 Meeting with John Neider, Ernie Anderson, Harry Alsentger & C. Schultes
Re: Cost Figures New 1000 GPM Well
Discussed Mercury content
- 11-18-76 Grab samples - Raw Water from Wells #4 and #5 delivered to
Technological Services, Camden
Quality Lab. Audubon
Re: Tests on Mercury
Lead
Zinc
Chromium
Copper
- 11-24-76 Ltr to N.J.D.E.P. Mr. John Wilford
Re: Progress and steps taken to date regarding
Mercury levels
- 11-24-76 Called Joe Miller N.J.D.E.P. Water Resources (Pollution)
Re: Steps taken on Mercury

11-29-76 Meeting with our Engineering Firm Bob Volk Earl Masteller
Re: Mercury in Wells and Budget Figures

12-1-76 Meeting with Mr. Knorr
Re: Progress report on Wells

Lusby Control Laboratory, Audubon

Test Results	# 4	# 5	taken on 11-18-76
Copper	less than 0.5	0.5	
Lead	0.04	0.10 X	
Zinc	0.12	0.26	
Chromium	less than 0.03	0.03	
Mercury	<u>0.0046</u>	0.001	

12-3-76 Technological Resources, Inc. Camden

Test Results	# 4	# 5	taken on 11-18-76
Copper	0.14	0.01	
Lead	< 0.005	0.005	
Zinc	0.05	0.005	
Chromium	< 0.02	0.02	
Mercury	<u>0.0035</u>	<u>0.0021</u>	

12-10-76 Meeting with Gus Schuller Jr., Don Tanguer, Bob Volk at Schuller
Re: Mercury in Williamstown area

Plot Wells of various depths in Area
Map

Locate the massive concentration
Test wells

Can new well be located at base of
new elevated Tower

Cohansey Strata - Sand

609) 468-3396

VAL ASSOCIATES

P.O. Box 162

Plating Analysis & Consulting
For Electronics Industry
Water, Air & Soil Analysis

PHILIP V. DATZ, JR.
Chemist

*Gloucester
Mantua NJ VA*
748 Ridge Drive Road
Mantua, New Jersey 08051

June 9, 1978

Water Analysis Samples

Location - *Tower*
~~Hubert Boulevard~~

5/26/78 Sample Taken

Mercury Filtered - .4 ppb

5/26/78 Sample Taken

Mercury Unfiltered - .4 ppb

Well # 4

5/8/78 Sample Taken

Mercury - .35 ppb

5/10/78 Sample Taken (Well # 4)

Mercury - 1.6 ppb

June 75

ROUTINE INSPECTION REPORT - PUBLIC WATER SUPPLY

PWS ID No. 0811002 Page 1

1980

Water Supply Purveyor

Monroe Municipal Utilities Authority

Date

March 20, 1980

Municipality

Monroe Township

County

Gloucester

Mailing Address

372 South Main Street, Williamstown, New Jersey 08094

Administrator

Mr. J.V. Dinovi, Chairman

Lic. Operator: T

Gustav Mihlebach
609-629-5300 (plant)

W

same

Business Phones:

609-629-4400

609-589-2976 (home)

Person Interviewed

Mr. Gustav Mihlebach

Position

Superintendent

1. Source: Location, Description, Capacity (mgd) Washington Ave. Well # 4-0.72 mgd (for emergency use only), Chestnut Street & Water Street Well # 5-0.81 mgd, Ellen Terrace & Lake Ave. Well # 6-0.60 mgd, corkery Lane Well # 7-1.14 mgd.

Est. Total Effective Cap. (mgd) 3.27

2. Treatment: Wells # 4, 5, & 6-Chlorination (gas) and pH adjustment with Caustic Soda. Well # 7-chlorination (gas) and pH adjustment with lime.

Est. Total Effective Cap. (mgd) 3.27

3. Finished Water Storage: Description, Capacity (MG) Chestnut & Water St. elevated tank-0.15 mg, Herbert Blvd. elevated tank-0.30 mg, Corkery Lane & Black Horse Pike elevated tank-1.0 mg
Est. Total Effective (MG) 1.45

4. Auxiliary Power Well # 4-gasoline engine direct drive, Well # 5-diesel engine, direct drive, Well # 7-diesel generator for well & treatment. Total 2.67 mgd

5. Emergency Interconnections none

Max Day 1.63 (10/25/79) Min. Day .124 (1/31/80)

6. Plant Delivered (mgd): Maximum 1.022 (7/79) Minimum .520 (3/80) Annual Average .801

Bulk Purchase From none mgdBulk Sale To none mgd

7. Number of Services 2,699 % Metered 100 Total Est. Population Served 9,400

8. Municipalities served and est. services in each Monroe Twp

9. Distribution Mains: Size 2 to 12 ins. Pressures 40 to 50 psi. Fire Hydrants yes

10. Water restrictions none

11. New Construction & Project # none

12. Plant Chemical-Physical Analysis (type, freq.) Chlorine residuals twice a day; pH is checked daily

13. Monthly bacteriological sampling of system by purveyor: No. required 10 No. taken 10

Name of Laboratory Quality Control Laboratory, Audubon, N.J.

Monroe Municipal Utilities Authority

372 South Main Street
Williamstown, New Jersey 08094

Gustav Mihlebach
Superintendent
Phone: 629-4400

RECEIVED

Jacqueline Schoenewald
Office Manager
Phone: 629-4400

AUG 7-80

August 5, 1980

STATE DEPT. OF ENVIRONMENTAL PROTECTION
BUREAU OF POTABLE WATER

State of New Jersey
Department of Environmental Protection
Division of Water Resources
P.O. Box CN-029
Trenton, New Jersey 08625

Attention: Mr. Daniel S. Mozer
Senior Environmental Engineer

RE: Inspection Report
March 20, 1980

Dear Mr. Mozer:

In the Inspection report - under number 14 deficiencies noted:


- (1) Well #4 blow off has been screened to prevent entry of any foreign matter.
- (2) Well #4 is not being used, the monthly report to N.J. D.E.P. is marked off line.

Under number 17 Immediate requirements:

- (1) Well #4 is Off Line.
- (2) Well #5 is being used to meet the heavy daily demand.
- (3) We are increasing the percentage of lime in the slurry solution to adjust the pH.

Very truly yours,

MONROE MUNICIPAL UTILITIES AUTHORITY



GUSTAV MIHLEBACH
Superintendent

GM/cdf
cc: File

TABULAR ANALYTICAL DATA FROM PUBLIC UTILITY SUPPLY
MONROE MUNICIPAL UTILITIES AUTHORITY

County GLoucester
 Municipality MONROE TWP.
 Date Collected 3-13-82
 Collected by Brian Keene Memo # 82-67 Project # W

BACTERIOLOGICAL ANALYSES: Coliform organisms determined by the membrane filter technique are reported in colonies per 100 ml. Chlorine residuals are reported in ppm.

Sample Number	Point of Collection	Coliform Organisms		Chlorine Residual	
		Fecal	Total	Free	Total
06384	WELL #6, LAKE AVE (RAW WATER)	9:45AM		0	0
06385	WELL #7, CORKERY LN.	10:20		↓	↓
06386	TEST WELL, AVERY DR.	11:00		↓	↓
06387	WELL #4, WASHINGTON ST.	11:40AM		↓	↓

PHYSICAL - CHEMICAL ANALYSES: Determinations are in ppm except color, odor, turbidity, and pH. Figures in parentheses are from the N. J. Potable Water Standards and/or National Interim Primary Regulations.

Sample Number		06384	Sample Number	06385	06386	06387
Color (10)			Arsenic (0.05)			
Odor (III)			Barium (1.0)			
Turbidity (5)			Cadmium (0.010)			
pH			Chromium ⁺⁶ (0.05)			
Alkalinity to pH 4			Copper (1.0)			
Nitrate as NO ₃ (45)			Cyanide (0.20)			
Chloride (250)			Lead (0.05)			
Total Dis. Solids (500)		10.0007	Mercury (0.002)	10.0005 K	10.0012	10.0044
ABS/LAS (0.5)			Selenium (0.01)			
Total Hardness (150)			Silver (0.05)			
Total Iron (0.3)			Phenol (0.001)			
Manganese (0.05)			Endrin (0.0002)			
Boron (100)			Lindane (0.004)			
Sulphate (250)			Methoxychlor (0.1)			
Fluoride (2.0)			Toxaphene (0.005)			
Zinc (5.0)			2,4-D (0.1)			
			Silvex (0.01)			

RECEIVED

MAY 3 1982

Remarks WELL #5 OUT OF SERVICE AT TIME OF SAMPLING
WELL #4 PUMPED TO WASTE 2 HRS PRIOR TO SAMPLING

* Exceeds standard

B27

Monroe Municipal Utilities Authority

372 South Main Street
Williamstown, New Jersey 08094

Gloucester Co.
(Potable Water)
RECEIVED

MAR 17 1982

N.J. STATE DEPT. OF ENVIRONMENTAL PROTECTION
BUREAU OF POTABLE WATER
Jacqueline Schoenewald

Executive Director

Phone: 629-4400

Gustav Mihlebach

Superintendent

Phone: 629-4400

March 15, 1982

N.J. State Dept. Environmental Protection
P.O. Box 2809
Trenton, New Jersey

Attention: Mr. Dan Mozer

RE: Groundwater Quality

Dear Dan:

To confirm our telephone conversation on Friday (3/12/82, 3:30 P.M.), I would like to mention the subjects discussed.

#4 Well, whether it was abandoned, capped, sealed, amount of Mercury in the water, gasoline seepage from the old Petes' Getty Gas Station and is it being used. The Well is off line, however, I pump it overboard to keep it fresh, just in case of an emergency, such as a fire. A new chlorine booster pump will be installed in the next few weeks.


#5 Well, that it is supposed to be a marginal well and only used in an emergency because the Mercury Tests years back showed 1.5 ppb, still under the E.P.A. standard of 2 ppb. The Well is now pulled for general maintenance and the repair work will be bidded within 2 weeks.

Groundwater Quality in New Jersey. An inspection of Toxic Contaminants, March 1981 by Robert K. Tucker, PhD.

I asked whether the laboratory tests performed in the aforementioned study reflected any serious problems with our wells and the statement given, that I could make to the M.M.U.A. at its meeting on Tuesday, March 16, 1982 is "The quality of our potable water shows no significant amount of pesticides, nothing to be alarmed over."

Mercury tests had been performed by Quality Control Laboratory 2/1/82 at #5 Well, Test Well on Avery Drive and #7 Well and the results were less than 0.002/mg/l at all three locations. Also the State may be down in the near future to perform an inspection.

Very truly yours,


Gustav Mihlebach

GM/cdf
cc: File

Bas

TABULATION OF ANALYTICAL DATA FROM PUBLIC WATER SUPPLY

Supply MONROE MUNICIPAL UTILITIES AUTHORITY County GLoucester
 Municipality MONROE TWP. Date Collected 3-23-82
 Collected by Brian Keen APR 26 1982 Memo # 82-67 Project # W. _____

BACTERIOLOGICAL ANALYSES: Coliform organisms determined by the membrane filter technique are reported in colonies per 100 ml.
 Chlorine residuals are reported in ppm.

Sample Number	Point of Collection	Coliform Organisms		Chlorine Residual	
		Fecal	Total	Free	Total
06384	WELL #6 LAKE AVE (RAW WATER)	9:45AM		0	0
06385	WELL #7, CORKERY LN.	10:20			
06386	TEST WELL, AVERY DR.	11:00			
06387	WELL #4 WASHINGTON ST.	11:40AM			

PHYSICAL - CHEMICAL ANALYSES: Determinations are in ppm except color, odor, turbidity, and pH. Figures in parentheses are from the N. J. Potable Water Standards and/or National Interim Primary Regulations.

Sample Number		06384	Sample Number	06385	06386	06387
Color (10)			Arsenic (0.05)			
Odor (III)			Barium (1.0)			
Turbidity (5)			Cadmium (0.010)			
pH			Chromium ⁺⁶ (0.05)			
Alkalinity to pH 4			Copper (1.0)			
Nitrate as NO ₃ (45)			Cyanide (0.20)			
Chloride (250)			Lead (0.05)			
Total Dis. Solids (500)		10.0007	Mercury (0.002)	10.0005 K	10.0012	* 0.0044
ABSTLAS (0.5)			Selenium (0.01)			
Total Hardness (150)			Silver (0.05)			
Total Iron (0.3)			Phenol (0.001)			
Manganese (0.05)			Endrin (0.0002)			
Sodium (50)			Lindane (0.004)			
Sulphate (250)			Methoxychlor (0.1)			
Fluoride (2.0)			Toxaphene (0.005)			
Zinc (5.0)			2,4-D (0.1)			
			Silvex (0.01)			

REPORT SUBMITTED

APR 20 1982

NJDOH Environmental
Chemistry Laboratory

Remarks WELL #5 OUT OF SERVICE AT TIME OF SAMPLING
WELL #4 PUMPED TO WASTE 2 HRS PRIOR TO SAMPLING

PLEASE TYPE OR PRINT
WITH BALLPOINT PEN

MUNICIPALITY	COUNTY	STREET
Monroe	St. Charles	Grandmasta
FACILITY	LOCATION	
Stormwater	Pte 322 & Washington St	
REPRESENTATIVE	TITLE	COLL NAME
		Picciotto
REMARKS		
Typical stormwater runoff of storm water from Mill Ave. area		

BACT. LAB NO. _____
DATE REC'D. _____
BOTTLE NO. 1404
DATE REC'D _____
STREET ENT. _____
READ _____

Station Identification Number

YR. MO. DAY : HOUR

Sample No.

SC, 820682 1355, (1) P8,

FIELD ANALYSIS

- ☐ Water Temp. °C. (2) P00010.
- ☐ D.O. - Winkler (3) P00300.
- ☐ D.O. - Probe (4) P00299.
- ☐ pH (Field) (5) P00400.
- ☐ Sample Depth-ft. (6) P00003.
- ☐ Stream Flow-CFS (7) P00061.
- ☐ Gate Height-ft. (8) P00065.
- ☐ Spec. Cond. @ 25°C (9) P00095.
- ☒ Salinity ‰ (10) P00480.
- ☐ Tide Stage (11) P70211.

[illegible]

CONDITION CODES

- ☐ Weather Conditions (12) P00041,
- ☐ Flow Severity (13) P01351,
- ☐ _____ Severity (14) P013_
- ☐ _____ Severity (15) P013_

--	--	--	--

NUTRIENTS

LEVEL ☐ HIGH ☐ LOW

- NO₂ - N (16) P00615,
NO₂ + NO₃ - N (17) P00630,
H₃ - N (18) P00610,
t. Kjeldahl N (19) P00625,
P ☐ (20) P70507,
PO₄ ☐ (21) P00660,
orus- ☐ (22) P00665,
DA ☐ (23) P00650.

BACTERIOLOGICAL - DILUTIONS (REQUESTED)

- | | | | | | | | | |
|----------------|----|---|----|----|----|----|----|----|
| Fecal Coliform | 0 | 1 | -1 | -2 | -3 | -4 | -5 | -6 |
| Total Coliform | 10 | 1 | 10 | 10 | 10 | 10 | 10 | 10 |

Fecal Streptococci	0	1	-1	-2	-3	-4	-5	-6
	10	1	10	10	10	10	10	10

Fecal coli ☐ MPN (24) P31615 ☐ MF (25) P31613

#100 ml

☐ Fecal Strept

MPN/100ml (26) P31677

☐ Tot coli

MPN/100 ml (27) P31505

BIOCHEMICAL OXYGEN DEMAND

INITIAL D.O. (lab.) _____ SAMPLE _____

SEED YES ☐ NO ☐

CONC. %

BOD__

- ☐ BOD 5-DAY(28) P310,
6-DAY(29) P312,
- ☐ COD (30) P340,
- ☐ TOC (31) P00680,

- ☐ Color Pt - Cou (32)P00080,
- ☐ Turbidity (33)P00076,
- ☐ Suspended Solids(34)P00530,
- ☐ Suspended Solids(35)P00540,
Ash
- ☐ Tot. Solids (36)P00500,
- ☐ Tot. Solids - Ash (37)P00510,
- ☐ Tot. Dissolved Solids (TDS) (38)P70300,

[illegible]

- | | | |
|---|------|---------|
| <input type="checkbox"/> pH (LAB) | (39) | P00403, |
| <input type="checkbox"/> Alkalinity
as CaCO ₃ | (40) | P00410, |
| <input type="checkbox"/> Min. Acidity
as CaCO ₃ | (41) | P00436, |
| <input type="checkbox"/> Chloride | (42) | P00940, |
| <input type="checkbox"/> MBAS | (43) | P38260, |
| <input type="checkbox"/> Phenols | (44) | P32730, |
| <input type="checkbox"/> Hardness - tot
as CaCO ₃ | (45) | P00900, |
| <input type="checkbox"/> Sulfate | (46) | P00945, |
| <input type="checkbox"/> Oil & Grease | (47) | P00556, |
| <input type="checkbox"/> Petroleum
Hydrocarbons | (48) | P45501, |
| <input type="checkbox"/> Cyanide | (49) | P00720, |

1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
---	---	---	---	---	---	---	---	---	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	-----

- ☐ As - tot ug/l (50) P01002
- ☐ Cd - tot ug/l (51) P01027
- ☐ Cr - tot ug/l (52) P01034
- ☐ Cu - tot ug/l (53) P01042
- ☐ Fe - tot ug/l (54) P01045
- ☒ Hg - tot ug/l (55) P71900
- ☐ Mn - tot ug/l (56) P01055
- ☐ Ni - tot ug/l (57) P01067
- ☐ Pb - tot ug/l (58) P01051
- ☐ Zn - tot ug/l (59) P01092

5K

ADDITIONAL ANALYSIS

- | | | | |
|--------------------------|-------|---|-------|
| <input type="checkbox"/> | _____ | P | _____ |
| <input type="checkbox"/> | _____ | P | _____ |
| <input type="checkbox"/> | _____ | P | _____ |
| <input type="checkbox"/> | _____ | P | _____ |
| <input type="checkbox"/> | _____ | P | _____ |

RESULTS mg/l unless otherwise noted

Chemist Review

Part 1 (White) - Water Quality Inventory Copy
Part 2 (Canary) - Laboratory Copy

Part 3 (Pink) - Laboratory Copy
Part 4 (Goldenrod) - Field Samplers Copy

STORM SEWER CONTAMINATION

B 30



NEW

DEPARTMENT OF ENVIRONMENTAL PROTECTION
DIVISION OF WATER RESOURCES
ENFORCEMENT & REGULATORY SERVICES

1982

COMPLIANCE EVALUATION INSPECTION
PUBLIC COMMUNITY WATER SUPPLYDATE 5/4/82

GENERAL INFORMATION	
PURVEYOR/MONROE MUNICIPAL UTILITIES AUTHORITY FACILITY	
FILE LOCATION <u>MONROE TWP</u>	PW-ID # <u>6811002</u>
MAILING ADDRESS <u>372 SO. MAIN STREET</u>	
ADMIN. <u>MR J.V. DINOVI CHAIRMAN</u>	REQUIRED T <u>2</u> LICENSES W <u>2</u>
BUSINESS TELEPHONE # Admin.: <u>609-629-4400</u> Licensed Operators: T <u>2</u>	<u>GUSTAV MINCEBACK</u> W <u>2</u>

FACILITY DESCRIPTION

SOURCES: descriptions, locations, capacities(mgd): WASHINGTON AVE #4. - 0.77 mgd (for emergency use, presently the well is offline.) Water Street Well #5 - 0.81 mgd. Lake Ave Well #6 - 0.6 mgd. Carbery Lane Well #7 - 1.14 mgd.

Est Tot Eff Cap: 3.27

TREATMENT: source, type, capacities(mgd): Wells 4, 5 & 6 Chlorination (gas) and PH adjustment with Caustic Soda. Well #7 Chlorination (gas) and PH adjustment with lime.

Est Tot Eff Cap: 3.27

FINISHED WATER STORAGE: descriptions, locations, capacities(mg): Chestnut and Water St elevated tank 0.15 mg, Herbert Blvd elevated tank 0.30 mg; Carbery Lane Black Horse Pike elevated tank 1.0 mg.

Est Tot Cap: 1.45

EMERGENCY INTERCONNECTIONS: descriptions, available gallonage(mgd): none

Est Tot Avail: ---

AUXILIARY POWER: location, type, capabilities: Well #4 gasoline engine, direct drive, Well #5 diesel engine, direct drive, Well #7 diesel generator for well & treatment.
Total 2067



DELIVERY INFORMATION		
PLANT DELIVERED WATER (mgd/month/year)	Max <u>36.521 mgd 7/81</u>	Min <u>13.120 mgd 2/81</u>
		Annual Average <u>27.029</u>
BULK PURCHASES (provider, mgd)	<u>none</u>	
BULK SALES (customer, mgd)	<u>none</u>	
NUMBER OF SERVICES	<u>3500</u>	% METERED <u>100</u>
MUNICIPALITIES SERVED (est. services in each)	<u>Williamstown Monroe Twp</u>	
	TOTAL ESTIMATED POPULATION SERVED <u>9400</u>	
CURRENT/RECENT WATER RESTRICTIONS	<u>none</u>	
NEW CONSTRUCTION (Project Numbers)	<u>none</u>	
DISTRIBUTION MAINS:	Sizing <u>4</u> (min) to <u>12</u> (max)	
	Pressures <u>40</u> (min) to <u>45</u> (max)	
	Hydrants/Flushing Program <u>semi-annual</u>	

MONITORING & REPORTING

PARAMETER(S)	FREQUENCY REQUIRED	FREQUENCY PERFORMED
Coliform	10 per month	10 per month
Inorganics	1/3 yr	1/3 yr
Nitrate	1/3 yr	1/3 yr
Trihalomethanes	N/A	N/A
Organics	N/A	N/A
Turbidity	N/A	N/A
RADIOLOGICAL	1/4 yr	1/4 yr

NAME OF LABORATORY Quality Control Lab CERTIFICATION # 04002
ADDRESS 243 White Horse Pike Audubon NJ

COMPLIANCE EVALUATION

SOURCE DEFICIENCIES Well #4 Mercury in water adjacent to Kankin Station.
Well #5 not in operation. Out for general maintenance and repair after
mercury contamination below EPA standard and MCL established by the Safe
Drinking Water Act

TREATMENT DEFICIENCIES none



COMPLIANCE EVALUATION (Continued)

STORAGE AND/OR DISTRIBUTION DEFICIENCIES Distribution system contains undersized main

LICENSING, MONITORING AND/OR REPORTING DEFICIENCIES None

COMPLIANCE SAMPLING VIOLATIONS:

LOCATION	DATA SOURCE	PARAM	MAX CONTMNT LEVEL	RESULT	LOCATION	DATA SOURCE	PARAM	MAX CONTMNT LEVEL	RESULT

OVERALL COMPLIANCE RATING:

☒ ACCEPTABLE

☐ CONDITIONALLY ACCEPTABLE

☐ UNACCEPTABLE

NOTICE: YOU ARE REQUIRED TO INFORM THE N.J.D.E.P. IN WRITING OF YOUR ACTUAL OR INTENDED ACTIONS TO COMPLY WITH N.J.S.A. 58:12A-1 ET SEQ. VIA IMPLEMENTATION OF REMEDIAL MEASURES TO CORRECT THE DEFICIENCIES LISTED IN THIS REPORT. FAILURE TO ADEQUATELY RESPOND IN A TIMELY FASHION WILL RENDER YOU LIABLE FOR PENALTIES OF UP TO \$5,000.00 FOR EACH VIOLATION, PURSUANT TO N.J.A.C. 7:10-3.

INSPECTOR:

J. P. Ricciardi
Signature

Name

F.C.I.

Title

VI

Region

PERSON INTERVIEWED:

G. Millbach
Name

Asst

Title

Monroe Municipal Utilities
Organization

TABULATION OF ANALYTICAL DATA FROM PUBLIC WATER SUPPLY

Wellwater
Monsie's
Beccia's
County Essex
Date Collected 6/2/82
Region VI Memo # _____ Project # W- _____

LOGICAL ANALYSES: Coliform organisms determined by the membrane filter technique are reported in colonies per 100 ml.
Chlorine residuals are reported in ppm.

Number	Point of Collection	Coliform Organisms		Chlorine Residual	
		Fecal	Total	Free	Total
0	Well #6 Lake Ave	1300			
42	Well #5 Water St	200			

CHEMICAL ANALYSES: Determinations are in ppm except color, odor, turbidity, and pH. Figures in parentheses are from the N. J. Potable Water Standards and/or National Interim Primary Regulations.

Number	Sample Number	
(10)	14640	14642
(III)	Arsenic (0.05)	
(5)	Barium (1.0)	
	Cadmium (0.010)	
	Chromium ⁺⁶ (0.05)	
pH 4	Copper (1.0)	
O ₃ (45)	Cyanide (0.20)	
(250)	Lead (0.05)	
solids (500)	Mercury (0.002)	0.0005K 0.0005K
(0.5)	Selenium (0.01)	
ness (150)	Silver (0.05)	
(0.3)	Phenol (0.001)	
(0.05)	Endrin (0.0002)	
(50)	Lindane (0.004)	
(250)	Methoxychlor (0.1)	
(2.0)	Toxaphene (0.005)	
(5.0)	2,4-D (0.1)	
	Silvex (0.01)	

RECEIVED

JUN 25 1982

STATE DEPT. OF ENVIRONMENTAL PROTECTION
BUREAU OF POTABLE WATER

REPORT SUBMITTED

JUN 16 1982

NJDOH Environmental
Chemistry Laboratory

Quality Control Laboratory and Environmental Support Alliance

243 White Horse Pike
Audubon, New Jersey 08106

"Certified Test"
DEPL 04002

atory"

609-428-1303

609-296-797

Information
sis #

A 958

Customer Information

Co. Monroe M.U.A.

Address _____ Phone _____

Sample drawn by Gus M Date 4/14/83 Time 1 P.M.

From #5 well

Date rec'd at lab 4/14/83 T _____

By _____

Date rec'd by Tech. _____ T _____

By _____

Date analyses started _____ T _____

Date analyses comp. _____ T _____

CHEMICAL

Test	Quan.	Meth.	Tech.	Date/Time
Acidity				
Alkalinity				
Aluminum				
Ammonia				
Antimony				
Arsenic				
Acid Extr.				
Barium				
BOD (5 day)				
Bromides				
Bismuth				
Base-Neutral Extr.				
Cyanide				
Chlorine				
Chlorides				
Cadmium				
Calcium				
Carbon Dioxide				
Cesium				
COD				
Chromium				
Cobalt				
Color				
Copper				
Density				
D. Oxygen				
Detergents ABS/LAS				
Fluorides				
Fungicides				
Hardness				
Hydrogen Sul.				
Herbicides				
Iron				
Iodine				
Iodide				
Kjeldahl N				
Lanthan				


Test	Quan.	Meth.	Tech.	Date/Time
Lead				
Lithium				
Magnesium				
Manganese				
Mercury	less than .002mg/l			
Molybdenum				
Moisture				
Nickel				
Nitrate				
Nitrite				
Odor				
Oils & Grease				
Pesticides & PCB's				
Petro Hydrocarbons				
Phenols				
Phosphate				
Phosphorus				
Potassium				
Platinum				
Selenium				
Silver				
Sulfate				
Sulfite				
Sulfide				
Sodium				
Silica				
S. Matter				
THM				
Thallium				
Turbidity				
Taste				
T. Solids				
TDS				
TOC				
Vanadium				
Volatile Org.				
Volatile Solids				
Zinc				
Zirconium				

BACTERIOLOGICAL

Test	Dil.	Total	Meth.	Tech.	Date/Time
T. Cells					
T. Collform					

Test	Dil.	Total	Meth.	Tech.	Date/Time
F. Collform					
F. Strep					

Remarks _____

 B 35
Bruce Greenwald, Lab Mgr.

Quality Control Laboratory and Environmental Support Alliance

243 White Horse Pike
Audubon, New Jersey 08106

"Certified Test Laboratory"
DEP Lab. ID# 04002

609-428-1303 609-296-7970

Information
Analysis #

957

Customer Information

Co. Monroe M.U.A.

Potable Water

Address _____ Phone _____

Sample drawn by Gus M Date 4/14/83 Time 1 P.M.

From #4 well

Date rec'd at lab 4/14/83 T _____

By _____

Date rec'd by Tech. _____ T _____

By _____

Date analyses started _____ T _____

Date analyses comp. _____ T _____

CHEMICAL

Test	Quan.	Meth.	Tech.	Date/Time
Acidity				
Alkalinity				
Aluminum				
Ammonia				
Antimony				
Arsenic				
Acid Extr.				
Barium				
BOD (5 day)				
Bromides				
Bismuth				
Base-Neutral Extr.				
Cyanide				
Chlorine				
Chlorides				
Cadmium				
Calcium				
Carbon Dioxide				
Cesium				
COD				
Chromium				
Cobalt				
Color				
Copper				
Density				
D. Oxygen				
Detergents ABS/LAS				
Fluorides				
Fungicides				
Hardness				
Hydrogen Sul.				
Herbicides				
Iron				
Iodine				
Iodide				
Kjeldahl N				
Lanthan				

Test	Quan.	Meth.	Tech.	Date/Time
Lead				
Lithium				
Magnesium				
Manganese				
Mercury	<u>.0046mg/l</u>			
Molybdenum				
Moisture				
Nickel				
Nitrate				
Nitrite				
Odor				
Oils & Grease				
Pesticides & PCB's				
Petro Hydrocarbons				
Phenols				
Phosphate				
Phosphorus				
Potassium				
Platinum				
Selenium				
Silver				
Sulfate				
Sulfite				
Sulfide				
Sodium				
Silica				
S. Matter				
THM				
Thallium				
Turbidity				
Taste				
T. Solids				
TDS				
TOC				
Vanadium				
Volatile Org.				
Volatile Solids				
Zinc				
Zirconium				

BACTERIOLOGICAL

Test	Dil.	Total	Meth.	Tech.	Date/Time
T. Cells					
T. Collform					

Test	Dil.	Total	Meth.	Tech.	Date/Time
F. Collform					
F. Strep					

Remarks _____

[Signature]

Bruce Greenwald, Lab Mgr.

B-36

Water Supply Purveyor Monroe Municipal Utilities Authority Date March 20, 1980

14. Deficiencies noted:

Source 1. Well # 4-well blow-off is not protected against entry of pollution. Underground gasoline storage tank is located within 100 ft. of well. 2. Well # 4-past Brueau records indicates raw water from this well contains mercury in excess of the MCL established by the Safe Drinking Water Act.

Treatment -

Storage and Distribution 1. Distribution system contains undersized mains.

Other -

15. Sampling: Dates/Comments 3/20/80 microbiological analysis was satisfactory. Limited chemical analysis showed the finished water from Well # 7 to be corrosive. Langelier Index=-2.0

16. Adequacy of facilities	Excellent <input type="checkbox"/>	Good <input checked="" type="checkbox"/>	Fair <input type="checkbox"/>	Poor <input type="checkbox"/>	Unsatisfactory <input type="checkbox"/>
Condition of facilities	Excellent <input checked="" type="checkbox"/>	Good <input type="checkbox"/>	Fair <input type="checkbox"/>	Poor <input type="checkbox"/>	Unsatisfactory <input type="checkbox"/>
Operation of facilities	Excellent <input checked="" type="checkbox"/>	Good <input type="checkbox"/>	Fair <input type="checkbox"/>	Poor <input type="checkbox"/>	Unsatisfactory <input type="checkbox"/>

Specific Comments -

Operator's Reports Satisfactory

17. Immediate Requirements* 1. Use Well # 4 in an emergency only. 2. Use Well # 5 only when necessary to meet daily water demands. 3. Adjust pH of finished water from Well # 7 to render water less corrosive

18. General Recommendations 1. Maintain surveillance to detect leakage of gasoline into Well # 4. 2. Gradually replace undersized mains smaller than 6 in. pipe diameter.

*NOTE: Kindly inform this Department of your actions relative to implementation of item 17 within 14 days of receipt.

Inspected: Daniel S. Mozer

Signature

Reviewed: William J. Laffey

Signature

5/9/80

Date

DSM:el Daniel S. Mozer

Name

William J. Laffey

Name

Senior Environmental Engineer

Title

Supervising Environmental Engineer

Title

JUN 20 1984

Monroe Township N.J.A.
372 South Main Street
Williamstown, New Jersey 08094

RE: Monitoring for Mercury
P.W. - ID No.: DE11602
Monroe Township/Gloucester County

Gentlemen:

The Department's records of Well #4 indicates that the raw water from this well contains mercury in excess of the MCL established by the Safe Drinking Water Act. It is known that Well #4 is used for emergency only, however you are directed to maintain a monthly surveillance of Well #4 and the test well on Avery Drive for mercury. This monitoring is to be reported to this Department along with the monthly operators reports.

If you have any questions concerning the above, please contact Al Anderson, the Compliance Investigator responsible for this case, who can be reached at (609) 292-1924 or by letter through this Division.

Thank you for your cooperation.

Very truly yours,

Original signed & mailed

Nick DeMeo
Supervising Environmental
Compliance Investigator
Southern Region
Enforcement Element

AS:ral

cc: George Cossaboon, Licensed Operator
Bureau of Potable Water
Robert Williams, USEPA - Region II
bcc: Region File THROUGH: DeMeo & Ricciardi
Central File
Al Anderson
Marianne Montgomery

Quality Control Laboratory and Environmental Support Alliance

243 White Horse Pike
Audubon, New Jersey 08106

"Certified Laboratory"
D-695 b. 10/04002

609-428-1303

609-296

Lab. Information

Analysis # D-695

Date rec'd at lab 11/26/84 1:45PM

By _____

Date rec'd by Tech. _____ T _____

By _____

Date analyses started _____ T _____

Date analyses comp. _____ T _____

Customer Information

Co. Monroe M.U.A

Address _____ Phone _____

Sample drawn by B.G. Date 11/26/84 Time 11:33 A.M.

From Washington Ave. Well #4

CHEMICAL

Test	Quan.	Meth.	Tech.	Date/Time
Acidity				
Alkalinity				
Aluminum				
Ammonia				
Antimony				
Arsenic				
Acid Extr.				
Barium				
BOD (5 day)				
Bromides				
Bismuth				
Base-Neutral Extr.				
Cyanide				
Chlorine				
Chlorides				
Cadmium				
Calcium				
Carbon Dioxide				
Cesium				
COD				
Chromium				
Cobalt				
Color				
Copper				
Density				
D. Oxygen				
Detergents ABS/LAS				
Fluorides				
Fungicides				
Hardness				
Hydrogen Sul.				
Herbicides				
Iron				
Iodine				
Iodide				
Kjeldahl N				
Lanthan				


Test	Quan.	Meth.	Tech.	Date/Time
Lead				
Lithium				
Magnesium				
Manganese				
Mercury	.00295mg/l			
Molybdenum				
Moisture				
Nickel				
Nitrate				
Nitrite				
Odor				
Oils & Grease				
Pesticides & PCB's				
Petro Hydrocarbons				
Phenols				
Phosphate				
Phosphorus				
Potassium				
Platinum				
Selenium				
Silver				
Sulfate				
Sulfite				
Sulfide				
Sodium				
Silica				
S. Matter				
THM				
Thallium				
Turbidity				
Taste				
T. Solids				
TDS				
TOC				
Vanadium				
Volatile Org.				
Volatile Solids				
Zinc				
Zirconium				

BACTERIOLOGICAL

Test	Dil.	Total	Meth.	Tech.	Date/Time
T. Cells					
T. Collform					

Test	Dil.	Total	Meth.	Tech.	Date/Time
F. Coliform					
F. Strep					

Remarks _____



B-38

Bruce Greenwald, Lab Mgr.

Quality Control Laboratory and Environmental Support Alliance

243 White Horse Pike
Audubon, New Jersey 08106

"Certified Testing Laboratory"
Lab. ID# 04002

609-428-1303

609-291-1000

Lab. Information
Analysis # D 1797

Date rec'd at lab 12/17/84 1:10PM

By _____

Date rec'd by Tech. _____ T _____

By _____

Date analyses started _____ T _____

Date analyses comp. _____ T _____

Customer Information

Co. Monroe M.U.A.

Address Williamstown, N.J. Phone _____

Sample drawn by B.G. Date 12/17/84 Time 11:12 A.M.

From Washington Ave. Well #4

CHEMICAL

Test	Quan.	Meth.	Tech.	Date/Time
Acidity				
Alkalinity				
Aluminum				
Ammonia				
Antimony				
Arsenic				
Acid Extr.				
Barium				
BOD (5 day)				
Bromides				
Bismuth				
Base-Neutral Extr.				
Cyanide				
Chlorine				
Chlorides				
Cadmium				
Calcium				
Carbon Dioxide				
Cesium				
COD				
Chromium				
Cobalt				
Color				
Copper				
Density				
D. Oxygen				
Detergents ABS/LAS				
Fluorides				
Fungicides				
Hardness				
Hydrogen Sul.				
Herbicides				
Iron				
Iodine				
Iodide				
Kjeldahl N				
Lanthan				

Test	Quan.	Meth.	Tech.	Date/Time
Lead				
Lithium				
Magnesium				
Manganese				
Mercury	0.0015mg/l			
Molybdenum				
Moisture				
Nickel				
Nitrate				
Nitrite				
Odor				
Oils & Grease				
Pesticides & PCB's				
Petro Hydrocarbons				
Phenols				
Phosphate				
Phosphorus				
Potassium				
Platinum				
Selenium				
Silver				
Sulfate				
Sulfite				
Sulfide				
Sodium				
Silica				
S. Matter				
THM				
Thallium				
Turbidity				
Taste				
T. Solids				
TDS				
TOC				
Vanadium				
Volatile Org.				
Volatile Solids				
Zinc				
Zirconium				

RECEIVED

FEB 8 1985

N.J. STATE DEPT. OF ENVIRONMENTAL PROTECTION
BUREAU OF POTABLE WATER

BACTERIOLOGICAL

Test	Dil.	Total	Meth.	Tech.	Date/Time
T. Cells					
T. Colliform					

Test	Dil.	Total	Meth.	Tech.	Date/Time
F. Colliform					
F. Strep					

Remarks _____

B-39

Bruce Greenwald, Lab Mgr

Quality Control Laboratory an

243 White Horse Pike
Audubon, New Jersey 08106

"Certified T Laboratory"
DE 107 04002

609-428-1303

609-296-7

Lab. Information

Analysis # D 2320

Date rec'd at lab /24/85 T2:30PM

By _____

Date rec'd by Tech. _____ T _____

By _____

Date analyses started _____ T _____

Date analyses comp. _____ T _____

Customer Information

Co. Monroe M.U.A.

Address Williamstown, N.J. Phone _____

Sample drawn by B.G. Date 1/24/85 Time 1:51 P.M.

From Washington Ave. (Well)

CHEMICAL

Test	Quan.	Meth.	Tech.	Date/Time
Acidity				
Alkalinity				
Aluminum				
Ammonia				
Antimony				
Arsenic				
Acid Extr.				
Barium				
BOD (5 day)				
Bromides				
Bismuth				
Base-Neutral Extr.				
Cyanide				
Chlorine				
Chlorides				
Cadmium				
Calcium				
Carbon Dioxide				
Cesium				
COD				
Chromium				
Cobalt				
Color				
Copper				
Density				
D. Oxygen				
Detergents ABS/LAS				
Fluorides				
Fungicides				
Hardness				
Hydrogen Sul.				
Herbicides				
Iron				
Iodine				
Iodide				
Kjeldahl N				
Lanthan				

Test	Quan.	Meth.	Tech.	Date/Time
Lead				
Lithium				
Magnesium				
Manganese				
Mercury	<u>.0029mg/l</u>			
Molybdenum				
Moisture				
Nickel				
Nitrate				
Nitrite				
Odor				
Oils & Grease				
Pesticides & PCB's				
Petro Hydrocarbons				
Phenols				
Phosphate				
Phosphorus				
Potassium				
Platinum				
Selenium				
Silver				
Sulfate				
Sulfite				
Sulfide				
Sodium				
Silica				
S. Matter				
THM				
Thallium				
Turbidity				
Taste				
T. Solids				
TDS				
TOC				
Vanadium				
Volatile Org.				
Volatile Solids				
Zinc				
Zirconium				

RECEIVED

FEB 8 - 1985

N.J. STATE DEPT. OF ENVIRONMENTAL PROTECTION
BUREAU OF POTABLE WATER

BACTERIOLOGICAL

Test	Dil.	Total	Meth.	Tech.	Date/Time
T. Cells					
T. Collform					

Test	Dil.	Total	Meth.	Tech.	Date/Time
F. Collform					
F. Strep					

Remarks _____

B-40

Bruce Greenwald, Lab Mgr.

Quality Control Laboratory and Environmental Support Alliance

243 White Horse Pike
Audubon, New Jersey 08106

"Certified Laboratory"
D 01 04002

609-428-1303 609-296

Lab Information E 9045

Anal. #

Date rec'd at lab 12/19/85 2:50pm

Customer Information

Co. Monroe Township MUA

Address Williamstown, N.J. Phone

Sample drawn by A.L. Date 12/19/85 Time 1:39pm

From Well #4 - Washington Ave.

By

Date rec'd by Tech. T

By

Date analyses started T

Date analyses comp. T

CHEMICAL

Test	Quan.	Meth.	Tech.	Date/Time
Acidity				
Alkalinity				
Aluminum				
Ammonia				
Antimony				
Arsenic				
Acid Extr.				
Barium				
BOD (5 day)				
Bromides				
Bismuth				
Base-Neutral Extr.				
Cyanide				
Chlorine				
Chlorides				
Cadmium				
Calcium				
Carbon Dioxide				
Cesium				
COD				
Chromium				
Cobalt				
Color				
Copper				
Density				
D. Oxygen				
Detergents ABS/LAS				
Fluorides				
Fungicides				
Hardness				
Hydrogen Sul.				
Herbicides				
Iron				
Iodine				
Iodide				
Kjeldahl N				
Lanthan				

Test	Quan.	Meth.	Tech.	Date/Time
Lead				
Lithium				
Magnesium				
Manganese				
Mercury	.00177	mg/l		
Molybdenum				
Moisture				
Nickel				
Nitrate				
Nitrite				
Odor				
Oils & Grease				
Pesticides & PCB's				
Petro Hydrocarbons				
Phenols				
Phosphate				
Phosphorus				
Potassium				
Platinum				
Selenium				
Silver				
Sulfate				
Sulfite				
Sulfide				
Sodium				
Silica				
S. Matter				
THM				
Thallium				
Turbidity				
Taste				
T. Solids				
TDS				
TOC				
Vanadium				
Volatile Org.				
Volatile Solids				
Zinc				
Zirconium				

Test	Dil.	Total	Meth.	Tech.	Date/Time
T. Cells					
T. Coliform					12/19/85

Test	Dil.	Total	Meth.	Tech.	Date/Time
F. Coliform					
F. Strep					

Remarks

N.J. State Dept. of Environmental Protection
BUREAU OF POTABLE WATER

B-41
Bruce Greenwald, Lab Mgr



BLK

COMPLIANCE EVALUATION INSPECTION
PUBLIC COMMUNITY WATER SUPPLY

DATE

June 27, 1985

GENERAL INFORMATIONPURVEYOR/
FACILITY

Monroe Township, N.J.A.

FILE LOCATION

Monroe Twp. / Gloucester Co.

PW-ID #

0811002

MAILING ADDRESS

372 South Main Street, Williamstown, N.J.

ADMIN.

MS Jacqueline Schoenewald

REQUIRED
LICENSEST-3
W-3

GEORGE

BUSINESS

TELEPHONE # Admin.: 629-7586

Licensed Operators: T-3

C-3

W-4

M. Cassabone

FACILITY DESCRIPTION

SOURCES: descriptions, locations, capacities(mgd):

Well #4 Washington Ave 0.72 mgd;

Well #5 Water St. 0.81 mgd; Well #6 Lake Ave 0.60 mgd;

Well #7 Corkery Lane 1.14 mgd.

Well #4 emergency use only

Est Tot Eff Cap: 3.27 mgd

TREATMENT: source, type, capacities(mgd): CAS chlorination at all wells.

Wells 4, 5 & 6 PH adjusted with Caustic Soda, Well #7
PH adjusted with lime.

Est Tot Eff Cap: 3.27 mgd

FINISHED WATER STORAGE: descriptions, locations, capacities(mg):

Elevated Tank - Water St.

0.15 mg; Elevated Tank - Herbert Boulevard 0.30 mg;

Elevated Tank - Corkery Lane 1.0 mg.

Est Tot Cap: 1.45 mg

EMERGENCY INTERCONNECTIONS: descriptions, available gallonage(mgd):

None

Est Tot Avail:

AUXILIARY POWER: location, type, capabilities:

Well #5 (Right Angle Drive) diesel

engine/generator for well and treatment - 50 Kw - 0.81 mgd;

Well #7 diesel engine/generator for well and

treatment - 10.0 Kw - 1.14 mgd.

Tot. aux. cap 1.95 mgd



COMPLIANCE EVALUATION (Continued)

STORAGE AND/OR DISTRIBUTION DEFICIENCIES

None

LICENSING, MONITORING AND/OR REPORTING DEFICIENCIES

None

COMPLIANCE SAMPLING VIOLATIONS:

LOCATION	DATA SOURCE	PARAM	MAX CONTMNT LEVEL	RESULT	LOCATION	DATA SOURCE	PARAM	MAX CONTMNT LEVEL	RESULT

OVERALL COMPLIANCE RATING:

☒ ACCEPTABLE

☐ CONDITIONALLY ACCEPTABLE

☐ UNACCEPTABLE

NOTICE: YOU ARE REQUIRED TO INFORM THE N.J.D.E.P. IN WRITING OF YOUR ACTUAL OR INTENDED ACTIONS TO COMPLY WITH N.J.S.A. 58:12A-1 ET SEQ. VIA IMPLEMENTATION OF REMEDIAL MEASURES TO CORRECT THE DEFICIENCIES LISTED IN THIS REPORT. FAILURE TO ADEQUATELY RESPOND IN A TIMELY FASHION WILL RENDER YOU LIABLE FOR PENALTIES OF UP TO \$5,000.00 FOR EACH VIOLATION, PURSUANT TO N.J.A.C. 7:10-3.

INSPECTOR:

Joseph C. Kaya
Signature

Joseph A. Kaya
Name

Env. Comp. Inv.
Title

South
Region

PERSON INTERVIEWED:

George Cossabone
Name

Operator
Title

Minnie Tap M.U.A.
Organization



DELIVERY INFORMATION

PLANT DELIVERED WATER (mgd, month, year) Max 1.194 June, 84 Min .815 Feb, 84 Annual Average 920, 84

BULK PURCHASES (provider, mgd) None

BULK SALES (customer, mgd) None

NUMBER OF SERVICES 4400 % METERED 100

MUNICIPALITIES SERVED (est. services in each) All Services in Monroe Twp.

TOTAL ESTIMATED POPULATION SERVICED

CURRENT/RECENT WATER RESTRICTIONS Voluntary Conservation

NEW CONSTRUCTION (Project Numbers) None

DISTRIBUTION MAINS: Sizing 4" (min) to 10" (max)
Pressures 45 psi (min) to 65 psi (max)
Hydrants/Flushing Program Yes/Yes

MONITORING & REPORTING

PARAMETER(S)	FREQUENCY REQUIRED	FREQUENCY PERFORMED
PH & Cl ₂	Daily	Daily
Coliform	15- month	15- month
Inorganics & NA	1- 3 years	1- 3 yrs 10-1-84
Nitrate	1- 3 years	1- 3 yrs
Trihalomethanes	4- 3 months	4-3 mo's 5-30-84
Organics	N/A	N/A
Turbidity	N/A	N/A
Radio	1- 4 years	1-4 yrs 6-24-83
A-280's	1- 6 mo's	1-6 mo's 5-30-84
Secondaries	1- 3 years	1-3 yrs 10-1-84

recently completed

NAME OF LABORATORY Quality Control CERTIFICATION # 04002

ADDRESS Audubon N.J.

COMPLIANCE EVALUATION

SOURCE DEFICIENCIES None

TREATMENT DEFICIENCIES None

COMPLIANCE EVALUATION INSPECTION
PUBLIC COMMUNITY WATER SUPPLY

DATE JAN 5 1986

1986

GENERAL INFORMATION

PURVEYOR/ FACILITY <u>MENKLE TWP. MUA</u>	
FILE LOCATION <u>MENKLE TWP. GLOUCESTER CO.</u>	PW-ID # <u>0511022</u>
MAILING ADDRESS <u>372 SOUTH MAIN ST., WILLIAMSTOWN NJ</u>	
ADMIN. <u>MR. JACQUELINE SCHENKEL</u>	REQUIRED T - 3 LICENSES W - 3
BUSINESS <u>629-7586</u>	T-3 W-3
TELEPHONE # Admin.: <u>629-7586</u>	Licensed Operators: <u>TE. COSSARNE W E. COSSARNE</u>

FACILITY DESCRIPTION

SOURCES: descriptions, locations, capacities(mgd):

4 WELLS WELL #4 WASHINGTON
AVE 0.72 MGD WELL #5 WATER ST. 0.81 MGD
WELL #6 LAKE AVE 0.66 MGD WELL
#7 PARKERY LANE 1.14 MGD Est Tot Eff Cap: 3.27 MGD

TREATMENT: source, type, capacities(mgd):

CL2S CHLORINATION AT ALL WELLS
WELLS 4, 5 AND 6 PH ADJUSTMENT WITH SODA
SODA WELL #7 LIME ADJUSTMENT OF PH.
 Est Tot Eff Cap: 3.27 MGD

FINISHED WATER STORAGE: descriptions, locations, capacities(mg):


SELECTED TANK
WATER ST 1.15 MG SELECTED TANK WERTHER RD
0.3 MG SELECTED TANK PARKERY LANE 1.14 MG
 Est Tot Cap: 1.45 MG

EMERGENCY INTERCONNECTIONS: descriptions, available gallonage(mgd):


NONE
 Est Tot Avail: -

AUXILIARY POWER: location, type, capabilities:

WELL #5 DIESEL NIGHT HOUSE
WELL #7 DIESEL GENERATOR SOURCE AND
TREATMENT 1.14 MGD



SCALE 1:24000




LATITUDE : 39° 41' 03"
 LONGITUDE : 74° 59' 25"
 EPA ID # NJD93C767679

MONROE TWP. MUNICIPAL WELLS
 #4 & 5
 MONROE TWP. / GLOUCESTER CO.
 NEW JERSEY

WILLIAMSTOWN, N.J.
 NW/4 HAMMONTON 15 QUADRANGLE
 N3937.5—W7452.5 7.5

PITMAN EAST, N.J.
 N3937.5—W7500/7.5




MONROE TWP. MUNICIPAL WELLS
#4 & 5

PUBLIC M. U. A.
WATER SUPPLY SYSTEM


MONROE TOWNSHIP / GLOUCESTER CO.
NEW JERSEY

SHEET 31
TOPOGRAPHIC SERIES


Scale: 1"=63,360'



MAP #2



75°00' 39°36'



75° 00' 39° 36'
X=1906069 51

GEOLOGIC MAP

A. Pitman East, Runnemede

B. Atlantic Coastal-Great Egg Harbor River; Delaware Bay-Maurice River;
Delaware River-Big Timber Creek, Mantua Creek

C. 2. Map No.	Location	Period of Record
	452 South Branch Big Timber Creek at Blackwood	1964-

Water Quality Standards: (explained in Atlas Sheet description)
FW3 except where classified FW1

D. Quaternary Gravels (Qg), Cohansey Formation (Tch), Kirlwood Sand (Tkw),
Vincentown Sand (Tvt), Hornerstown Marl (Tht), Navesink Marl (Kns),
Mount Laurel and Wenonah Formations (Krw)

E. 1. Physiographic Province: Coastal Plain
Subdivision: Inner Plain, Outer Plain
Major Topographic Features: Clay and Marl Region, Pine Plains
Elevations (ft. above sea level): hills 180, valleys 10
Relief (ft.): 170

2. a. Normal Year: 46"
Dry Year: 34"
Wet Year: 52"

b. January: 33°F
July: 76°F

c. 249 days. Last killing frost: 4/25; first killing frost: 10/20

F. Div. of Fish, Game and Shellfisheries:
Glassboro Fish and Wildlife Management Area

I. Water Well Records

<u>Location</u>	<u>Owner</u>	<u>Year Drilled</u>	<u>Screen Setting or Depth of Casing</u>	<u>Total Depth</u>	<u>g/m Yield</u>	<u>Formation</u>
31-22-124	Deptford Twp.	1971	414-447	485	735	Kmr
31-22-129	Washington Twp.Mun.Util.Auth.	1972	369-417	460	440	"
31-22-212	Blackwood Water Co.	1956	426-447	513	708	"
31-22-223	Garden State Water Co., #6	1971	410-480	505	1012	"
31-22-234	Gloucester Twp.Bd.of Ed.	1964	455-475	475	220	"
31-22-242	Garden State Water Co.	1974	433-475	544	1000	"
31-22-397	Gloucester Twp.Bd.of Ed.	1960	293-	315	80	Kns
31-22-433	Washington Twp.Mun.Util.Auth.	1972	575-640	659	1000	Kmr
31-22-459	" Bd.of Ed.	1970	230-260	260	270	Ket
31-22-486	Fred Smith	1967	250-300	305	500	"
31-22-516	Wash.Twp.Mun.Util.Auth., #2	1967	542-576	597	503	Kmr
31-22-528	" #8	1968	544-620	667	735	"
31-22-538	" #1	1959	581-612	670	620	"
31-22-558	" #6	1964	584-652	760	858	"
31-22-724	Fred Smith	1966	20-45	65	60	Tch
31-22-783	"	1964	20-80	100	528	"
{ x 31-22-867	Joseph Frederessi	1971	50-80	80	200	"
{ x 31-22-996	Norman Tomasello	1964	80-100	100	596	"

J. Geodetic Control Survey monuments described in
Index Maps 54,55,61

A. Clementon, Williamstown

B. Atlantic Coastal-Great Egg Harbor River, Atsion, Mechesac,
Delaware River-Big Timber Creek

C. 2. Map No.	Location	Period of Record
439	Great Egg Harbor at Berlin	1964-

Water Quality Standards: (explained in Atlas Sheet description)
FW2 except where classified FW3

D. Quaternary Gravel (Qg), Cohansey Sand (Tch), Kirkwood Sand (Tkw)

E. 1. Physiographic Province: Coastal Plain
Subdivision: Outer Plain
Major Topographic Features: Pine Plains
Elevations (ft.above sea level): hills 180, valleys 50
Relief (ft.): 130

2. a. Normal Year: 46"
Dry Year: 34"
Wet Year: 54"

b. January: 38°F
July: 75°F

c. 246 days. Last killing frost: 4/25; first killing frost: 10/15

F. Div. of Parks and Forestry:
Inskip State Park
Camden County:
New Brooklyn Park

4c

I. Water Well Records

<u>Location</u>	<u>Owner</u>	<u>Year Drilled</u>	<u>Screen Setting or Depth of Casing</u>	<u>Total Depth</u>	<u>g/m Yield</u>	<u>Formation</u>
31-23-162	Pine Valley Golf Club	1955	-	267	200	Kmw
31-23-183	Pine Valley Water Co.	1960	31-86	105	100	Tch
31-23-235	Borough of Berlin, #10	1967	645-713	800	1012	Kmr
31-23-236	"	1952	310-360	398	450	Kmw
31-23-236	"	1955	650-713	955	1001	Kmr
31-23-344	" #11	1972	675-745	747	1078	"
31-23-347	Overbrook High School	1971	315-335	335	145	Tvt?
31-23-356	Owens-Illinois Glass Co.	1951	410-440	552	115	Kmw
31-23-367	Lower Camden Reg. High School	1957	100-110	170	240	Tkw
31-23-395	Ivystone Water Works	1963	420-460	460	528	Kmw
31-23-467	Lafferty & Sons	1959	61-82	113	201	Tch
31-23-538	Johns-Manville	1963	410-450	450	300	Kmw
31-23-538	"	1963	410-450	900	200	"
31-23-659	A.T. & T.	1966	120-130	209	150	Tkw
31-23-694	Joseph Parillo	1966	52-57	82	100	Tch
31-23-728	Joseph Volpa	1969	112-127	127	-	Tkw
X 31-23-764	Levitt & Sons, Inc.	1971	81-96	157	200	Tch
X 31-23-777	Monroe Twp. Mun. Util. Auth.	1970	111-145	166	412	Tkw
X 31-23-818	Winslow Water Co.	1971	64-90	136	1000	Tch
X 31-23-858	"	1971	72-103	119	1000	"
X 31-23-899	USGS, New Brooklyn Test	1960	-	2090	-	Wgn
31-23-965	Dan DeSilvo	1968	25-84	90	60	Tch
31-23-996	A. K. Brown, Jr.	1967	40-100	100	300	"

J. Geodetic Control Survey monuments described in
Index Maps 55,61; adjacent Index Maps 54,62

- A. Newfield, Pitman East
- B. Atlantic Coastal-Great Egg Harbor River; Delaware Bay-Maurice River
- C. Water Quality Standards: (explained in Atlas Sheet description)
FW1 except where classified FW3
- D. Quaternary Gravel (Qg), Cohansey Sand (Tch)
- E. 1. Physiographic Province: Coastal Plain
Subdivision: Outer Plain
Major Topographic Features: Pine Plains
Elevations (ft.above sea level): hills 150, valleys 90
Relief (ft.): 60
2. a. Normal Year: 47"
Dry Year: 33"
Wet Year: 53"
- b. January: 35°F
July: 75°F
- c. 249 days. Last killing frost: 4/25; first killing frost: 10/20
- F. Div. of Fish, Game and Shellfisheries:
Glassboro Fish and Wildlife Management Area

I. Water Well Records

<u>Location</u>	<u>Owner</u>	<u>Year Drilled</u>	<u>Screen Setting or Depth of Casing</u>	<u>Total Depth</u>	<u>g/m Yield</u>	<u>Formation</u>
31-32-174	Borough of Clayton, #4	1973	670-740	943	1043	Kmr
31-32-412	John Glover	1954	62-74	76	60	Tch
31-32-441	Borough of Clayton, #2	1956	745-800	1010	708	Kmr
X 31-32-612	Leshay Bros.	1965	19-141	141	1000	Tch-Tkw
X 31-32-619	Joseph Pagano	1966	40-180	180	60	" "
31-32-937	Albert B. Chard	1973	45-75	75	60	Tch

J. Geodetic Control Survey monuments described in
Index Maps 61,67

A. Buena, Williamstown

B. Atlantic Coastal-Great Egg Harbor River, Nescochague;
Delaware Bay-Maurice River

C. Water Quality Standards: (explained in Atlas Sheet description)
FW2 except where classified FW3

D. Quaternary Gravel (Qg), Cohansey Sand (Tch)

E. 1. Physiographic Province: Coastal Plain
Subdivision: Outer Plain
Major Topographic Features: Pine Plains
Elevations (ft. above sea level): hills 140, valleys 70
Relief (ft.): 70

2. a. Normal Year: 47"
Dry Year: 34"
Wet Year: 56"

b. January: 34°F
July: 75°F


c. 248 days. Last killing frost: 4/25; first killing frost: 10/15

F. Div. of Parks and Forestry:
Inskip State Park
Div. of Fish, Game and Shellfisheries:
Winslow Fish and Wildlife Management Area

I. Water Well Records

<u>Location</u>	<u>Owner</u>	<u>Year Drilled</u>	<u>Screen Setting or Depth of Casing</u>	<u>Total Depth</u>	<u>g/m Yield</u>	<u>Formation</u>
X 31-33-131	Frank Yegla	1972	40-80	80	50	Tch
X 31-33-146	Monroe Twp. Mun. Util. Auth., #5	1967	127-160	180	510	"
X 31-33-147	Violet Packing Co.	1967	123-143	150	300	"
X 31-33-149	Monroe Twp. Mun. Util. Auth., #4	1951	69-106	107	805	"
X 31-33-151	Decora Inc.	1974	105-120	120	250	"
X 31-33-41	W. H. Hays, Pros.	1955	108-140	140	500	"
31-33-594	American Mobile Home	1971	147-167	167	200	"
31-33-594	"	1971	147-167	167	200	"
31-33-954	Wharton Realty Co.	1962	56-82	97	100	"


J. Geodetic Control Survey monuments described in
Index Maps 61,67; adjacent Index Maps 62,68



MAP #5

POPULATION MAP

75°00' 39°36'



Map # 6

PLATE 19

PLATE 31

PLATE 33


PLATE 118

PLATE 117

PLATE 116

TAX MAP

TOWNSHIP OF MONROE
GLOUCESTER COUNTY, NEW JERSEY
SCALE: 1" = 100' JUNE 1981
PETER N. LIBERATO, N.J.L.S., L.C. No. 3546
CONSULTING ENGINEER SERVICES
Engineers, Planners and Land Surveyors
P.O. Box 616, Woodbury, N.J. 08096



WELL # 4
MAP # 7


WASHINGTON AVE. PLATE 32

LINWOOD AVE

EMERGENCY ACCESS

PLATE 33

CROSS KEYS WILLIAMSTOWN (MAIN STREET) ROAD



WELL #5
MAP #8

SHISLER (VACATED) AVE

TAX MAP
TOWNSHIP OF MONMOUTH
GLOUCESTER COUNTY, NEW JERSEY
SCALE: 1" = 50' JUNE
PETER M. LIBERATO, N.J.S. LICENSED
CONSULTING ENGINEER SURVEYOR
Engineers, Planners and Land Surveyors
P.O. Box 510, Woodbury, N.J. 08096

PLATE 134

(N. J. S. H. RTE. 322)
GLASSBORO - WILLIAMSTOWN ROAD

PLATE 118


PLATE 132

PLATE 118

PLATE 130


TAX MAP

TOWNSHIP OF MONROE
GLOUCESTER COUNTY, NEW JERSEY
SCALE: 1" = 100' JUNE 1981
PETER N. LIBERATO, N.J.S.L. No. 15546
CONSULTING ENGINEER SERVICES
Engineers, Planners and Land Surveyors
P.O. Box 616, Woodbury, N.J. 08096



Map #9

Block 13301
Lot 11 & 12 - Gravel P.T.
- Thomas H. Webb Jr.
RD 7 Box 175
Jackson Road
Williamstown, NJ
Block 13301
Lot 14 - Atlantic City Elec. Co.
P.O. Box 1500
Pleasantville, NJ
08232
(Williamstown, NJ 08064)



SUBJECT TO REVISION

WATER WITHDRAWAL
POINTS AND
NJGS CASE INDEX
SITES WITHIN
5.0 MILES OF:

LATITUDE 394103
LONGITUDE 745925

DRAFT

SCALE: 1 Mile




x WATER WITHDRAWAL POINTS
o NJGS CASE INDEX SITES
1 MILE AND 5 MILE RADIUS INDICATED

NJGS CASE INDEX DATA RETRIEVED FROM:
NEW JERSEY GEOLOGICAL SURVEY
ON 12/22/87

PLOT PRODUCED BY:
NJDEP
DIVISION OF WATER RESOURCES
BUREAU OF WATER ALLOCATION
CN-1229
TRENTON, NJ 08625
DATE: 04/06/88

SUBJECT TO REVISION




Map # 10

NUMBER	NAME	SOURCEID	LOCID	LAT	LON	LLACC	DISTANCE	COUNTY	MUN	DEPTH	GE01	GE02	CAPACITY
GL0003	STEJO INC.	WELL 1		393832	750354	U	4.9	15			GTCH		
GL0004	SMITH, FRED	WELL 1		393830	750353	U	4.9	15			GTCH		
10139W	LENAPE HIGH SCHOOL	3105329	1	394230	750327	F	3.9	05	21	220	GKMW		100
GL0052	SMITH, RALPH J.	WELL 1		394235	750320	U	3.9	15			GTCH		
5194	WASHINGTON TOWNSHIP MUA	3126047	10	394328	750215		3.7	15	18	107	GTCH		1000
10105W	MOON NURSERIES INC.	3108862	1	393926	750151	F	2.8	15	05	115	GTCH		90
10105W	MOON NURSERIES INC.	3111378	2	393926	750151	F	2.8	15	05	122	GTCH		350
2014P	NATIONWIDE MOBILE HOMES	5100033	WELL NO. 1	394253	750120	I	2.7	15	11	81	GTCH		250
GL0060	OLSEN, HAROLD R.	WELL 1		393713	750114	U	4.7	15			GTCH		
2014P	NATIONWIDE MOBILE HOMES	3118471	WELL NO. 2	394232	750112	I	2.3	15	11	135	GTCH		300
10405W	JANVIER VOLUNTEER FIRE CO.	3122246	1	393710	750054	F	4.6	15	05	105	GTCH		150
5007	GARDEN STATE WATER COMPANY	PROPOSED	12	394410	750028		3.7	07	15		GKMW		350
5007	GARDEN STATE WATER COMPANY	3116697	8	394415	750017		3.8	07	15	135	GTCH		500
GL0159	SICKLER, MELVIN E.	WELL 1		394005	750006	U	1.3	15			GTCH		
GL0159	SICKLER, MELVIN E.	POND 1		394005	750000	U	1.3	15			SD		
2177P	VIOLET PACKING CO.	3105150	WELL NO. 2	394050	745958	I	0.5	15	11	143	GTCH		300
2177P	VIOLET PACKING CO.	3115840	3	394040	745955		0.6	15	11	160	GTCH		60
GL0156	LOTBL, FRANK J.	STREAM 1		393925	745948	U	1.9	15			SD		
5161	MONROE MUA	3105375	6	394219	745944	I	1.5	15	11	144	GTCH		400
GL0181	LESHAY FARMS, SAMUEL	WELL 1		393925	745940	U	1.9	15			GTCH		
5007	GARDEN STATE WATER COMPANY	3122273	10	394500	745928	F	4.5	07	15	430	GKMW		350
5161	MONROE MUA	3105375	6	394219	745944	I	1.5	15	11	144	GTCH		400
5007	GARDEN STATE WATER COMPANY	PROPOSED	11	394514	745913		4.8	07	15		GTCH		350
CD0046	MATRO FARMS, GAETANO	WELL 1		394348	745909	U	3.2	07			GTCH		
CD0046	MATRO FARMS, GAETANO	POND 1		394348	745909	U	3.2	07			SCHUL		
10479W	WINGLOW TOWNSHIP	3123879	1	394342	745849	F	3.1	07	36	105	GTCH		100
GL0024	FATHER & SON NURSERY	WELL 1		394142	745840	U	1.0	15			GTCH		
5161	MONROE MUA	3114090	7	394010	745838	I	1.2	15	11	147	GTCH		900
5096	WINGLOW TWP. WATER & SEWER DEPT	3105578	3	394300	745830		2.4	07	36	97	GTCH		60
5096	WINGLOW TWP. WATER & SEWER DEPT	3106074	4	394225	745807		1.9	07	36	107	GTCH		1000
5311	SOUTHERN JERSEY WATER CO.	PROPOSED WELL 1		3945	7458		4.7	07	36	140	GTCH		700
5096	WINGLOW TWP. WATER & SEWER DEPT	3105543	2	394332	745740		3.2	07	36	103	GTCH		600
10056W	MONROE TWP., COMMUNITY AFFAIRS	3114496	1	393922	745738	F	2.5	15	11	111	GTCK		
5096	WINGLOW TWP. WATER & SEWER DEPT	3105542	1	394248	745710		2.8	07	36	113	GTCH		1200
10004W	CECIL FIRE CO. #1 (TWP. MONROE)	3119549	1	393833	745658	F	3.6	15	11	128	GTCK		300
10004W	CECIL FIRE CO. #1 (TWP. MONROE)	3119550	2	393835	745658	F	3.6	15	11	118	GTCK		13
10401W	FRIENDLY VLG. OF WILLIAMSTOWN	3105733	2	393821	745619	F	4.1	15	11	167	GTCH		200
10401W	FRIENDLY VLG. OF WILLIAMSTOWN	3105732	1	393820	745618	F	4.1	15	11	167	GTCH		200
10560W	CERTAIN-TEED CORP.	5100034	1	394417	745538	F	5.0	07	36	180	GTCH		300
CD0050	CURCIO, MICHAEL A.	WELL 1		394155	745509	U	3.9	07			GTCH		
CD0001	DE SILVO, DAN	3105210	WELL 1	394255	745425	T	4.9	07	36	90	GTCH		250
CD0055	FIORIENTINO, MARK W.	WELL 1		394243	745410	U	5.0	07			GTCH		
10506W	BROWN, ALBERT K. JR.	3105078	1	394225	745407	F	4.9	07	36	100	GTCK		

Number of Observations: 43

SITENUM	NAME	LAT	LON	DISTANCE	CONTAM	FNCODE1	FNCODE2	STATUS1	STATUS2
784	EASTCOAST POLLUTION CONTROL, INC., CLAYTON, GLOUCESTER CO.	393947	750423	4.6	0	0160	1020	1	
260	TURNERSVILLE GETTY, BLACK HORSE PIKE, GLOUCESTER CO.	394418	750224	4.6	51	1020	1025	1	C
1145	EGLI RESIDENCE, 731 SICKLERVILLE RD, MONROE TWP, GLOUSETER CO.	394203	745910	1.2				3	

Number of Observations: 3



NATIONAL FLOOD INSURANCE PROGRAM

FIRM
FLOOD INSURANCE RATE MAP

TOWNSHIP OF
MONROE,
NEW JERSEY
GLOUCESTER COUNTY

PANEL 15 OF 40
SEE MAP INDEX FOR PANELS NOT SHOWN

COMMUNITY-PANEL NUMBER
340208 0015 B

EFFECTIVE DATE:
JANUARY 20, 1982

ZONE C



KEY TO MAP

100-Year Flood Boundary	ZONE B
100-Year Flood Boundary	ZONE AT
Zone Designation	ZONE AS
100-Year Flood Boundary	ZONE B
100-Year Flood Boundary	513
Sea Flood Elevation at First Where Uniform Width Zone	45.0071
Uniform Submarine Mark	407.14
Zone D Boundary	441.5
Sea Wall	
*Referenced to the National Geodetic Vertical Datum of 1929	

PRIVATE DRIVE

ROAD

Map 11

Monroe Municipal Utilities Authority

372 South Main Street
Williamstown, New Jersey 08094

Jacqueline Schoenewald
Executive Director
Phone: 629-1444

George Cossabone
Superintendent
Phone: 629-7586

APR 15 1988

April 5, 1988

Bureau of Planning and Assessment
65 Prospect Street
Trenton, New Jersey 08618

Attn: Mr. Frank Faranca

Dear Frank,

Enclosed is the copies of our most recent testing results for mercury, sodium, fluorides, and inorganics which you requested.

If you have any questions regarding the above please call me at (609) 629-7586.

Very truly yours,

MONROE MUNICIPAL UTILITIES AUTHORITY


George P. Cossabone
Superintendent

GPC/amb
cc: File

ENCS.

ATTACHMENT A

P & P LABORATORIES, INC.
ENVIRONMENTAL & CLINICAL TOXICOLOGY
2025 Woodlynne Avenue
Woodlynne, NJ 08107
(609) 962-6611
DEP # 04479

WATER POTABILITY ANALYSIS

CLIENT :

Monroe Twp. MUA
372 S. Main Street
Williamstown, NJ 08094

WASHINGTON AVE
WELL #4

SAMPLE NO. : 8424 COLLECTED BY : P & P Lab.
DATE COLLECTED : 1/29/88 TIME : 11:25
DATE RECEIVED : [REDACTED] TIME : 15:00
SOURCE OF SAMPLE : [REDACTED]

Location

METALS & INORG/ORGANICS	RESULTS *	MCL **	COMMENTS
Arsenic		0.05	
Barium		0.10	
Cadmium		0.01	
Chromium		0.05	
Copper		0.05	
Fluoride		0.8-4.0	
Lead		0.05	
Manganese		0.002	
Sodium	< 0.002	50.00	
Selenium		0.01	
Silver		0.05	
Zinc		1.00	
Nickel			
Chlordane			

* mg/l unless specified

** Maximum Contaminant Level

< = Less Than

TNTC= Too Numerous To Count

Henry J. Pielichowski
Tech. Lab. Supervisor

[Signature]

P & P LABORATORIES, INC.
ENVIRONMENTAL & CLINICAL TOXICOLOGY
2025 Woodlynne Avenue
Woodlynne, NJ 08107
(609) 962-6611
DEP # 04479

WATER POTABILITY ANALYSIS

CLIENT :

Monroe Twp. MUA
372 S. Main Street
Williamstown, NJ 08094

Avery Dr
Test Well

SAMPLE NO. : 8425 COLLECTED BY : P & P Lab
DATE COLLECTED : 1/29/88 TIME : 11:43
DATE RECEIVED : [REDACTED] TIME : 16:00
SOURCE OF SAMPLE : [REDACTED]

Location :

METALS & INORG/ORGANICS	RESULTS *	MCL **	COMMENTS
Arsenic		0.05	
Barium		0.10	
Cadmium		0.01	
Chromium		0.05	
Copper		0.05	
Fluoride		0.8-4.0	
Lead		0.05	
[REDACTED]		0.002	
Sodium	20.002	50.00	
Selenium		0.01	
Silver		0.05	
Zinc		1.00	
Nickel			
Chlordane			

* mg/l unless specified
** Maximum Contaminant Level
< = Less Than
TNTC= Too Numerous To Count

Henry J. Pielichowski
Tech. Lab. Supervisor

HP

P & P LABORATORIES, INC.
ENVIRONMENTAL & CLINICAL TOXICOLOGY
2025 Woodlynne Avenue
Woodlynne, NJ 08107
(609) 962-6611
DEP # 04479

WATER POTABILITY ANALYSIS

CLIENT :

Monroe Twp. MUA
372 S. Main Street
Williamstown, NJ 08094

Water St
wall #5

SAMPLE NO.
DATE COLLECTED

:8422
:1/29/88

COLLECTED BY : P & P Lab

TIME

DATE RECEIVED
SOURCE OF SAMPLE

TIME : 16:00

Location

METALS & INORG/ORGANICS | RESULTS * | MCL ** | COMMENTS |

Arsenic

0.05

Barium

0.10

Cadmium

0.01

Chromium

0.05

Copper

0.05

Fluoride

0.8-4.0

Lead

0.05

Mercury

0.002

Sodium

<0.002

50.00

Selenium

0.01

Silver

0.05

Zinc

1.00

Nickel

Chlordane

*mg/l unless specified

** Maximum Contaminant Level

<= Less Than

TNTC= Too Numerous To Count

Henry J. Pielichowski
Tech. Lab. Supervisor

HP

P & P LABORATORIES, INC.
ENVIRONMENTAL & CLINICAL TOXICOLOGY
2025 Woodlynne Avenue
Woodlynne, NJ 08107
(609) 962-6611
DEP # 04479

WATER POTABILITY ANALYST'S

CLIENT :

Monroe Twp. MUA
872 S. Main Street
Williamstown, NJ 08094

LAKE AVE
Well #6

SAMPLE NO. : 8433

COLLECTED BY : P & P Lab

DATE COLLECTED

TIME : 12:07

DATE RECEIVED

1/29/88

TIME : 16:00

SOURCE OF SAMPLE

Location

METALS & INORG/ORGANICS	RESULTS *	MCL **	COMMENTS
Arsenic		0.05	
Barium		0.10	
Cadmium		0.01	
Chromium		0.05	
Copper		0.05	
Fluoride		0.874	
Lead		0.05	
Manganese		0.002	
Sodium	LO.002	50.00	
Selenium		0.01	
Silver		0.05	
Zinc		1.00	
Nickel			
Chlordane			

* mg/l unless specified

** Maximum Contaminant Level

< = Less Than

TNTC= Too Numerous To Count

Henry J. Pielichowski
Tech. Lab. Supervisor

[Signature]

P & P LABORATORIES, INC.
ENVIRONMENTAL & CLINICAL TOXICOLOGY
2025 Woodlynne Avenue
Woodlynne, NJ 08107
(609) 962-6611
DEP # 04479

WATER POTABILITY ANALYSIS

CLIENT :

Monroe Twp MUA
372 S Main Street
Williamstown, NJ 08094

CORKERY LANE
Well #7

SAMPLE NO.
DATE COLLECTED

8421

COLLECTED BY : P & P Lab.

TIME 11:52

DATE RECEIVED

1/28/83

TIME 15:00

SOURCE OF SAMPLE

Location

METALS & INORG/ORGANICS

RESULTS *

MCL **

COMMENTS

Arsenic

0.05

Barium

0.10

Cadmium

0.01

Chromium

0.05

Copper

0.05

Fluoride

0.8-4.0

Lead

0.05

Manganese

0.002

Sodium

40,002

50.00

Selenium

0.01

Silver

0.05

Zinc

1.00

Nickel

Chlordane

* mg/l unless specified

** Maximum Contaminant Level

< = Less Than

TNTC= Too Numerous To Count

Henry J. Pielichowski
Tech. Lab Supervisor

P & P LABORATORIES, INC.
 ENVIRONMENTAL & CLINICAL TOXICOLOGY
 211 White Horse Pike
 Audubon, NJ 08106
 (609) 547-8421
 DEP # 04479

CERTIFICATE OF ANALYSIS
 =====

IDENTIFICATION

name...: Monroe Twp M.U.A.
 address...: 372 South Main Street
 Williamstown, NJ 08094
 ID #...: 7932

SAMPLE SOURCE

source...: McDonald's
 Men's Room Sink
 collection...: 12/28/87 13:00
 received...: 12/28/87 13:45
 completion...: 12/29/87
 collected by...: P & P Lab

RESULTS (mg/l unless specified)

TEST PARAMETER	RESULTS	TEST PARAMETER	RESULTS
BOD(5)		Total Alkalinity	
COD		Chlorine Demand	
TDC		Chlorine Residual	
Suspended Solids		Chlorides	
Total Solids		Petro-Hydrocarbons	
T. Diss. Solids		Hardness as CaCO3	
Sett. Solids(ml/l)		Aluminum	
pH (Units)		Antimony	
Phenols.(ug/l)		Barium	
Cyanide(Total)		Cadmium	
Cyanide(Free)		Calcium	
Fluoride		Chromium (Tot)	
ABS/LAS(mg/l LAS)		Chromium (Hex)	
Oil & Grease		Copper	
TK Nitrogen as N		Iron	
Ammonia as N		Lead	
Org. Nitrogen as N		Magnesium	
Nitrate - N		Manganese	
Nitrite - N		Mercury	
T. Phosphate (P)		Nickel	
D. Phosphate (P)		Potassium	
Sulfate		Selenium	
Sulfite			
Color		Zinc	
Turbidity(NTU)		Fecal Coliform #	
Conduct.(umohms)		Total Coliform #	
Temperature C-deg.			
Langelier Index			

* col/100 ml

Henry J. Pielichowski
 Tech Lab Supervisor

Henry Pielichowski

Customer Information
Co. **Monroe MUA**
Address **Williamstown, N.J.** Phone _____
Sample drawn by **A..** Date **12/5/85** Time **1:15pm**
From **Corkery's Lane - Well #7**

CHEMICAL


Test	Quan.	Meth.	Tech.	Date/Time
Acidity				
Alkalinity				
Aluminum				
Ammonia				
Antimony				
Arsenic				
Acid Extr.				
Barium				
BOD (5 day)				
Bromides				
Bismuth				
Base-Neutral Extr.				
Cyanide				
Chlorine				
Chlorides				
Cadmium				
Calcium				
Carbon Dioxide				
Cesium				
COD				
Chromium				
Cobalt				
Color				
Copper				
Density				
D. Oxygen				
Detergents ABS/LAS				
Fluorides	less than 0.05mg/l			
Fungicides				
Hardness				
Hydrogen Sul.				
Herbicides				
Iron				
Iodine				
Iodide				
Kjeldahl N				
Lanthan				

Test	Quan.	Meth.	Tech.	Date/Time
Lead				
Lithium				
Magnesium				
Manganese				
Mercury				
Molybdenum				
Moisture				
Nickel				
Nitrate				
Nitrite				
Odor				
Oils & Grease				
Pesticides & PCB's				
Petro Hydrocarbons				
Phenols				
Phosphate				
Phosphorus				
Potassium				
Platinum				
Selenium				
Silver				
Sulfate				
Sulfite				
Sulfide				
Sodium				
Silica				
S. Matter				
THM				
Thallium				
Turbidity				
Taste				
T. Solids				
TDS				
TOC				
Vanadium				
Volatile Org.				
Volatile Solids				
Zinc				
Zirconium				

BACTERIOLOGICAL

Test	Dil.	Total	Meth.	Tech.	Date/Time
T. Cells					
T. Coliform					

Test	Dil.	Total	Meth.	Tech.	Date/Time
F. Coliform					
F. Strep					

Remarks _____

Bruce Greenwald, Lab Mgr.

Customer Information

Co. Monroe MUA
 Address Williamstown, N.J. Phone _____
 Sample drawn by A.. Date 12/5/85 Time 1:15pm
 From Corkery's Lane - Well #7

CHEMICAL

Test	Quan.	Meth.	Tech.	Date/Time
Acidity				
Alkalinity				
Aluminum				
Ammonia				
Antimony				
Arsenic				
Acid Extr.				
Barium				
BOD (5 day)				
Bromides				
Bismuth				
Base-Neutral Extr.				
Cyanide				
Chlorine				
Chlorides				
Cadmium				
Calcium				
Carbon Dioxide				
Cesium				
COD				
Chromium				
Cobalt				
Color				
Copper				
Density				
D. Oxygen				
Detergents ABS/LAS				
Fluorides	less than 0.05mg/l			
Fungicides				
Hardness				
Hydrogen Sul.				
Herbicides				
Iron				
Iodine				
Iodide				
Kjeldahl N				
Lanthan				


Test	Quan.	Meth.	Tech.	Date/Time
Lead				
Lithium				
Magnesium				
Manganese				
Mercury				
Molybdenum				
Moisture				
Nickel				
Nitrate				
Nitrite				
Odor				
Oils & Grease				
Pesticides & PCB's				
Petro Hydrocarbons				
Phenols				
Phosphate				
Phosphorus				
Potassium				
Platinum				
Selenium				
Silver				
Sulfate				
Sulfite				
Sulfide				
Sodium				
Silica				
S. Matter				
THM				
Thallium				
Turbidity				
Taste				
T. Solids				
TDS				
TOC				
Vanadium				
Volatile Org.				
Volatile Solids				
Zinc				
Zirconium				

BACTERIOLOGICAL

Test	Dil.	Total	Meth.	Tech.	Date/Time
T. Cells					
T. Coliform					

Test	Dil.	Total	Meth.	Tech.	Date/Time
F. Coliform					
F. Strep					

Remarks _____



Bruce Greenwald, Lab Mgr.

Customer Information
Co. **Monroe MUA**
Address **Williamstown, N.J.** Phone _____
Sample drawn by **A.L.** Date **12/5/85** Time **1:23pm**
From **Well #6 Lake Ave.**

CHEMICAL


Test	Quan.	Meth.	Tech.	Date/Time
Acidity				
Alkalinity				
Aluminum				
Ammonia				
Antimony				
Arsenic				
Acid Extr.				
Barium				
BOD (5 day)				
Bromides				
Bismuth				
Base-Neutral Extr.				
Cyanide				
Chlorine				
Chlorides				
Cadmium				
Calcium				
Carbon Dioxide				
Cesium				
COD				
Chromium				
Cobalt				
Color				
Copper				
Density				
D. Oxygen				
Detergents ABS/LAS				
Fluorides	less than 0.05mg/l			
Fungicides				
Hardness				
Hydrogen Sul.				
Herbicides				
Iron				
Iodine				
Iodide				
Kjeldahl N				
Lanthan				

Test	Quan.	Meth.	Tech.	Date/Time
Lead				
Lithium				
Magnesium				
Manganese				
Mercury				
Molybdenum				
Moisture				
Nickel				
Nitrate				
Nitrite				
Odor				
Oils & Grease				
Pesticides & PCB's				
Petro Hydrocarbons				
Phenols				
Phosphate				
Phosphorus				
Potassium				
Platinum				
Selenium				
Silver				
Sulfate				
Sulfite				
Sulfide				
Sodium				
Silica				
S. Matter				
THM				
Thallium				
Turbidity				
Taste				
T. Solids				
TDS				
TOC				
Vanadium				
Volatile Org.				
Volatile Solids				
Zinc				
Zirconium				

BACTERIOLOGICAL

Test	Dil.	Total	Meth.	Tech.	Date/Time
T. Cells					
T. Collform					

Test	Dil.	Total	Meth.	Tech.	Date/Time
F. Collform					
F. Strep					

Remarks _____

Bruce Greenwald, Lab Mgr.

Quality Control Laboratory and Environmental Support Alliance

243 White Horse Pike
Audubon, New Jersey 08106

"Certified Test
DE 104002

Laboratory"
104002

609-428-1303

609-296-7

Lab. Information

Analysis #

E 8531

Date rec'd at lab

12/5/85 T 2:45pm

By

Date rec'd by Tech.

T

By

Date analyses started

T

Date analyses comp.

T

Customer Information

Co. Monroe MUA

Address Williamstown, N.J.

Phone

Sample drawn by A.L. Date 12/5/85 Time 1:23pm

From Well #6 Lake Ave.

CHEMICAL

Test	Quan.	Meth.	Tech.	Date/Time
Acidity				
Alkalinity				
Aluminum				
Ammonia				
Antimony				
Arsenic				
Acid Extr.				
Barium				
BOD (5 day)				
Bromides				
Bismuth				
Base-Neutral Extr.				
Cyanide				
Chlorine				
Chlorides				
Cadmium				
Calcium				
Carbon Dioxide				
Cesium				
COD				
Chromium				
Cobalt				
Color				
Copper				
Density				
D. Oxygen				
Detergents ABS/LAS				
Fluorides	less than 0.05mg/l			
Fungicides				
Hardness				
Hydrogen Sul.				
Herbicides				
Iron				
Iodine				
Iodide				
Kjeldahl N				
Lanthan				

Test	Quan.	Meth.	Tech.	Date/Time
Lead				
Lithium				
Magnesium				
Manganese				
Mercury				
Molybdenum				
Moisture				
Nickel				
Nitrate				
Nitrite				
Odor				
Oils & Grease				
Pesticides & PCB's				
Petro Hydrocarbons				
Phenols				
Phosphate				
Phosphorus				
Potassium				
Platinum				
Selenium				
Silver				
Sulfate				
Sulfite				
Sulfide				
Sodium				
Silica				
S. Matter				
THM				
Thallium				
Turbidity				
Taste				
T. Solids				
TDS				
TOC				
Vanadium				
Volatile Org.				
Volatile Solids				
Zinc				
Zirconium				

BACTERIOLOGICAL

Test	Dil.	Total	Meth.	Tech.	Date/Time
T. Cells					
T. Coliform					

Test	Dil.	Total	Meth.	Tech.	Date/Time
F. Coliform					
F. Strep					

Remarks

Bruce Greenwald, Lab Mgr.

Quality Control Laboratory and Environmental Support Alliance

243 White Horse Pike
Audubon, New Jersey 08106

"Certified Test
DE

Laboratory"
04002

609-428-1303

609-296-7

Lab. Information
Analysis #

E 8533

Date rec'd at lab **12/5/85 T 2:45pm**

By _____

Date rec'd by Tech. _____ T _____

By _____

Date analyses started _____ T _____

Date analyses comp. _____ T _____

Customer Information

Co. **Monroe MIA**

Address **Williamstown, N.J.** Phone _____

Sample drawn by **A.L.** Date **12/5/85** Time **1:10pm**

From **Well #5, Water Street, (restroom tap)**

CHEMICAL

Test	Quan.	Meth.	Tech.	Date/Time
Acidity				
Alkalinity				
Aluminum				
Ammonia				
Antimony				
Arsenic				
Acid Extr.				
Barium				
BOD (5 day)				
Bromides				
Bismuth				
Base-Neutral Extr.				
Cyanide				
Chlorine				
Chlorides				
Cadmium				
Calcium				
Carbon Dioxide				
Cesium				
COD				
Chromium				
Cobalt				
Color				
Copper				
Density				
D. Oxygen				
Detergents ABS/LAS				
Fluorides	less than 0.05mg/l			
Fungicides				
Hardness				
Hydrogen Sul.				
Herbicides				
Iron				
Iodine				
Iodide				
Kjeldahl N				
Lanthan				


Test	Quan.	Meth.	Tech.	Date/Time
Lead				
Lithium				
Magnesium				
Manganese				
Mercury				
Molybdenum				
Moisture				
Nickel				
Nitrate				
Nitrite				
Odor				
Oils & Grease				
Pesticides & PCB's				
Petro Hydrocarbons				
Phenols				
Phosphate				
Phosphorus				
Potassium				
Platinum				
Selenium				
Silver				
Sulfate				
Sulfite				
Sulfide				
Sodium				
Silica				
S. Matter				
THM				
Thallium				
Turbidity				
Taste				
T. Solids				
TDS				
TOC				
Vanadium				
Volatile Org.				
Volatile Solids				
Zinc				
Zirconium				

BACTERIOLOGICAL

Test	Dil.	Total	Meth.	Tech.	Date/Time
T. Cells					
T. Colliform					

Test	Dil.	Total	Meth.	Tech.	Date/Time
F. Colliform					
F. Strep					

Remarks _____



Bruce Greenwald, Lab Mgr.

Quality Control Laboratory and Environmental Support Alliance

243 White Horse Pike
Audubon, New Jersey 08106

"Certified Test
DEP

"Laboratory"
04002

609-428-1303

609-296-79

Lab. Information

E 8533

Analysis #

Date rec'd at lab 12/5/85 T 2:45pm

Customer Information

Co. Monroe MUA

Address Williamstown, N.J. Phone

Sample drawn by A.L. Date 12/5/85 Time 1:10pm

From Well #5, Water Street, (restroom tap)

By

Date rec'd by Tech. T

By

Date analyses started T

Date analyses comp. T

CHEMICAL

Test	Quan.	Meth.	Tech.	Date/Time
Acidity				
Alkalinity				
Aluminum				
Ammonia				
Antimony				
Arsenic				
Acid Extr.				
Barium				
BOD (5 day)				
Bromides				
Bismuth				
Base-Neutral Extr.				
Cyanide				
Chlorine				
Chlorides				
Cadmium				
Calcium				
Carbon Dioxide				
Cesium				
COD				
Chromium				
Cobalt				
Color				
Copper				
Density				
D. Oxygen				
Detergents ABS/LAS				
Fluorides	less than 0.05mg/l			
Fungicides				
Hardness				
Hydrogen Sul.				
Herbicides				
Iron				
Iodine				
Iodide				
Kjeldahl N				
Lanthan				


Test	Quan.	Meth.	Tech.	Date/Time
Lead				
Lithium				
Magnesium				
Manganese				
Mercury				
Molybdenum				
Moisture				
Nickel				
Nitrate				
Nitrite				
Odor				
Oils & Grease				
Pesticides & PCB's				
Petro Hydrocarbons				
Phenols				
Phosphate				
Phosphorus				
Potassium				
Platinum				
Selenium				
Silver				
Sulfate				
Sulfite				
Sulfide				
Sodium				
Silica				
S. Matter				
THM				
Thallium				
Turbidity				
Taste				
T. Solids				
TDS				
TOC				
Vanadium				
Volatile Org.				
Volatile Solids				
Zinc				
Zirconium				

BACTERIOLOGICAL

Test	Dil.	Total	Meth.	Tech.	Date/Time
T. Cells					
T. Coliform					

Test	Dil.	Total	Meth.	Tech.	Date/Time
F. Coliform					
F. Strep					

Remarks



Bruce Greenwald, Lab Mgr.

P & P LABORATORIES, INC.
ENVIRONMENTAL & CLINICAL TOXICOLOGY

211 White Horse Pike
Audubon, NJ 08106
(609) 547-8421
DEP # 04479

IDENTIFICATION

name : Monroe Twp M.U.A.
address : 372 South Main St.
Williamstown, NJ 08094
ID # : 5544

SAMPLE SOURCE

source : McDonalds
Men's Room Sink
received : 8/05/87 17:00

PRIMARY DRINKING WATER TESTS

PARAMETERS	RESULTS *	MCL **	COMMENTS
Arsenic	<0.05	0.05	
Barium	<0.10	0.10	
Cadmium	<0.01	0.01	
Chromium	<0.05	0.05	
Lead	<0.05	0.05	
Mercury	<0.002	0.00	
Nitrate - N	4.45	10.00	
Selenium	<0.01	0.01	
Silver	<0.05	0.05	
Fluoride	<0.01		
Sodium	25.64	50.00	

SECONDARY DRINKING WATER TESTS

PARAMETERS	RESULTS *	MCL **	COMMENTS
Hardness		250.00	
Sodium		50.00	
Odor		4 TON	
Manganese		0.05	
Foaming Agents		0.50	
Copper		1.00	
Chlorides		250.00	
Sulfate		250.00	
Zinc		1.00	
pH		5.5 - 8.5	
TDS		250.00	
Corrosivity ***		0	

* mg/l unless specified
** maximum contamination level
*** Langlier index

Henry J. Pielichowski
Tech. Lab. Supervisor

Henry Pielichowski

Quality Control Laboratory and Environmental Support Alliance

243 White Horse Pike
Audubon, New Jersey 08106

"Certified Laboratory"
DEP Lab. ID# 04002

609-428-1303 609-296-

Lab. Information
Analysis #

C 8896

Date rec'd at lab 10/1/84 T 2 P.M.

Customer Information

Co. Monroe M.U.A.

Address Williamstown, N.J.

Phone

Sample drawn by B.G. Date 10/1/84 Time 12:42 P.M.

From McDonald's - Black Horse Pike (restroom tap)

By

Date rec'd by Tech. T

By

Date analyses started T

Date analyses comp. T

CHEMICAL

Test	Quan.	Meth.	Tech.	Date/Time
Acidity				
Alkalinity				
Aluminum				
Ammonia				
Antimony				
Arsenic				
Acid Extr.				
Barium				
BOD (5 day)				
Bromides				
Bismuth				
Base-Neutral Extr.				
Cyanide				
Chlorine				
Chlorides	14mg/l			
Cadmium				
Calcium				
Carbon Dioxide				
Cesium				
COD				
Chromium				
Cobalt				
Color	1.2 color units			
Copper	less than .05mg/l			
Density				
D. Oxygen				
Detergents ABS/LAS	less than .05mg/l			
Fluorides				
Fungicides				
Hardness	44mg/l			
Hydrogen Sul.				
Herbicides				
Iron	0.06mg/l			
Iodine				
Iodide				
Kjeldahl N				
Lanthan				

Test	Quan.	Meth.	Tech.	Date/Time
Lead				
Lithium				
Magnesium				
Manganese	less than .05mg/l			
Mercury				
Molybdenum				
Moisture				
Nickel				
Nitrate				
Nitrite				
Odor	1 T.O.N.			
Oils & Grease				
Pesticides & PCB's				
Petro Hydrocarbons				
Phenols				
Phosphate				
Phosphorus				
Potassium				
Platinum				
Selenium				
Silver				
Sulfate	3mg/l			
Sulfite				
Sulfide				
Sodium	7mg/l			
Silica				
S. Matter				
THM				
Thallium				
Turbidity				
Taste				
T. Solids				
TDS				
TOC				
Vanadium				
Volatile Org.				
Volatile Solids				
Zinc	less than .05mg/l			
Zirconium				

BACTERIOLOGICAL

Test	Dil.	Total	Meth.	Tech.	Date/Time
T. Cells					
T. Coliform					

Test	Dil.	Total	Meth.	Tech.	Date/Time
F. Coliform					
F. Strep					

Remarks

Bruce Greenwald, Lab Mgr.



DELIVERY INFORMATION

PLANT DELIVERED WATER (mgd, month, year) Max <u>6/05 11/12 MGD</u> Min <u>12/05 532 MGD</u> Annual Average <u>1000 1001 MGD</u>	
BULK PURCHASES (provider, mgd) <u>NONE</u>	
BULK SALES (customer, mgd) <u>NONE</u>	
NUMBER OF SERVICES <u>4400</u>	% METERED <u>100</u>
MUNICIPALITIES SERVED (est. services in each) <u>ALL SERVICES IN MONROE TWP</u>	
	TOTAL ESTIMATED POPULATION SERVED <u>13000</u>
CURRENT/RECENT WATER RESTRICTIONS <u>NONE</u>	
NEW CONSTRUCTION (Project Numbers) <u>NONE</u>	
DISTRIBUTION MAINS: Sizing <u>4"</u> (min) to <u>10"</u> (max) Pressures <u>45</u> (min) to <u>65</u> (max) Hydrants/Flushing Program <u>YES/YES</u>	

MONITORING & REPORTING

PARAMETER(S)	FREQUENCY REQUIRED	FREQUENCY PERFORMED
Coliform	<u>1000000</u>	<u>1000000</u>
Inorganics & NA	<u>EVERY 3 YRS</u>	<u>10/1/84</u>
Nitrate	<u>EVERY 3 YRS</u>	<u>5/30/84</u>
Trihalomethanes	<u>1000000</u>	<u>1000000</u>
Organics	<u>N/A</u>	<u>N/A</u>
Turbidity	<u>N/A</u>	<u>N/A</u>
RADIOLUCIDITY	<u>EVERY 4 YRS</u>	<u>6/84</u>
SEMIANNUAL TESTS	<u>EVERY 3 YRS</u>	<u>10/84</u>
ALGAE	<u>1000000</u>	<u>1000000</u>
TOXICITY	<u>1000000</u>	<u>1000000</u>

NAME OF LABORATORY QUALITY CONTROL CERTIFICATION # CALCE
ADDRESS BUDUBEN N.Y.

COMPLIANCE EVALUATION

SOURCE DEFICIENCIES NONE NOTED

TREATMENT DEFICIENCIES NONE NOTED



COMPLIANCE EVALUATION (Continued)

STORAGE AND/OR DISTRIBUTION DEFICIENCIES THERE ARE UNDERSIZED
PIPIAS WITHIN THE SYSTEM

LICENSING, MONITORING AND/OR REPORTING DEFICIENCIES NONE NOTED

COMPLIANCE SAMPLING VIOLATIONS:

LOCATION	DATA SOURCE	PARAM	MAX CONTMNT LEVEL	RESULT	LOCATION	DATA SOURCE	PARAM	MAX CONTMNT LEVEL	RESULT

OVERALL COMPLIANCE RATING:

☒ ACCEPTABLE

☐ CONDITIONALLY ACCEPTABLE

☐ UNACCEPTABLE

NOTICE: YOU ARE REQUIRED TO INFORM THE N.J.D.E.P. IN WRITING OF YOUR ACTUAL OR INTENDED ACTIONS TO COMPLY WITH N.J.S.A. 58:12A-1 ET SEQ. VIA IMPLEMENTATION OF REMEDIAL MEASURES TO CORRECT THE DEFICIENCIES LISTED IN THIS REPORT. FAILURE TO ADEQUATELY RESPOND IN A TIMELY FASHION WILL RENDER YOU LIABLE FOR PENALTIES OF UP TO \$5,000.00 FOR EACH VIOLATION, PURSUANT TO N.J.A.C. 7:10-3.

INSPECTOR: Albert Rute
Signature

PERSON INTERVIEWED: GEORGE COSSARONE
Name

ALBERT RUTE
Name

LICENSED OPERATOR
Title

ENVIRONMENTAL INVESTIGATOR
Title

MONROE TWP. MUA
Organization

SOUTHERN
Region

Quality Control Laboratory and

ironmental Support Alliance

243 White Horse Pike
Audubon, New Jersey 08106

"Certified", Laboratory"
D 10104002

609-428-1303

609-296

Information F 430 N 4 R 7
Analysis #

Date rec'd at lab 1/23/86 2:30pm

By

Date rec'd by Tech. T

By

Date analyses started T

Date analyses comp. T

Customer Information

Co. Monroe Township MUA 0811002

Address Williamstown, N.J. Phone

Sample drawn by A.L. Date 1/23/86 Time 11:50am

From Well #4 - Washington Ave.

CHEMICAL

Test	Quan.	Meth.	Tech.	Date/Time
Acidity				
Alkalinity				
Aluminum				
Ammonia				
Antimony				
Arsenic				
Acid Extr.				
Barium				
BOD (5 day)				
Bromides				
Bismuth				
Base-Neutral Extr.				
Cyanide				
Chlorine				
Chlorides				
Cadmium				
Calcium				
Carbon Dioxide				
Cesium				
COD				
Chromium				
Cobalt				
Color				
Copper				
Density				
D. Oxygen				
Detergents ABS/LAS				
Fluorides				
Fungicides				
Hardness				
Hydrogen Sul.				
Herbicides				
Iron				
Iodine				
Iodide				
Kjeldahl N				
Lanthan				

Test	Quan.	Meth.	Tech.	Date/Time
Lead				
Lithium				
Magnesium				
Manganese				
Mercury	0.0017mg/l			
Molybdenum				
Moisture				
Nickel				
Nitrate				
Nitrite				
Odor				
Oils & Grease				
Pesticides & PCB's				
Petro Hydrocarbons				
Phenols				
Phosphate				
Phosphorus				
Potassium				
Platinum				
Selenium				
Silver				
Sulfate				
Sulfite				
Sulfide				
Sodium				
Silica				
S. Matter				
THM				
Thallium				
Turbidity				
Taste				
T. Solids				
TDS				
TOC				
Vanadium				
Volatile Org.				
Volatile Solids				
Zinc				
Zirconium				

Test	Dil.	Total	Meth.	Tech.	Date/Time
T. Cells					
T. Coliform					

BACTERIOLOGICAL
RECEIVED

Test	Dil.	Total	Meth.	Tech.	Date/Time
F. Coliform					
F. Strep					

Remarks

N.J. State Dept. of Environmental Protection
BUREAU OF POTABLE WATER

B-48

Bruce Greenwald, Lab Mgr

Quality Control Laboratory and Environmental Support Alliance

243 White Horse Pike
Audubon, New Jersey 08106

"Certified" Lab. "ory"
D. 10104002

609-428-1303 609-296

Lab Information

An 5# F 2195

Date rec'd at lab 2/27/86 4:20pm

By _____

Date rec'd by Tech. _____ T _____

By _____

Date analyses started _____ T _____

Date analyses comp. _____ T _____

Customer Information

Co. Monroe Township MUA

Williamstown, N.J.

Address _____ Phone _____

Sample drawn by A.L. Date 2/27/86 Time 11:45am

From Well #4, Washington Ave.

CHEMICAL

Test	Quan.	Meth.	Tech.	Date/Time
Acidity				
Alkalinity				
Aluminum				
Ammonia				
Antimony				
Arsenic				
Acid Extr.				
Barium				
BOD (5 day)				
Bromides				
Bismuth				
Base-Neutral Extr.				
Cyanide				
Chlorine				
Chlorides				
Cadmium				
Calcium				
Carbon Dioxide				
Cesium				
COD				
Chromium				
Cobalt				
Color				
Copper				
Density				
D. Oxygen				
Detergents				
ABS/LAS				
Fluorides				
Fungicides				
Hardness				
Hydrogen Sul.				
Herbicides				
Iron				
Iodine				
Iodide				
Kjeldahl N				
Lanthan				

Test	Quan.	Meth.	Tech.	Date/Time
Lead				
Lithium				
Magnesium				
Manganese				
Mercury	<u>.0016mg/l</u>			
Molybdenum				
Moisture				
Nickel				
Nitrate				
Nitrite				
Odor				
Oils & Grease				
Pesticides & PCB's				
Petro Hydrocarbons				
Phenols				
Phosphate				
Phosphorus				
Potassium				
Platinum				
Selenium				
Silver				
Sulfate				
Sulfite				
Sulfide				
Sodium				
Silica				
S. Matter				
THM				
Thallium				
Turbidity				
Taste				
T. Solids				
TDS				
TOC				
Vanadium				
Volatile Org.				
Volatile Solids				
Zinc				
Zirconium				

BACTERIOLOGICAL

Test	Dil.	Total	Meth.	Tech.	Date/Time	Test	Dil.	Total	Meth.	Tech.	Date/Time
T. Cells						D. Coliform					
T. Colliform						F. Strep					

Remarks _____

7 1936

N.J. State Dept. of Environmental Protection

BUREAU OF POTABLE WATER

B-49

Bruce Greenwald, Lab Mgr.

COMPLAINT INVESTIGATION

Hold for sample results file

GCHD FILE #: 96384

DWM FILE #:

MUNICIPALITY: Monroe

INVESTIGATOR: S. Weber

DATE & TIME RECEIVED referred down by Regional

DATE & TIME ASSIGNED 7-18-86

LOCATION: Env. Services Bldg

PROPERTY OWNER: Monroe Twp Bd of Ed.

ADDRESS: Clayton Ave Winstown

MAILING ADDRESS:

BLOCK _____ LOT:

RESPONSIBLE PARTY:

LOCATION TELEPHONE #:

ADDRESS:

FACILITY ID #:

NJ DEP REP:

TELEPHONE #:

COMPLAINANT: Mercury contamination in well *contact U. Comola*

NATURE OF COMPLAINT: Reported by Dutcheson Lab & Qual. Control Lab

PHOTOGRAPHS TAKEN: _____ SAMPLES: _____

FINDINGS:

7/17/86 Investigation on site revealed well to be inside 10' deep pit in Environmental Services Bldg. Well is 2" diam or angled well w/ a jet pump & galvanized water tank. Various paints & cleaning agents for school stored in building. Building is near athletic fields. Office personnel indicate agency in Elmer maintains fields. Found a 35 gal container of product called "Star Put 151 Weed Killer & Sterilant approx 10' from well pit - which has been opened (has spent on end) - manufactured by Sunshine Chem P.O. Box 767 Cherry Hill NJ 800-232-6576 contains Monuron trichloroacetate. Also present was Weed Killer - Green Death - same manuf. - Water sample collected for heavy metals + mercury from outside faucet. Note - office people indicate that spray tanks not hooked up to faucet to fill. - Site was former orchard per office personnel. - Shaker 8-28-86 - Spoke w/ Mr. Shapiro of Sunshine Chem. - Neither product of theirs contains mercury. *SDH*

DISPOSITION:

N/A
SDH 10-17-86

Supervisor Signature & Date

Investigator Signature

ATTACHMENT

B50



COUNTY OF GLOUCESTER
STATE OF NEW JERSEY
DEPARTMENT OF HEALTH
CARPENTER ST. & ALLENS LANE
WOODBURY, NEW JERSEY 08096-2699
(609) 853-3405

ROY L. BAYLOR
FREEHOLDER

ROBERT J. SMITH, M.P.H., DIRECTOR
DEPARTMENT OF HEALTH

Monroe Township Board of Health
Environmental Services Building
Academy Street
Williamstown, NJ 08094

September 3, 1986

SUBJECT: Complaint #86364
Individual Water Supply System
Environmental Services Building
Monroe Township

Enclosed is a copy of the water analysis results for the sample collected from the subject water supply on July 17, 1986. The sample was analyzed for heavy metals. The results confirm the previously found mercury concentration. The source of the mercury concentration is unknown. During our investigation the cleaning products stored in the building were noted and none indicated that they contained mercury. Additionally the company which distributes the weed killer (Sunshine Chemical) present was contacted and they confirmed that no mercury was contained in those products either.

In interviews with office personnel it was indicated that the area was an orchard in the past. It is possible the mercury originated in sprays used at that time which have now reached the water table.

Due to the excessive mercury concentration present the water should not be used for drinking or cooking. It is recommended that bottled water be provided until a permanent alternate supply can be supplied.

If you have any questions, please do not hesitate to contact this office.

Very sincerely yours,

STEVEN WEBER
Chief Sanitary Inspector

SW/aal
Enclosure

1686 300 1986



Three Hundred Years of Public Service

I. Methodology

This analysis adhered to the methods described in:

- . EPA Manual of Methods for the Analysis of Water and Wastes, 1979.

II. Analytical Results

A. Metals and Bacteria

Sample Designation

<u>Parameter</u>	<u>NAC1487</u> <u>SW860717-A</u>
Arsenic, total, mg/l	< 0.01
Barium, total, mg/l	< 0.10
Cadmium, total, mg/l	< 0.01
Chromium, total, mg/l	< 0.05
Lead, total, mg/l	< 0.05
Mercury, total, mg/l	0.0036
Selenium, total, mg/l	< 0.01
Silver, total, mg/l	< 0.01
Sodium, total, mg/l	7.5
Copper, total, mg/l	0.23
Iron, total, mg/l	0.19
Manganese, total, mg/l	0.042
Zinc, total, mg/l	< 0.05

max allowable concentration
is 0.002 mg/l

Water Analysis Field Data Sheet

Municipality <i>Monroe</i>		Reason for sample (e.g. new well)	
Owner <i>Bd of Education</i>		Phone number	
Location <i>Env. Services Bldg</i>		Mailing Address <i>Academy St Wmstown</i>	
Sample # <i>0860717A</i>	Time of Collection <i>2:00pm</i>	Date sampled <i>7/17/86</i>	Name of sampler <i>S. Weber</i>
Diagram of sample Sites (non-potable)		Sample taken from <i>outside faucet</i>	Water Temp.
		Depth of Well <i>7 2' shallow</i>	Well to Septic (type)
		Analysis requested <i>10420 Mercury + Metals</i>	
Field Comments, sampling conditions <i>sun water 10 min</i>		Received at lab Date: <i>W. B. J.</i> Time: <i>7-21-86</i> <i>11:15</i>	Lab # Analysis conducted Date: Time:

LABORATORY RESULTS

BACTERIOLOGICAL	CHEMICAL
A. MEMBRANE FILTER (colonies/100 ml.)	1. Nitrate (NO ₃ -N mg/l)
Total Coliforms:	2. pH
Fecal Coliforms:	3. Iron (mg/l)
Fecal Streptococci:	4. Manganese (mg/l)
B. MPN (most probable number/100 ml)	5. M.B.A.S. (mg/1 LAS)
Total Coliforms:	
Fecal Coliforms:	
Fecal Streptococci:	
C. Total Plate Count (colonies/ml)	Laboratory Director

DEPARTMENT OF CONSERVATION
AND ECONOMIC DEVELOPMENT
Division of Water Policy & Supply
WELL RECORD

3133.149 P
Permit No. 31-361
Application No. 729
County Gloucester

1. OWNER Monroe Township ADDRESS Williamstown, Gloucester County,
Owner's Well No. 4 SURFACE ELEVATION _____ Feet
(Above mean sea level)
2. LOCATION Washington Ave. Pumping Station
3. DATE COMPLETED 11/12/51 DRILLER A. C. Schultes & Sons, Woodbury N.J.
4. DIAMETER: Top 12" Inches Bottom 12 Inches TOTAL DEPTH 106 Feet
5. CASING: Type Blk Steel Diameter 12 Inches Length 67' 11" Feet
6. SCREEN: Type Johnson Opening .030 Diameter 12" Inches Length 41' 9" Feet
Size of .030
Range in Depth { Top 69 Feet Geologic Formation Cohansey
Bottom 106 Feet
Tail piece. Diameter None Inches Length / Feet
7. WELL FLOWS NATURALLY No Gallons per Minute at / Feet above surface
Water rises to / Feet above surface
8. RECORD OF TEST: Date 11/12/51 Yield 805 Gallons per minute
Static water level before pumping 12' 6" Feet below surface
Pumping level 32' 5" feet below surface after 24 hours pumping
Drawdown 20 Feet Specific Capacity 40.25 Gals. per min. per ft. of drawdown
How Pumped Turbine Test Pump How measured Orifice
Observed effect on nearby wells None
9. PERMANENT PUMPING EQUIPMENT:
Type Under another contract Capacity _____ Gallons per minute
How Driven _____ Horse Power _____ R.P.M. _____
Depth of pump in well _____ Feet Depth of Foot piece in well _____ Feet
Depth of Air Line in well _____ Feet Type of Meter on Pump _____
10. USED FOR Public Supply AMOUNT { Average _____ Gallons Daily
Maximum _____ Gallons Daily
11. QUALITY OF WATER _____ Good _____ Sample: Yes / No. _____
Taste None Odor None Color clear Temperature 58 °F
12. LOG See reverse Are samples available? No
(Give details on back of sheet or on separate sheet)
13. SOURCE OF DATA Driller's Log
14. DATA OBTAINED BY A. C. Schultes Jr DATE 11/15/51

(Note: Use other side of this sheet for additional information such as log of materials penetrated, analysis of the water, sketch map, sketch of special casing arrangements, etc.)

ATTACHMENT C

Log of Well

17	0	2'	Fill	Qbt	Quaternary BRIDGETON Formation
	2'	6'	Brown Sand		
	6'	12'	Brown Sand & Stones		
	12'	17'	Gravel & Stones		
89	17'	28'	Coarse Sand & Gravel	Tch	(Cenozoic FORMATION)
	28'	33'	Fine Sand & Clay		
	33'	35'	Coarse Yellow Sand		
	35'	44'	Yellow Clay		
	44'	56'	Coarse Sand		
	56'	58'	Fine Yellow Sand		
	58'	66'	Yellow Sand		
	66'	71'	Yellow Sand		
	71'	74'	Yellow Sand		
	74'	76'	Yellow Sand		
	76'	81'	Sand & Gravel		
	81'	96'	Dark Yellow Sand Gravel		
	96'	104'	Dark Yellow Sand		
	104'	106'	Dark Brown Sand cemented		
	106'	107'	Black Muddy Clay	TKW	KIRKWOOD FORMATION

RECEIVED

NOV 13 1964

NEW YORK STATE DEPARTMENT OF
THE ENVIRONMENT
BUREAU OF LAND USE
CROTONA PARK

DEPARTMENT OF CONSERVATION
AND ECONOMIC DEVELOPMENT
DIVISION OF WATER POLICY & SUPPLY

31 33 - 1116
Permit No. 31-5035
Application No. _____
County _____

WELL RECORD

MONROE TOWNSHIP MUNICIPAL

1. OWNER UTILITIES AUTHORITY ADDRESS Township of Monroe, N. J.

Owner's Well No. 5 SURFACE ELEVATION _____ Feet
(Above mean sea level)

2. LOCATION Monroe Township, Gloucester Co.

3. DATE COMPLETED 1/18/67 DRILLER A. C. SCHULTES & SONS, INC.

4. DIAMETER: top 12 inches Bottom 8 inches TOTAL DEPTH 160 Feet

5. CASING: Type Steel Diameter 12 X 8 inches Length 121'6"
Johnson

6. SCREEN: Type Stain. Steel Size of Opening .060 Diameter 8 inches Length _____ Feet
Screen - 29'8"
Range in Depth { Top 126'11" Feet
Bottom 160 Feet
Geologic Formation _____
Cellar - 3'5"

Tail piece: Diameter _____ inches Length _____ Feet

7. WELL FLOWS NATURALLY No Gallons per Minute at _____ Feet above surface
Water rises to _____ Feet above surface

8. RECORD OF TEST: Date _____ Yield 510 Gallons per minute
Static water level before pumping _____ Feet below surface
Pumping level _____ feet below surface after _____ hours pumping
Drawdown _____ Feet Specific Capacity _____ Gals. per min. per ft. of drawdown
How Pumped Vertical Turbine Pump (test) How measured Orifice

Observed effect on nearby wells None

9. PERMANENT PUMPING EQUIPMENT:

Type Vertical Turbine Pump Mfrs. Name Worthington

Capacity _____ G.P.M. How Driven Electric H.P. _____ R.P.M. 1800

Depth of Pump in well _____ Feet Depth of Footpiece in well _____ Feet

Depth of Air Line in well _____ Feet Type of Meter on Pump _____ Size _____ inches

10. USED FOR Public Supply AMOUNT { Average _____ Gallons Daily
Maximum _____ Gallons Daily

11. QUALITY OF WATER Good (pH - 4.8) Sample: Yes _____ No _____

Taste None Odor None Color Clear Temp. _____ °F

12. LOG See Attached Are samples available? _____

(Give details on back of sheet or on separate sheet. If electric log was made, please furnish copy)

13. SOURCE OF DATA Drillers Log

14. DATA OBTAINED BY A. C. SCHULTES & SONS, INC. Date 2/4/67

(NOTE: Use other side of this sheet for additional information such as log of materials penetrated, analysis of the water, sketch map, sketch of special casing arrangements etc.)

Gravel Packed Well

GROUND	LEVEL	WELL LOG	FEET FROM GROUND SURFACE	NAME OF OWNER	
				MONROE TOWNSHIP MUNICIPAL UTILITIES AUTHORITY	
		Fill	0 TO 4'	Well No.	2
		Sand (laminated)	4 - 8'	Job No.	7194
		Sand & stones	8 - 51'	Location	Williamstown, NJ
		Sand (some laminated)	51 - 58'	Test Pumped (Hrs.)	9 1/2 hrs.
		Clay (black)	58 - 63'	Capacity G.P.M.	510
		Sand	63 - 68'	Static Level (Ground)	36' 2"
		Clay (black)	68 - 79'	Pumping Level (Ground)	82'
		Sand	79 - 84'	Specific Capacity	11
		Hardpan	84 - 85'	Diameter of Outer Casing	12"
		Sand	85 - 87'	Diameter of Inner Casing	8"
		Clay (laminated)	87 - 92'	Depth of Well (Ground)	160
		Sand/thin layers clay	92 - 116'	Depth to R. L. Nipple (Ground)	
		Sand/thin layers hardpan	116 - 126'	Depth to Gravel (Ground)	20'
		Hardpan	126 - 127'	Gravel Size	#3
		Very hard packed sand	127 - 155'	Length of Casing	12" = 121' 6"
		Pine sand	155 - 157'	Length of Casing	8" = 126' 11"
		Clay	157 - 160'	Underream Size	32
				Type of Screen	Johnson 2/8
				Size of Screen (Dia.)	8" I.D.
				Top Screen Fitting	Coupling
				Bottom Screen Fitting	Plug
				Slot Size	#60
				Blank	#40
				Bags of Cement	100
				Drilling Machine	1250
				Date Well Completed	1/13/66
				Driller	Hammond

DEPARTMENT OF CONSERVATION
AND ECONOMIC DEVELOPMENT
DIVISION OF WATER POLICY & SUPPLY

31-33-14721
Permit No. 31-5150
Application No. _____
County _____

WELL RECORD

1. OWNER Violet Packing Company ADDRESS 123 Railroad Ave., Williamstown, N.J.
Owner's Well No. 31-5150 SURFACE ELEVATION 150 Feet
(Above mean sea level)
2. LOCATION 123 Railroad Ave., Williamstown, N. J.
3. DATE COMPLETED 8/15/67 DRILLER J. G. Holman
4. DIAMETER: top 8 inches Bottom 8 inches TOTAL DEPTH 143 Feet
5. CASING: Type Black iron Diameter 8 inches Length 123 Feet
6. SCREEN: Type Stainless steel ^{Size of} opening .015 diameter 8 inches Length 20 Feet
- Range in Depth { Top 115 Feet
Bottom 150 Feet
- Geologic Formation _____
- Tail piece: Diameter _____ inches Length _____ Feet
7. WELL FLOWS NATURALLY _____ Gallons per Minute at _____ Feet above surface
Water rises to _____ Feet above surface
8. RECORD OF TEST: Date 8/15/67 Yield 300 Gallons per minute
Static water level before pumping 27 Feet below surface
Pumping level 46 1/2 feet below surface after 3 hours pumping
Drawdown 20 Feet Specific Capacity 15 Gals. per min. per ft. of drawdown
How Pumped Turbine How measured Tank
Observed effect on nearby wells _____
9. PERMANENT PUMPING EQUIPMENT:
Type Submersible Turbine Mfrs. Name X Jacuzzi Bros.
Capacity 300 G.P.M. How Driven Electricity H.P. 20 R.P.M. 3500
Depth of Pump in well 65 Feet Depth of Footpiece in well 91 Feet
Depth of Air Line in well _____ Feet Type of Meter on Pump _____ Size _____ inches
10. USED FOR Industrial cooling AMOUNT { Average _____ Gallons Daily
Maximum _____ Gallons Daily
11. QUALITY OF WATER Good Sample: Yes _____ No _____
Taste _____ Odor _____ Color _____ Temp. _____ of
12. 1 Co Attached Are samples available? _____
(Give details on back of sheet or on separate sheet. If electric log was made, please furnish copy)
13. SOURCE OF DATA _____
14. DATA OBTAINED BY J. G. HOLMAN Date August 30, 1967

(NOTE: Use other side of this sheet for additional information such as log of materials penetrated, analysis of the water, sketch map, sketch of special casing arrangements etc.)

WELL RECORD AKA AVERY DRIVE TEST WELL

1. OWNER Monroe MUA ADDRESS Main St Williamstown
Owner's Well No. Monitoring Well SURFACE ELEVATION 150 Feet
(Above sea level)
Newberry Farms
2. LOCATION Left side of entrance - near first transformer
3. DATE COMPLETED _____ DRILLER Vance Skinner Company Inc.
4. DIAMETER: top 6 inches Bottom 4 inches TOTAL DEPTH 120 Feet
5. CASING: Type PVC Diameter 4 inches Length 100 Feet
6. SCREEN: Type PVC Size of Opening 030 Diameter 4 inches Length 20 Feet
Range in Depth { Top 100 Feet
Bottom 120 Feet Geologic Formation Tch
- Tail piece: Diameter _____ inches Length _____ Feet
7. WELL FLOWS NATURALLY No Gallons per Minute at _____ Feet above surface
Water rises to _____ Feet above surface
8. RECORD OF TEST: Date May 24 1978 Yield 65 Gallons per minute
Static water level before pumping 116 1/2 Feet below surface
Pumping level 30 1/2 feet below surface after 24 hours pumping
Drawdown 14 Feet Specific Capacity 4.6 Gals. per min. per ft. of drawdown
How Pumped Submersible How measured 4 x 2 1/2 Orifice
Observed effect on nearby wells None checked.
9. PERMANENT PUMPING EQUIPMENT:
Type Submersible Mfr. Name Bucks
Capacity 60 G.P.M. How Driven Electric H.P. 3 R.P.M. 3450
Depth of Pump in well 65 Feet Depth of Footpiece in well None Feet
Depth of Air Line in well 65 Feet Type of Meter on Pump None Size _____ inches
10. USED FOR Monitoring Water Quality AMOUNT { Average _____ Gallons Daily
Maximum _____ Gallons Daily
11. QUALITY OF WATER Good Sample: Yes ☒ No. _____
Taste No Odor No Color No Temp. _____ °F
12. LOG See attached sheet Are samples available? No
(Give details on back of sheet or on separate sheet. If electric log was used, please furnish copy)
13. SOURCE OF DATA Well Records Vance Skinner Company
14. DATA OBTAINED BY W.V. Skinner Date 1-22-79

(NOTE: Use other side of this sheet for additional information such as log of materials penetrated, analysis of the water, sketch map, sketch of special casing arrangements etc.)

Date well completed 4-2-10 Block _____
 First water line _____ Lot _____
 Water line in well _____ Index 31-3-182
 Screen—Length & Material _____ Permit No. 31-13734
 Type of Seal—Top & Bottom N/A Electric Log yes
 Pump used with well 3 HP Sub Water Analysis yes

0	60	120	180
Gravel - $1\frac{1}{2}$ "		slightly clayey	
orange sandy & clayey	slightly clayey		
		more clayey	
10	70	130	190
	$1\frac{1}{2}$ "	grading to	
	more clayey		
20	80	140	200
Sand	clay	clay	
pale grayish orange f to med gr.	gravel brown silty & sandy	silty & sandy	
	more sandy	grayish orange	
30	90	150	210
	Sand	sandy clay	
coarser	grayish orange		
40	100	160	220
	silty & slightly clayey		
slightly clayey		Bottom of Hole	
	uniform med		
"J. stone" (6")	gr clean sand.		
50	110	170	230
pale grayish orange sand.			
$1\frac{1}{2}$ "	$1\frac{1}{2}$ "	grayish orange	
slightly clayey			



Betz • Converse • Murdoch • Inc.

One Plymouth Meeting Mall • Plymouth Meeting, Pennsylvania 19462 • Telephone 215 • 825-3800

FOR: Vance Skinner
P.O. Box 2
Vineland, NJ 08360

DATE OF REPORT: 6/9/78
PAGE: 1 of 2

ATTENTION: Mr. William Skinner

SAMPLES DATED: not dated
RECEIVED: 5/26/78

THE FOLLOWING REPORT COVERS THE LABORATORY EXAMINATION OF SAMPLES DELIVERED TO OUR LABORATORIES. PLEASE DO NOT HESITATE TO CONTACT US SHOULD ANY QUESTIONS ARISE.

VERY TRULY YOURS,


Pamela J. Barr
CUSTOMER SERVICES SUPERVISOR

	Monroe MVA Monitor. Well	Monroe Distant Site				
Total Solids, mg/l	143					
Chloride as Cl, mg/l	30					
Methyl Orange Alkalinity as CaCO ₃ , mg/l	5					
Sodium as Na, mg/l	15.0					
Iron as Fe, mg/l	0.005					
Manganese, Mn, mg/l	0.051					
Nitrate as N, mg/l	1.45					
Sulfate as SO ₄ , mg/l	3					
Turbidity, Nephelometric Units	0.48					
pH	4.8					
Mercury as Hg, mg/l	0.00152	0.00026				
Carbonate Hardness, ppm	40					
Non-carbonate Hardness ppm	0					

FOR: Vance Skinner
P.O. Box 2
Vineland, NJ 08360

DATE OF REPORT: 6/9/78

PAGE: 2 of 2

Attn: Mr. William Skinner

SAMPLES DATED: not dated
RECEIVED: 5/26/78

[illegible]

(609) 468-3396

VAL ASSOCIATES

P.O. Box 167

Plating Analysis & Consulting
For Electronics Industry
Water, Air & Soil Analysis

PHILIP V. DATZ, JR.
Chemist

748 Ridge Drive Road
Mantua, New Jersey 08051
June 9, 1978

Water Analysis Taken May 26 th

Monitor Well

Carbonate Hardness	- 16 ppm
Non- Carbonate	- 28 ppm
Total Hardness	- 44 ppm
Calcium Hardness	- 16 ppm
Chloride	- 36 ppm
Alkalinity	- P-o M-16 ppm
Carbonic Acid	- 10.0 ppm
Iron	- .03 ppm
Manganese	- .11 ppm
Nitrate	- As N o3 41.4 ppm
Sulfate	- 6.0 ppm
Turbidity	- 2 Formazine Turbidity Units
Sodium	- 23.8 ppm
Total Solids	- 150 ppm
pH	- 4.0

Sample Taken 5/26/78

Mercury Filtered ~~0.4 ppm~~
PPB

Sample Taken 5/26/78

Mercury Unfiltered - .4 ppm
PPB

(609) 468-3396

VAL ASSOCIATES

P.O. Box 162

Plating Analysis & Consulting
For Electronics Industry
Water, Air & Soil Analysis

PHILIP V. DATZ, JR.
Chemist

748 Ridge Drive Road
Mantua, New Jersey 08051
June 9, 1978

Water Analysis Samples

Location - Hubert Boulevard

5/26/78 Sample Taken

5/26/78 Sample Taken

Mercury Filtered - .4 ppb

mercury Unfiltered - .4 ppb

5/8/76 Sample Taken

5/10/76 Sample Taken (Well # 4)

Mercury - .35 ppb

Mercury - 1.6 ppb

WELL RECORD

1. OWNER Monroe MUA ADDRESS Main St. Williams town.
 Owner's Well No. Pilot Well (Foil Well 7) SURFACE ELEVATION 2 150 Feet
 (Above mean sea level)
2. LOCATION Corkery Lane.
Near Water Tower
3. DATE COMPLETED _____ DRILLER Vance Skinner Company Inc.
4. DIAMETER: top 6 inches Bottom 6 inches TOTAL DEPTH 140 Feet
5. CASING: Type Steel Diameter 6 inches Length 120 Feet
6. SCREEN: Type Wire Size of Opening 0.50 Diameter 6 inches Length 20 Feet
 Range in Depth { Top 120 Feet
 Bottom 140 Feet Geologic Formation Tch
- Tail piece Diameter None inches Length _____ Feet
7. WELL FLOWS NATURALLY No Gallons per Minute at _____ Feet above surface
 Water rises to _____ Feet above surface
8. RECORD OF TEST: Date 4/19/78 Yield 340 Gallons per minute
 Static water level before pumping 32' Feet below surface
 Pumping level 52.7 feet below surface after 72 hours pumping
 Drawdown 18.7 Feet Specific Capacity 18 Gals. per min. per ft. of drawdown
 How Pumped Turbine How measured 6x4 Orifice
 Observed effect on nearby wells Observation Well 50' distant 38.8'
9. PERMANENT PUMPING EQUIPMENT:
 Type Turbine Mfrs. Name Worthington
 Capacity 750 G.P.M. How Driven Electric H.P. _____ R.P.M. _____
 Depth of Pump in well _____ Feet Depth of Footpiece in well _____ Feet
 Depth of Air Line in well _____ Feet Type of Motor on Pump _____ Size _____ inches
10. USED FOR Public Supply AMOUNT { Average _____ Gallons Daily
 Maximum _____ Gallons Daily
11. QUALITY OF WATER Good Sample: Yes ✓ No. _____
 Taste Na Odor Na Color Na Temp. _____ °F
12. LOG See attached Sheet Are samples available? _____
 (Give details on back of sheet or on separate sheet. If electric log was made, please furnish copy)
13. SOURCE OF DATA Well Records - Vance Skinner Company
14. DATA OBTAINED BY W.V. Skinner Date 1-23-79

(NOTE: Use other side of this sheet for additional information such as log of materials penetrated, analysis of the water, the log map, sketch of special casing arrangements etc.)

0	60	120	180
Clay - brn	grayish orange	pale brown	
sandy f to	uniform f. to	med coarse	
med. gr. w/	mod. gr. qtzose	qr. sandl.	
thin layer of	sand. occ.		
gravel.	layer of coarse		
	gravel.		
10	70	130	190
	pale grayish	occ. thin	
	orange	strip gray	
Sandl - white		clay.	
f. to mod gr.			
w/ thin layers	clayey		
20 white clay.	80	140	200
grayish orange	very clayey	"erry" f. silty	
clayey	f. sandl -	clayey sandl.	
		micaceous	
sandy gravel	f. gr. pale	clayey yellowish	
	yellowish	brown	
	orange.		
30	90	150	210
slightly clayey	Clay -		
grayish orange			
non-uniform	Dark yellowish	v.f. silty f	
v.f. to coarse	brown - w/	clay sandl -	
gr. qtzose sandl	strips of med	micaceous	
	gray. silty		
	f. sandy clay		
40	100	160	220
dark yellowish			
orange - more	clayey - to	more clayey	
uniform	a dusky yellowish		
	brown. - strips		
	of lighter color		
	clay.		
50	110	170	230
moderate	Sandl -		
yellowish brown	pale yellowish	Bottom of hole	
non-uniform	brown - uniform		
f. to coarse gr	Coarse gr -		
qtzose sandl	angular -		
angular			

WELL RECORD

1. OWNER MONROE TOWNSHIP ADDRESS 372 S. Main Street, Williamstown, NJ
Owner's Well No. 7 SURFACE ELEVATION _____ Feet
(Above mean sea level)
2. LOCATION CORKERY LANE, WILLIAMSTOWN, NJ
3. DATE COMPLETED 2/16/79 DRILLER A. C. SCHULTES & SONS, INC.
4. DIAMETER: top 20 inches Bottom 12 inches TOTAL DEPTH 147' Feet
5. CASING: Type Steel Diameter 12 x 20 inches Length XXX' Feet
6. SCREEN: Type S.S. Size of Opening .045 Diameter 12" inches Length 29' Feet
Range in Depth { Top _____ Feet
Bottom _____ Feet Geologic Formation _____
Tail piece: Diameter _____ inches Length _____ Feet
7. WELL FLOWS NATURALLY 805 Gallons per Minute at _____ Feet above surface
Water rises to _____ Feet above surface
8. RECORD OF TEST: Date 2/16/79 Yield 805 Gallons per minute
Static water level before pumping 33'-9" Feet below surface
Pumping level 63'-13" feet below surface after 24 hours pumping
Drawdown 29'-43" Feet Specific Capacity 25.1 Gals. per min. per ft. of drawdown
How Pumped VTP How measured ORIFICE
Observed effect on nearby wells N/A
9. ~~TEMPORARY~~ PUMPING EQUIPMENT:
Type VTP Mfrs. Name WORTHINGTON
Capacity 800 G.P.M. How Driven Electric Motor P. 60 R.P.M. 1800
Depth of Pump in well 90 Feet Depth of Footplate in well N/A Feet
Depth of Air Line in well 90 Feet Type of Meter on Pump N/A Size _____ inches
10. USED FOR Municipal Use AMOUNT { Average _____ Gallons Daily
Maximum _____ Gallons Daily
11. QUALITY OF WATER SATISFACTORY Sample: Yes X No. _____
Taste None Odor None Color Clear Temp. 70 °F
12. LOG ELECTRIC LOG Are samples available? NO
(Give details on back of sheet or on separate sheet. If electric log was made, please furnish copy)
13. SOURCE OF DATA DRILLER'S LOG
14. DATA OBTAINED BY A.C. SCHULTES & SONS, INC. Date 9/28/79

(NOTE: Use other side of this sheet for additional information such as log of materials penetrated, analysis of the water, sketch map, sketch of special casing arrangements etc.)

WATER WELL RECORD

Completed record must be returned 60 days after completion of well
(N.J.S.A. 58:4A-14 - 15)

2. CHECK ☒ CORRECT 3. NO. OF REVISIONS: 0000000000

COUNTY		TOWNSHIP		LOT	BLOCK	PERMIT NO.
Gloucester		Monroe Twp. Wilkesbarn.		25A1	54	31-16229
OWNER (LAST NAME FIRST)		ADDRESS		DATE COMPLETED		
Bernhard Lillian		455 Clayton Rd.		DAY 29 MO. 9 YR. 2		

LOG OF OVERBURDEN AND BEDROCK MATERIALS (SEE INSTRUCTIONS)

[illegible]

CASING & OPEN HOLE RECORD

INSIDE DIAM. INCHES	MATERIAL	WALL THICKNESS INCHES	DEPTH FEET	
			FROM	TO
2	<input checked="" type="checkbox"/> STEEL <input type="checkbox"/> PLASTIC <input type="checkbox"/> OTHER <input type="checkbox"/> OPEN HOLE	040	3	3 1/2
	<input type="checkbox"/> STEEL <input type="checkbox"/> PLASTIC <input type="checkbox"/> OTHER <input type="checkbox"/> OPEN HOLE			
	<input type="checkbox"/> STEEL <input type="checkbox"/> PLASTIC <input type="checkbox"/> OTHER <input type="checkbox"/> OPEN HOLE			

BOREHOLE RECORD

SCREEN	SIZE OF OPENING (SLOT NO.)	DIAMETER	LENGTH
	8	2 INCHES	4 FEET
	MATERIAL AND TYPE	DEPTH TO TOP OF SCREEN	
	steel bars steel	34	FEET

SEIVE ANALYSIS YES ☐ NO ☐
GRAVEL PACK YES ☐ NO ☐ SIZE

PLUGGING & SEALING RECORD

DEPTH SET AT - FEET		MATERIAL AND TYPE (CEMENT GROUT, LEAD PACKER, ETC.)
FROM	TO	
0	10	Cement

LOCATION OF WELL

STANDARD FORM NO. 64 15
REPLACEMENT WEIL- only

PUMPING TEST

PUMPING TEST	PUMPING TEST METHOD <input type="checkbox"/> PUMP <input type="checkbox"/> AIRLIFT <input type="checkbox"/> SAILER		PUMPING RATE G.P.M. _____		DURATION OF PUMPING ____ HOURS _____ MIN.	
	STATIC LEVEL	WATER LEVEL END OF PUMPING	WATER LEVELS DURING			<input type="checkbox"/> PUMPING <input type="checkbox"/> RECOVERY
	9 FEET	FEET	15 MINUTES	30 MINUTES	45 MINUTES	60 MINUTES
	IS FLOWING WELL RATE	FEET	FEET	FEET	FEET	FEET
	PUMP INTAKE BEYOND			WATER AT END OF TEST		
RECOMMENDED PUMP TYPE <input checked="" type="checkbox"/> SURFACE <input type="checkbox"/> DEEP		RECOMMENDED PUMP SETTING		RECOMMENDED PUMPING RATE		
TRANSMISSIBILITY PLOT		YES <input type="checkbox"/> NO <input type="checkbox"/>				

FINAL
STATUS
OF WELL

FINAL STATUS OF WELL	<input checked="" type="checkbox"/> WATER SUPPLY	<input type="checkbox"/> ABANDONED, INSUFFICIENT SUPPLY
	<input type="checkbox"/> OVERPUMPING WELL	<input type="checkbox"/> ABANDONED, POOR QUALITY
	<input type="checkbox"/> TEST ONLY	<input type="checkbox"/> UNFINISHED
	<input type="checkbox"/> RECHARGE STUDY	
WATER USE	<input checked="" type="checkbox"/> DOMESTIC	<input type="checkbox"/> INDUSTRIAL
	<input type="checkbox"/> AGRICULTURE	<input type="checkbox"/> MUNICIPAL
	<input type="checkbox"/> PUBLIC SUPPLY	<input type="checkbox"/> PUBLIC SUPPLY
	<input type="checkbox"/> OTHER	<input type="checkbox"/> OTHER

DEPARTMENT OF ENVIRONMENTAL PROTECTION
DIVISION OF WATER RESOURCES

Permit No. 31-11709

Application No. _____

County _____

WELL RECORD

1. OWNER Veterans Administration ADDRESS Newark, N. J.
Owner's well No. 62 SURFACE ELEVATION 140 Feet
(Above mean sea level)
2. LOCATION Hurffville-Cross Keys Road Monroe Township
3. DATE COMPLETED 8-18-77 DRILLER M. J. Dechamps #1065
4. DIAMETER: top 1 1/2 inches Bottom 1 1/2 inches TOTAL DEPTH 55 Feet
5. CASING: Type Galv. Steel Diameter 1 1/2 inches Length 50 Feet
6. SCREEN: Type S. Steel Size of Opening 60 Diameter 1 1/2 inches Length 5 Feet
Range in Depth { Top _____ Feet
Bottom _____ Feet
Geologic Formation Sand
7. WELL FLOWS NATURALLY _____ Gallons per Minute at _____ Feet above surface
Water rises to _____ Feet above surface
8. RECORD OF TEST: Date 8-18-77 Yield 152 Gallons per minute
Static water level before pumping 15' Feet below surface
Pumping level 15 feet below surface after 2 hrs. hours pumping
Drawdown _____ Feet Specific Capacity _____ Gals. per min. per ft. of drawdown
How Pumped Dewatering pump How measured 5 gal. container
Observed effect on nearby wells None
9. PERMANENT PUMPING EQUIPMENT:
Type S. M. Jet Mfr. Name Nyers
Capacity 7 G.P.M. How Driven El. Motor H.P. 1/2 R.P.M. 3450
Depth of Pump in well _____ Feet Depth of Footpiece in well _____ Feet
Depth of Air Line in well _____ Feet Type of Motor on Pump _____ Size _____ inches
10. USED FOR Domestic AMOUNT { Average 450 Gallons Daily
Maximum 900 Gallons Daily
11. QUALITY OF WATER Good Sample: Yes X No _____
Taste None Odor None Color Clear Temp. 55 °F
12. LOG _____ Are samples available? _____
(Give details on back of sheet or on separate sheet. If electric log was made, please furnish copy)
13. SOURCE OF DATA M. J. Dechamps #1065
14. DATA OBTAINED BY M. J. Dechamps Date 8-18-77

(NOTE: Use other side of this sheet for additional information such as log of materials penetrated, analysis of the water, sketch app. sketch of special casing arrangements etc.)

WELL RECORD

1. OWNER F. H. WOOD HAMES ADDRESS HADDONFIELD
Owner's Well No. _____ SURFACE ELEVATION _____ Feet
(Above mean sea level)
2. LOCATION LOT 26 BIX 54 Monroe Twp Gloucester
3. DATE COMPLETED 4-2-77 DRILLER Gls Water Pump
4. DIAMETER: top 4 inches Bottom 4 inches TOTAL DEPTH 60 Feet
5. CASING: Type Steel Diameter 4 inches Length 60 Feet
6. SCREEN: Type Denie Size of Opening _____ Diameter 4 inches Length 7 Feet
Range in Depth { Top 48 Feet
Bottom 55 Feet Geologic Formation SAND
Tail piece: Diameter 4 inches Length 5 Feet
7. WELL FLOWS NATURALLY _____ Gallons per Minute at _____ Feet above surface
Water rises to _____ Feet above surface
8. RECORD OF TEST: Date 4-2-77 Yield 10 Gallons per minute
Static water level before pumping _____ Feet below surface
Pumping level 11 feet below surface after 1 hours pumping
Drawdown 6 Feet Specific Capacity _____ Gals. per min. per ft. of drawdown
How Pumped _____ How measured 1001 POINT
Observed effect on nearby wells NONE
9. PERMANENT PUMPING EQUIPMENT:
Type 1/2" Mfrs. Name MYERS
Capacity 15 G.P.M. How Driven ELEC H.P. 1/2 R.P.M. 1725
Depth of Pump in well 30 Feet Depth of Footpiece in well _____ Feet
Depth of Air Line in well _____ Feet Type of Motor on Pump CASE Size 2 Inches
10. USED FOR HOUSE AMOUNT { Average _____ Gallons Daily
Maximum _____ Gallons Daily
11. QUALITY OF WATER Good Sample: Yes _____ No _____
Taste Good Odor NONE Color SLURK Temp. 56 °F
12. LOG _____ Are samples available? _____
(Give details on back of sheet or on separate sheet. If electric log was made, please furnish copy)
13. SOURCE OF DATA _____
14. DATA OBTAINED BY Gls Water Pump Date 4-2-77

(NOTE: Use other side of this sheet for additional information such as log of materials penetrated analysis of the water, sketch map, sketch of special casing arrangements etc.)

GRAVEL AND CLAY TO- 30' - MOIST.
COARSE AND FINE YELLOW SAND TO- 60' WET

WELL RECORD

AUG 2 1978

1. OWNER Malvin Pitt ADDRESS Jones Kane Rd.Owner's Well No. _____ SURFACE ELEVATION 170 Feet
(Above mean sea level)2. LOCATION Jones Kane Rd., Williamstown, N.J. Lot 12B4 Blk 13. DATE COMPLETED Dec 15 '78 DRILLER Jack Sullivan4. DIAMETER: top 2 inches Bottom 2 inches TOTAL DEPTH 76 Feet5. CASING: Type Galv steel Diameter 2 inches Length 71 Feet6. SCREEN: Type Stainless Size of Opening 60g Diameter 2 inches Length 5 FeetRange in Depth { Top _____ Feet
Bottom _____ Feet Geologic Formation _____

Tail piece Diameter _____ inches Length _____ Feet

7. WELL FLOWS NATURALLY _____ Gallons per Minute at _____ Feet above surface

Water rises to _____ Feet above surface

8. RECORD OF TEST: Date 12/15/78 Yield 50 Gallons per minuteStatic water level before pumping 16 Feet below surface

Pumping level _____ feet below surface after _____ hours pumping

Drawdown _____ Feet Specific Capacity _____ Gals. per min. per ft. of drawdown

Now Pumped _____ Now measured _____

Observed effect on nearby wells _____

PERMANENT PUMPING EQUIPMENT:

Type SW jet Mfrs. Name GouldsCapacity 12 G.P.W. Now Driven elect H.P. 1/2 R.P.M. 3450

Depth of Pump in well _____ Feet Depth of Footpiece in well _____ Feet

Depth of Air Line in well _____ Feet Type of Motor on Pump _____ Size _____ inches

USED FOR Domestic AMOUNT { Average 250 Gallons Daily
Maximum 300 Gallons Daily11. QUALITY OF WATER Good Sample: Yes X No _____Taste none Odor none Color clear Temp. 58 °F

12. LOG _____ Are samples available? _____

(Give details on back of sheet or on separate sheet. If electric log was made, please furnish copy)

13. SOURCE OF DATA _____

14. DATA OBTAINED BY Jack Sullivan Date 5/17/80

(NOTE: Use other side of this sheet for additional information such as log of materials penetrated, analysis of the water, sketch map, sketch of special casing arrangements etc.)

DEPARTMENT OF ENVIRONMENTAL PROTECTION

Permit No. 37-1

Application No. _____

County _____

EMERGENCY REPLACEMENT WELL RECORD

1. OWNER James Elephant ADDRESS Corkery Lane Monroe Twp.
 Owner's Well No. 45 SURFACE ELEVATION 110 Feet
 (Above sea or level)
2. LOCATION Corkery Lane, Monroe Twp., N.J.
3. DATE COMPLETED 12/21/70 DRILLER W. J. DeChamps
4. DIAMETER: top 4 inches Bottom 4 inches TOTAL DEPTH 60 Feet
5. CASING: Type Steel Diameter 4 inches Length 60 Feet
6. SCREEN: Type Steel Size of Opening 1/2 inches Diameter 4 inches Length 3 Feet
- Range in Depth { Top _____ Feet
 Bottom _____ Feet Geologic Formation _____
- Tail piece: Diameter _____ inches Length _____ Feet
7. WELL FLOWS NATURALLY _____ Gallons per Minute at _____ Feet above surface
 Water rises to _____ Feet above surface
8. RECORD OF TEST: Date 12/21/70 Yield 25 Gallons per minute
 Static water level before pumping _____ Feet below surface
 Pumping level _____ feet below surface after _____ hours pumping
 Drawdown _____ Feet Specific Capacity _____ Gals. per min. per ft. of drawdown
 How Pumped Hand How measured 5 gal container
 Observed effect on nearby wells None
9. PERMANENT PUMPING EQUIPMENT:
 Type Submersible Mfrs. Name Fairbanks Morse
 Capacity _____ G.P.M. How Driven Electric H.P. 1 R.P.M. 2450
 Depth of Pump in well 2 Feet Depth of footpiece in well _____ Feet
 Depth of Air Line in well _____ Feet Type of Meter on Pump _____ Size _____ inches
10. USED FOR Water AMOUNT { Average 5500 Gallons Daily
 Maximum 36000 Gallons Daily
11. QUALITY OF WATER Good Sample: Yes _____ No _____
 Taste None Odor None Color Clear Temp. 55 °F
12. LOG Attached Are samples available? _____
 (Give details on back of sheet or on separate sheet. If electric log was made, please furnish copy.)
13. SOURCE OF DATA W. J. DeChamps
14. DATA OBTAINED BY W. J. DeChamps Date 1/10/81

(NOTE: Use other side of this sheet for additional information such as log of materials penetrated, analysis of the water, sketch map, sketch of special casing arrangements etc.)

DEPARTMENT OF ENVIRONMENTAL PROTECTION
DIVISION OF WATER RESOURCES


31-32-171 [X]
Permit No. 31-12968
Application No. _____

WELL RECORD

OWNER Donald W. McLaughlin ADDRESS 449 BlueBell Rd. Williamstown, N.J.
Owner's Well No! 148 SURFACE ELEVATION 100 Feet
(above mean sea level)
LOCATION Janvier Rd. Monroe Twp
DATE COMPLETED 10/4/78 DRILLER M. J. Dechamps
DIAMETER: top 2 inches Bottom 2 inches TOTAL DEPTH 55 Feet
CASING: Type Galv. steel Diameter 2 inches Length 50 Feet
SCREEN: Type S. Steel Size of Opening 60 Diameter 1 1/2 inches Length 5 Feet
Range in Depth Top _____ Feet
Bottom _____ Feet Geologic Formation Sand
Tail piece: Diameter _____ inches Length _____ Feet
WELL FLOWS NATURALLY _____ Gallons per Minute at _____ Feet above surface
Water rises to _____ Feet above surface
RECORD OF TEST: Date 10/4/78 Yield 23 Gallons per minute
Static water level before pumping 10 Feet below surface
Pumping level 10 ft feet below surface after 2 hours pumping
Drawdown _____ Feet Specific Capacity _____ Gals. per min. per ft. of drawdown
How Pumped Dewatering pump How measured 5 gal container
Observed effect on nearby wells _____ None
PERMANENT PUMPING EQUIPMENT:
Type S. W. Jet Mfrs. Name Fairbanks-Morse
Capacity 10 G.P.M. How Driven El. motor H.P. 1/2 R.P.M. 3450
Depth of Pump in well _____ Feet Depth of Footpiece in well _____ Feet
Depth of Air-Line in well _____ Feet Type of Meter on Pump _____ Size _____ inches
USED FOR Domestic AMOUNT Average 600 Gallons Daily
Maximum 1200 Gallons Daily
QUALITY OF WATER Good Sample: Yes X No. _____
Taste None Odor None Color Clear Temp. 55 or
LOG _____ Are samples available?
(Give details on back of sheet or separate feet. If electric log as made, please
furnish copy.)
SOURCE OF DATA M. J. Dechamps
DATA OBTAINED BY M. J. Dechamps Date 10/11/78
(Note: Use either side of this sheet for additions. Information such as log of mat-
erials penetrated, analysis of the water, sketch map, sketch of specific casing,
arrangements, etc.)

**STATE OF NEW JERSEY
DEPARTMENT OF CONSERVATION
AND ECONOMIC DEVELOPMENT**

**DIVISION OF WATER POLICY
AND SUPPLY**



SPECIAL REPORT 30

**WATER RESOURCES AND GEOLOGY OF
GLOUCESTER COUNTY, NEW JERSEY**

Prepared in Cooperation With
United States Department of the Interior
Geological Survey

1969

gravel pit near Ewan show medium- to coarse-grained sand (table 2). Downdip, the formation is generally coarser grained.

The thickness of the formation ranges from 50 feet in the outcrop area to about 160 feet in the southern part of the county. The upper part of the Kirkwood Formation dips to the southeast at about 9 to 13 feet per mile and the basal beds dip about 25 feet per mile.

The Kirkwood Formation ~~is a minor~~ aquifer in the county. Records indicate that there are a few domestic wells, 25 to 100 feet deep which yield from 10 to 50 gpm. In and near the outcrop the formation consists largely of clay, silt, and fine sand of low permeability. Although the Kirkwood Formation is thicker and more permeable in the southern part of the county, it is not tapped by wells because water is more readily available from the overlying Cohansey Sand.

The Kirkwood Formation is of hydrologic importance in Gloucester County because its large surface area can absorb precipitation which may be transmitted to the lower aquifers. Some recharge moves downdip to the more permeable parts of the Kirkwood Formation; however, much of the recharge on the outcrop is discharged to the nearby streams.

Results of chemical analyses of water from wells 16 and 26 (table 8) in the outcrop area of the Kirkwood Formation near Richwood and Turnersville show dissolved solids of 64 and 62 mg/l, iron 0.55 and 0.43 mg/l, nitrate 22 and 14 mg/l, and hardness of 28 and 20 mg/l, respectively. Because this aquifer is recharged locally and in places hydraulically connected to underlying aquifers, contamination of the shallow water-table ground-water reservoir by infiltration of sewage, industrial wastes, or other water of poor quality should be avoided in those places.

Locally, domestic and farm supplies can be developed in and near the outcrop area. Pleistocene gravel where present in appreciable thicknesses can be developed in conjunction with the Kirkwood Formation to improve well yields.

MIOCENE(?) AND PLIOCENE(?) SERIES

Cohansey Sand

Geology

The Cohansey Sand crops out in an area of about 150 square miles in Gloucester County (fig. 2). The formation is composed of fine- to coarse-grained quartzose sand, lenses of light-colored clay as much as 25 feet thick, and lenses of gravel. The sand is white, yellow, red, brown, and gray and the clays are shades of red, orange, and gray. Generally, ferruginous cemented zones are found only near contacts with the over-

lying Pleistocene deposits. The Cohansey Sand usually is composed of at least 90 percent silica with subordinate amounts of feldspar, magnetite, and ilmenite. An analysis of a sample collected in a pit at Downer shows about 94 percent fine to medium sand (table 2). The Cohansey Sand dips southeast about 11 feet per mile and ranges in thickness from a few feet in the outcrop area to 130 feet at Newfield.

The Cohansey Sand is underlain by the Kirkwood Formation and overlain unconformably by the Bridgeton Formation of Pleistocene age except in a small area along Mantua Creek east of Pitman, where it is overlain by the Cape May Formation, also of Pleistocene age.

Hydrology

The Cohansey Sand is the second most productive aquifer in the county. However, the amount of water withdrawn is small compared to the quantity potentially available; thus, the aquifer is considered almost undeveloped. Locally, there may be more than one water-bearing zone present; however, the formation is generally regarded as a hydrologic unit. In and near the outcrop area, the Cohansey Sand is hydraulically connected with the underlying Kirkwood Formation. Wells tapping the Cohansey Sand range from 25 to 130 feet deep and yield up to 800 gpm.

Artesian conditions exist locally in the Cohansey Sand because of lenses of clay which act as aquicludes for the more permeable parts of the formation. Pumping tests at Williamstown and Clayton indicate a coefficient of transmissibility of 60,000 gpd per ft and a permeability of nearly 1,000 gpd per sq ft. These figures compare favorably with those for the Raritan and Magothy Formations along the Delaware River.

Recharge to the Cohansey Sand is from precipitation on the outcrop area and ground-water movement is effected to some extent by the topography. In Gloucester County, a topographic and a hydrologic ridge trending southwest to northeast from Hardingville near the Salem County line through Glassboro to Turnersville causes ground water to move northward into Raccoon Creek, Chestnut Branch, Mantua Creek, and the south branch of Big Timber Creek. This ridge is joined by a north-south-trending ridge near Cross Keys. From the high-level intake area near Cross Keys some ground water moves south and discharges into the Great Egg Harbor River and some moves west and discharges into the Maurice River or its tributaries (fig. 9).

The Cohansey aquifer is in equilibrium, or in other words, the long-term recharge equals the long-term discharge. Recharge to the aquifer during the nongrowing season exceeds aquifer discharge. Hence, the amount of water stored in the aquifer usually increases during the nongrowing season. This increase in storage is substantial enough to permit

the water table in most parts of the outcrop area to remain higher than nearby stream channels throughout the growing season. As a result, the dry-weather flow of streams in the Cohansey Sand outcrop area represents ground-water discharge. The volume of ground water discharged to streams from the Cohansey Sand as well as direct storm runoff, is measured by recording gaging stations on the Maurice River at Norma (Salem County) and on the great Egg Harbor River at Folsom (Atlantic County).

Ground water from the Cohansey Sand is utilized largely for domestic and farm supplies, although some ground water is used by industry. The 1957 ground-water pumpage from the aquifer in the county was about 2 to 3 mgd from wells generally 100 to 200 feet deep, although many wells are only 25 to 50 feet deep. The possibilities for future development of water for industry, irrigation, and public supply from the Cohansey Sand are excellent. Wells capable of yielding 1,000 gpm are possible.

The concentration of dissolved solids in ground water from the Cohansey Sand is usually less than 100 mg/l. Results of chemical analyses of six samples (table 8) show that the iron concentration was generally less than 0.5 mg/l and carbonate hardness was 50 mg/l or less. The most undesirable feature of the water is the iron content for which the water must be treated to be rendered suitable for many uses. The temperature of the water is usually between 13° and 14°C.

This aquifer consists of a large thickness of saturated sediments of high porosity and permeability. Any large-scale pumping from the aquifer may decrease the flow of the main streams, such as Great Egg Harbor and Maurice Rivers and in turn may allow increased upstream movement of saline water in the tidal reaches of the streams in Atlantic and Cumberland Counties.

PLEISTOCENE SERIES

The Pleistocene Series consists of the Bridgeton, Pensauken, and Cape May Formations. These formations have similar geohydrologic characteristics and cap the older sediments (fig. 2).

Bridgeton Formation

The Bridgeton Formation crops out in an area of about 100 square miles in the southern half of the county. The exposures are irregular and are at altitudes ranging from 100 to 160 feet.

The Bridgeton Formation contains fine- to very coarse-grained quartzose sand and gravel. An analysis of a sample collected 2 miles northeast of

Mullica Hill shows more than 95 percent medium to very coarse sand (table 2). The sands are white, yellow, and brown; usually they are fairly well sorted, and the grains are subangular. The formation has a thickness of as much as 50 feet in the county.

The Bridgeton Formation yields from 10 to 50 gpm of water to wells for domestic and stock supplies. In the southern half of the county, the Bridgeton Formation is hydraulically connected with the underlying Cohansey Sand or the Kirkwood Formation. The Bridgeton Formation is a water-table aquifer and the shape of the water table is a subdued replica of the topography.

Pensauken Formation

The Pensauken Formation crops out in irregular and isolated patches in the north-central part of the county at altitudes of 40 to 120 feet. It includes an area of about 23 square miles (fig. 2). The formation consists of medium- to coarse-grained quartzose sand, and some gravel and clay. The sand grains are usually poorly sorted; subangular with colors of yellow, red, and brown. Locally, the grains of sand and gravel are indurated by ferruginous cement to form "ironstone." The Pensauken Formation is difficult to distinguish from the underlying Bridgeton Formation because of similar lithology. The formation is as much as 30 feet thick in the county. Elsewhere in the State, it attains a thickness in excess of 60 feet.

The hydrology of the Pensauken Formation is similar to that of the Bridgeton Formation. A few wells yield from 10 to 50 gpm of water for domestic use.

Cape May Formation

The Cape May Formation crops out adjacent to the Delaware River and tributary streams (fig. 2). It is found at altitudes as high as 90 feet along some streams, but usually it is not higher than 70 feet. The outcrop has an area of about 34 square miles in Gloucester County. The Cape May Formation is composed of medium- to coarse-grained quartzose sand with much gravel and minor amounts of clay. The sand and gravel are usually yellow or brown, but sometimes they are gray in color. The clays are yellow, brown, gray, and black. The materials are usually poorly sorted; and the sand grains are subangular. The Cape May materials are not compact or coated with iron oxide as are the older Pleistocene deposits. The formation is as much as 40 feet thick. Along the streams in the interior of the county, the Cape May Formation is about 30 feet thick. In some areas it is difficult to distinguish the Cape May Formation from the Pensauken Formation because of similar lithology.

Maurice River Basin


Nearly all the base flow out of the Gloucester County part of the Maurice River basin was measured at three sites (fig. 11). Still Run (table 5, site 18) was measured at Route 40, and Scotland Run and Indian Branch (table 5, sites 13 and 20) were measured upstream from Malaga Lake because the level of the lake was below the spillway at the time of the measurement (July 1957). The total measured base flow was 15.3 cfs (about 10 mgd) including 10 cfs from Still Run. These streams are tributaries of the Maurice River and derive their water from the Cohansey Sand and Pleistocene sand and gravel.


A comparison of the daily precipitation at nearby Clayton and the streamflow from the gaging station on the Maurice River at Norma for 1956 shows the rapid response to precipitation and the effects of recharge to the aquifers (fig. 14). The estimated daily ground-water discharge to the stream during 1956 ranged from about 57 to perhaps as much as 185 cfs. A hydrograph of monthly mean discharges for the 10-year period 1946-55 shows the lowest monthly flow averaged 52.0 cfs in July 1954 (fig. 13). The highest monthly flow averaged 371 cfs in February 1949. The minimum flow of record (1932-67) for 1 day was 23 cfs in 1964 and 1966 and the maximum 1 day flow was 7,360 cfs in 1940. The average discharge (1932-67) is 164 cfs.

Great Egg Harbor River Basin

The base flow from the Gloucester County part of Great Egg Harbor River basin measured near the Gloucester-Atlantic County line on July 26, 1957 was about 30 cfs or 19 mgd. This included nearly 11 cfs (7 mgd) of streamflow from Hospitality and Marsh Lake Branches which drain about 40 square miles in Gloucester County (table 5, site 16 and 17). At Berryland (table 5, site 15) the discharge of the Great Egg Harbor River was 18.8 cfs (12 mgd), of which about 10 cfs was inflow from Camden County. About 2 miles northeast of Williamstown and 8 miles upstream from Berryland, Four Mile Branch had a flow of 2.74 cfs (table 5, site 13). Excluding the inflow from Camden County, there was an increase in flow of about 6 cfs between sites 13 and 15 which is attributed to ground-water discharge and inflow from Squankum Branch and Minor drainages.

Hospitality Branch was measured near Cecil (table 5, site 14) and 4 miles downstream at Folsom (table 5, site 17). The increase in flow between the two sites was 3.21 cfs and is believed to be ground-water discharge from the Cohansey Sand and Pleistocene deposits into Faraway and White Oak Branches which are tributary to Hospitality Branch.





The gaging station at Folsom on the Great Egg Harbor River measures the streamflow from a drainage area of 56.3 square miles, of which 20 square miles are in Gloucester County. The estimated daily ground-water discharge in 1956 ranged from 39 to 120 cfs (fig. 15). A comparison of precipitation data at nearby Hammonton and daily discharge of the river at the gaging station for 1956 shows that precipitation infiltrates and moves through the aquifers and overland to the nearby streams. A hydrograph of the monthly mean discharge for the 10-year period 1946-55 shows that the lowest monthly flow averaged 20.3 cfs in September 1951 (fig. 13). The highest monthly flow averaged 178 cfs in January 1949. The maximum flow of record (1925-67) for 1 day was 1,440 cfs in 1940 and the minimum flow for 1 day was 15 cfs in 1957. The average discharge (1925-67) is 83.8 cfs.

The temperature of the water in the streams ranged from 59° to 80°F during the period of low-flow measurements of July 1957. An indication of the chemical quality of water was obtained by measuring the specific conductance. The specific conductance of the water for all the streams was 345 micromhos or less (roughly equivalent to 200 mg/l of dissolved solids). The water samples from streams flowing south in the Maurice and Great Egg Harbor River basins of Gloucester County had specific conductances ranging from 10 to 50 micromhos. This water is from the Cohansey Sand and Pleistocene sands and gravels and moves only short distances through the aquifer before it discharges into these streams. The water samples collected from streams flowing north to the Delaware River had specific conductances ranging from 100 to 345 micromhos. This water is mostly derived from the Kirkwood and Wenonah Formations and Mount Laurel Sand. Because of the low gradients of the streams, mean velocities ranged from 0.04 fps (foot per second) at Almonesson Creek to 1.38 fps at Chestnut Branch of Mantua Creek.

WATER BUDGET

An approximate long-term water-budget evaluation of the hydrologic cycle can be applied to the basins in Gloucester County. This budget can be expressed mathematically as:

$$P = Q + R + ET + S,$$

in which

P = precipitation

Q = pumpage withdrawals in the basin from aquifers that receive recharge from precipitation in the basin of interest

R = runoff, measured at gaging stations

ET = evapotranspiration

S = change in storage in the water-table aquifer

If pumpage is negligible or ground water is returned to the aquifer in the drainage area above the gaging station and if the water table is in equilibrium—that is, discharge equals recharge, then the water-budget equation reduces to:

$$P = R + ET.$$

Gloucester County can expect, on the average, about 44 inches of precipitation each year (about 2 mgd per square mile). The runoff figure shown below is the average discharge for the 10-year period (1946-55) converted to million gallons per day per square mile of drainage basin. On the basis of the assumptions made, the evapotranspiration (ET) is equal to the difference between the precipitation and the runoff, or

$$ET = P - R.$$

<i>Drainage basin</i>	<i>Area (square miles)</i>	<i>Average discharge (1946-55) (cfs)</i>	<i>P — R = ET (mgd per sq mi)</i>
Mantua Creek at Pitman	6.75	11.7	2 — 1.12 = 0.88
Maurice River at Norma	113	167	2 — 0.95 = 1.05
Great Egg Harbor River at Folsom	56.3	87.2	2 — 1.00 = 1.00

These figures indicate that, on the average, about half of the precipitation on the drainage areas is lost to evapotranspiration and half leaves the basin as runoff. At the gaging station on Mantua Creek at Pitman, which has a small drainage area, runoff is more rapid than at Maurice River or Great Egg Harbor River stations, and thus there is probably less time for evapotranspiration. These differences are shown in the calculations.

Measurements made during July 23-31, 1957 indicate that the base flow from the 200 square miles of drainage area of the Delaware River basin in Gloucester County was about 45 cfs; and the base flow from the 130 square miles of drainage area of the Maurice and Great Egg Harbor River basins in Gloucester County was about 35 cfs. The runoff for each basin was about 0.16 mgd per square mile from base flow measured in July 1957. For the Great Egg Harbor River basin including Hospitality Branch the base flow was 0.19 mgd per square mile, and for Maurice River basin in the county it was about 0.14 mgd per square mile. The total measured base flow in July 1957 from the county was 80 cfs (about 52 mgd). This ground-water discharge is probably close to the minimum outflow from the county.


SUMMARY AND CONCLUSIONS


The future growth and economy of Gloucester County are dependent to a large extent on the available water supply. In Gloucester County nearly all of the water supplies are now derived from ground water. Surface water is not used except by a few industries adjacent to the Delaware River and by some farmers who utilize irrigation ponds. The low relief of the county and the high porosity of the surficial Coastal Plain sediments make large surface-water reservoirs impractical. Much of the streamflow is derived from ground-water discharge which can be intercepted by wells before it reaches the streams. Although large quantities of water are available from the Delaware River, the high chloride content during times of low-flow make this source unsuitable for some purposes and the future water supply for the county will probably come primarily from ground-water sources.

Analysis of streamflow records for the 10-year period 1946-55 of the Maurice River at Norma (Salem County) and the Great Egg Harbor River at Folsom (Atlantic County) compared with base flow measurements made in 1957 for flow to the Delaware River, indicates that about 290 mgd of water flows out of Gloucester County and parts of adjacent counties. For the 10-year period 1946-55 the lowest monthly average flow was about 95 mgd and the lowest daily outflow was about 62 million gallons. In July 1957, during the drought, about 52 mgd of outflow from the county was measured.

The base flow of the streams in Gloucester County is water that has been discharged from the aquifers. The minimum measured base flow from the county (50-60 mgd) is all ground water that has been temporarily stored in the aquifers during periods of high precipitation and which has had an opportunity to migrate to and discharge into the streams. However, during average years, much of the average streamflow of 290 mgd is derived from this source. During 1966, about 40 mgd of water was pumped from the aquifers in the county. It is thus indicated that the amount of ground-water use can be increased many-fold without endangering the perennial ground-water supply.

Most of the ground water available for use is derived from precipitation. According to records, a long-term average of about 2 mgd of water falls on each square mile in the county. About half of this amount is lost to evapotranspiration and the other half is stream runoff. Theoretically the stream runoff is what is available for use. Gloucester County has a land area of 329 square miles. Thus, theoretically, 329 mgd is available for development from all sources not counting Gloucester County's share of the Delaware River. Because of the sandy character of the surficial de-






SOIL SURVEY

Gloucester County New Jersey



UNITED STATES DEPARTMENT OF AGRICULTURE
Soil Conservation Service
In cooperation with
NEW JERSEY AGRICULTURAL EXPERIMENT STATION

0
1/2
1 Mile
Scale 1:15 840
0
5000 Feet



SOIL LEGEND

The first letter in each soil symbol is the initial of the soil series name. If slope forms part of the soil name, a second capital letter shows the range of steepness. Symbols without a slope letter show level or nearly level soils or land types. A number in the symbol shows an eroded soil.

SYMBOL	NAME	SYMBOL	NAME
Ad	Alluvial land	LaA	Lakehurst sand, 0 to 5 percent slopes
AmB	Aura loamy sand, 0 to 5 percent slopes	LdB	Lakeland sand, 0 to 10 percent slopes
ArB	Aura sandy loam, 0 to 5 percent slopes	LeB	Lakewood sand, 0 to 5 percent slopes
AsB	Aura-Sassafras loamy sands, 0 to 5 percent slopes	LkA	Lenoir and Keyport loams, 0 to 5 percent slopes
AsC	Aura-Sassafras loamy sands, 5 to 10 percent slopes	Lo	Leon sand
AuB	Aura-Sassafras sandy loams, 0 to 5 percent slopes	Mc	Made land, coarse materials
AuC	Aura-Sassafras sandy loams, 5 to 10 percent slopes	Mf	Made land, fine materials
AuC3	Aura-Sassafras sandy loams, 5 to 10 percent slopes, severely eroded	MrB	Marlton sandy loam, 0 to 5 percent slopes
Ba	Bayboro loam	MrC	Marlton sandy loam, 5 to 10 percent slopes
Ck	Colemantown-Matlock loams	MrC3	Marlton sandy loam, 5 to 10 percent slopes, severely eroded
CmB	Collington loamy sand, 0 to 5 percent slopes	MrD	Marlton sandy loam, 10 to 15 percent slopes
CmC	Collington loamy sand, 5 to 10 percent slopes	MrD3	Marlton sandy loam, 10 to 15 percent slopes, severely eroded
CnA	Collington sandy loam, 0 to 2 percent slopes	MrE	Marlton sandy loam, 15 to 25 percent slopes
CnB	Collington sandy loam, 2 to 5 percent slopes	MrF	Marlton sandy loam, 25 to 40 percent slopes
CnC	Collington sandy loam, 5 to 10 percent slopes	Mu	Muck
CoB	Colts Neck soils, 0 to 5 percent slopes	NbB	Nixonton and Barclay soils, 0 to 5 percent slopes
CoC	Colts Neck soils, 5 to 10 percent slopes	Pa	Pasquotank fine sandy loam
DoB	Downer loamy sand, 0 to 5 percent slopes	Pg	Pits
DsA	Downer sandy loam, 0 to 2 percent slopes	Po	Pocomoke loam
DsB	Downer sandy loam, 2 to 5 percent slopes	Ps	Pocomoke sandy loam
Ek	Elkton loam	Sa	St. Johns sand
Fa	Fallsington loam	SfB	Sassafras loamy sand, 0 to 5 percent slopes
Fd	Fallsington sandy loam	SfC	Sassafras loamy sand, 5 to 10 percent slopes
FhB	Freehold loamy sand, 0 to 5 percent slopes	SrA	Sassafras sandy loam, 0 to 2 percent slopes
FhC	Freehold loamy sand, 5 to 10 percent slopes	SrB	Sassafras sandy loam, 2 to 5 percent slopes
FnB	Freehold sand, thick surface variant, 0 to 10 percent slopes	SrC	Sassafras sandy loam, 5 to 10 percent slopes
FoA	Freehold sandy loam, 0 to 2 percent slopes	SrD3	Sassafras sandy loam, 10 to 15 percent slopes, severely eroded
FoB	Freehold sandy loam, 2 to 5 percent slopes	SsD	Sassafras soils, 10 to 15 percent slopes
FoC	Freehold sandy loam, 5 to 10 percent slopes	SsE	Sassafras soils, 15 to 40 percent slopes
FoC3	Freehold sandy loam, 5 to 10 percent slopes, severely eroded	Tm	Tidal marsh
FoD3	Freehold sandy loam, 10 to 15 percent slopes, severely eroded	WaD3	Westphalia fine sandy loam, 10 to 15 percent slopes, severely eroded
FsD	Freehold soils, 10 to 15 percent slopes	WhB	Westphalia soils, 0 to 5 percent slopes
FtE	Freehold, Colts Neck, and Collington soils, 15 to 25 percent slopes	WhC	Westphalia soils, 5 to 10 percent slopes
FtF	Freehold, Colts Neck, and Collington soils, 25 to 40 percent slopes	WhD	Westphalia soils, 10 to 15 percent slopes
Fw	Fresh water marsh	WhE	Westphalia soils, 15 to 40 percent slopes
KpB	Keyport sandy loam, 0 to 5 percent slopes	WnA	Woodstown and Dragston loams, 0 to 2 percent slopes
KpC3	Keyport sandy loam, 5 to 10 percent slopes, severely eroded	WoB	Woodstown and Dragston loamy sands, 0 to 5 percent slopes
KrB	Kresson sandy loam, 0 to 5 percent slopes	WsB	Woodstown and Dragston sandy loams, 0 to 5 percent slopes
		WtB	Woodstown and Klej loamy sands, 0 to 5 percent slopes

NEW CASTLE CO

TABLE 6.—*Brief descriptions of the soils, and their*

Map symbols	Soil type	Depth to seasonally high ground water (before artificial drainage)	Brief soil descriptions ¹	Depth from surface
Ad.....	Alluvial land.....	1 foot.....	2 to 2½ feet of stream deposits of silty sand; material is variable; upper 6 inches is high in organic matter; poorly to very poorly drained.	<i>Inches</i> 0-30
AmB.....	Aura loamy sand.....	10 feet or more.....	About 1 foot of sand over 1 foot of silty sand underlain by a mixture of clayey sand and fine, angular gravel that is hard when dry; well drained.	0-16 16-30 30-60
ArB.....	Aura sandy loam.....	10 feet or more.....	About 2 to 2½ feet of silty sand over a mixture of clayey sand and fine, angular gravel that is hard when dry; well drained.	0-14 14-24 24-60
AsB.....	Aura-Sassafras loamy sands: slopes of 0 to 5 percent.	5 to 10 feet or more.....	Mostly like Aura loamy sand.....	
AsC.....	Aura-Sassafras loamy sands: slopes of 5 to 10 percent.	10 feet or more.....	Mostly like Sassafras loamy sand.....	
AuB.....	Aura-Sassafras sandy loams: slopes of 0 to 5 percent.	10 feet or more.....	Mostly like Aura sandy loam.....	
AuC.....	Aura-Sassafras sandy loams: slopes of 5 to 10 percent.	10 feet or more.....	Mostly like Sassafras sandy loam.....	
AuC3.....	Aura-Sassafras sandy loams: slopes of 5 to 10 percent and severely eroded.	10 feet or more.....	Mostly like Sassafras sandy loam.....	
Ba.....	Bayboro loam.....	Ponded at surface.....	About 1 foot of organic silt over 3 feet of plastic clay; very poorly drained.	0-10 10-48
Ck.....	Colemantown-Matlock loams.....	Ponded at surface.....	About 1 foot of organic silt over 4 feet of plastic clay; in places clay is stratified with sand below a depth of 30 inches; poorly or very poorly drained.	0-12 12-60
CmB, CmC.....	Collington loamy sand.....	10 feet or more.....	1½ feet of poorly graded sand over 1½ feet of clayey sand that is underlain by loose silty sand; well drained.	0-18 18-34 34-60
CnA, CnB, CnC.....	Collington sandy loam.....	5 to 10 feet or more.....	About 1 foot of silty sand over 1½ feet of clayey sand that is underlain by 2½ feet of silty sand; well drained.	0-14 14-32 32-60
CoB, CoC.....	Colts Neck soils.....	10 feet or more.....	About 1 foot of a sand-silt mixture over 2 feet of clayey sand that is underlain by 2 feet of silty sand; material contains ironstone in places; well drained.	0-12 12-40 40-60
DoB.....	Downer loamy sand.....	5 to 10 feet.....	About 1½ feet of a poorly graded sand over 1 foot of silty sand; beneath this is 2½ feet of poorly graded sand that, in places, is made up of as much as 10 percent round, hard pebbles; well drained.	0-20 20-30 30-60
DsA, DsB.....	Downer sandy loam	5 to 10 feet.....	2½ feet of sand-silt mixture over 2½ feet of silty sand that, in places, contains up to 10 percent round, hard pebbles; well drained.	0-16 16-30 30-60
Ek.....	Elkton loam.....	1 foot, but surface ponded at times.	About 8 inches of inorganic silt over 4 feet of plastic clay; in places clay is stratified with sand below a depth of 30 inches; poorly drained.	0-8 8-60
Fa.....	Fallsington loam.....	1 foot.....	About 2½ feet of silty or clayey sand over poorly graded sand or gravelly sand; in places layers of clay occur below a depth of 30 inches; poorly drained.	0-30 30-48
Fd.....	Fallsington sandy loam.....	Same as Fallsington loam.....		

See footnotes at end of table.

The soils in this general area respond to fertilization, but the very sandy ones, of course, need frequent applications. Moisture relations are good except in areas where an underlying layer keeps the soil wet or in areas where the soil is so sandy that it is likely to be droughty.

Nearly all the soils that have a thick, very sandy surface layer are used for apples, peaches, or vegetables. Asparagus is the most extensive crop. Sweetpotatoes, tomatoes, peppers, eggplants, and pumpkins are other important crops.

The less sandy soils, which are more fertile and have better moisture relationships, are used for vegetables and fruits and for small grains, alfalfa hay, corn, soybeans, and pasture. Flowers and nursery stock are also grown.

If adequately drained, the naturally wet soils can be used for vegetables, soybeans, and other crops. About half the wet acreage is in forest.

Gently sloping to steep, olive clay soils:
Marlton-Kresson association (MK)

This general area occurs in a broken, wavy belt, $1\frac{1}{2}$ to 2 miles wide. It extends from Harrisonville station in the southern part of the county northward through Mullica Hill to Blackwood Terrace. Slopes are gentle on the broad uplands between the streams that cross the area. Adjacent to the streams, the slopes are short and steep to very steep.

The soils in this general area are distinguished by the very high content of glauconite, which makes the soils and underlying material olive green or dark olive in color. The soils also have a comparatively high content of clay, although their parent materials and underlying substrata generally are somewhat friable.

The soils are moderately fertile, but water moves through them slowly. During much of the time, they are either too moist or too dry to be worked. Runoff is rapid, and the hazard of erosion is severe on cultivated slopes.

The Marlton soils occupy almost 90 percent of the area. The Kresson soil, which is wetter and more mottled, occupies most of the remaining 10 percent; it is on nearly level and depressed areas.

Where they form extensive unbroken areas, the Marlton and Kresson soils are used mainly for general crops and pasture. Smaller tracts of these soils, as well as adjacent sandy soils, are used for tomatoes, peppers, and eggplants.

This general area and the adjacent general area—gently to strongly sloping soils from greensand (FCC)—comprise the greensand belt in Gloucester County. The soils in these two general areas contain glauconite.

From 1800 to 1920, it was common for farmers to spend the winters digging, hauling, and spreading the olive clay, locally called marl, for use as fertilizer (5). This practice was started, of course, before soluble commercial fertilizers were generally available. The glauconite in the clay contains potash, but, because it is very slowly soluble, plants cannot obtain it easily.

Nearly level to steep, fine sandy soils:
Westphalia-Nixonton-Barclay association (WNB)

The soils of this general area lie in a broken, irregular belt, 4 to 6 miles wide. This belt extends from the southern boundary of the county northward through Harrison-

ville, Cedar Grove, Barnsboro, and Hurffville. It is spotted by hills capped with gravelly soils.

Drainage of the area is toward the Delaware River. Many of the tributaries of the river rise in this area. Slopes generally are gentle to moderate, but, near the headwaters of streams and in other local areas, they are as much as 10 to 20 percent. The elevation ranges from 90 to 120 feet. In the higher places, the water table is below depths of 10 to 20 feet; in the lower places, it is at the surface. The high water table is a result of the slowly permeable layer of clay that, in places, underlies the fine sandy stratum from which most of the soils have formed.

The Westphalia soils occupy about 60 percent of this general soil area. Nixonton and Barclay soils, composed mainly of fine sand, are the dominant soils on the remaining 40 percent. The Westphalia, Nixonton, and Barclay soils are progressively wetter in the order named.

The soils are generally used for vegetables, fruits, and general crops. Asparagus, sweetpotatoes, and tomatoes are the most common crops. Almost half of the nurseries of the county are located in this area.

About 70 percent of the area has been cleared for farming, but forests remain on wet sites and on steep slopes along streams. The forests produce good stands of yellow-poplar, which is used locally to make produce baskets. Holly is abundant.

Gravelly soils on the higher divides:
Aura-Sassafras-Downer association (ASD)

This general soil area occupies the southeastern half of the county, except where other general soil areas are interspersed. Those interspersed are inland wet soils (MAFP) along streams, and the gray sands (LLL) in the eastern corner. In addition, isolated tracts of this general area cap the higher hills in the western part of the county.

This general area constitutes the drainage divide that separates streams that flow northwestward to the Delaware River from those that flow southward and eastward. Only a very small part of the area, along its western boundary, drains to the Delaware River.

In general, the elevation ranges from 120 to 170 feet. Most of the slopes are broad and gentle. Nevertheless, along the western border and on isolated hills at the edges of the gravel deposits, there are slopes that are up to 10 percent or more.

The well-drained Aura soils occupy about 70 percent of this general soil area. The Sassafras, Downer, and other soils occupy the rest. The Aura soils have an especially firm layer, normally at depths of 24 to 36 inches, through which few roots penetrate. Sassafras and Downer soils, which are also well drained, lack this firm layer.

The Woodstown, Dragston, Fallsington, and Pocomoke soils occur less extensively in this general area. These are wet soils that have a high water table in winter.

Approximately 55 percent of the area has been cleared and is used mainly for general crops, vegetables, and fruits. This general area has broad areas of generally well-drained soils and a comparatively high altitude that favors air drainage. It is, therefore, well suited to apples and peaches. An estimated 4,000 of the more than 5,000 acres of apple and peach trees in the county occurs in this general area. Flowers are grown commercially. The main vegetables are tomatoes, asparagus, peppers, and egg-



Figure 2.—Irrigated lettuce on Aura sandy loam.

plants. In addition, lettuce, spinach, radishes, scallions, dandelions, fennel, and many other high-value crops are raised (fig. 2). Many of these crops are produced on small farms equipped with overhead irrigation.

Forests have been cut frequently for firewood and have been damaged by wildfires. The poor condition of the forests, however, does not reflect the capacity of the soils to grow trees. Pines have survived the fires in areas that formerly supported fairly good stands of oak.

Gray sands: Lakeland-Lakewood-Lakehurst association (LLL)

This small, nearly level area occurs in the eastern corner of the county, at elevations ranging from 70 to 100 feet.

The soils have developed from sands, and their surface layers have been leached gray to some extent. These soils hold little water available for plants, and commercial fertilizer washes out easily.

The Lakeland, Lakewood, and Lakehurst soils are dominant. Water enters and drains through the Lakeland and Lakewood soils at an excessive rate. The same is true of the Lakehurst soil, except that the water table rises to within 20 to 30 inches of the surface during winter and is within 4 to 6 feet during drier seasons.

All the soils are so infertile and droughty that they have not been cleared extensively for crops. Much of the cleared acreage is now idle. Sweetpotatoes, peaches, and pumpkins are grown to a minor extent. Most areas are still in forests of pitch pine.

Inland wet soils: Muck-Alluvial land-Fallsington-Pocomoke association (MAFP)

The inland wet soils occur in nearly level, narrow, wet areas along streams. Elevations range from 10 to 160 feet.

Muck makes up about 50 percent of this general soil area; Alluvial land and Fallsington, Pocomoke, and minor soils make up most of the rest. Muck and the Fallsington and Pocomoke soils are most abundant along streams that drain to the east and southeast. They also occur to a minor extent in the narrower areas that drain to

the Delaware River, and in these places Alluvial land is most extensive.

Included in this general area are the Pasquotank, Bayboro, Leon, and St. Johns soils, all of which are wet to very wet.

An estimated 25 percent of the area has been cleared. The water table must be lowered in all the soils before crops can be grown. After a soil has been properly drained, corn, soybeans, summer vegetables, and pasture plants can be grown.

Forests of Atlantic white-cedar and maple grow on much of the Muck. Oak, sweetgum, maple, and other species grow on the other soils.

Descriptions of the Soils

This section describes the soil series and individual soils—mapping units—of Gloucester County. Characteristics of the soils and properties that affect use and management are given, and suitable crops are suggested.

The soil series and mapping units are arranged alphabetically. A detailed description, including a complete description of the soil profile, is given for each series. After this, there is a description of the mapping units in the series. Technical terms used in the soil descriptions are defined in the Soil Survey Manual (9)¹ and in the Glossary in the back part of the report. Descriptions of soil color are based on the Munsell color charts.

A list of the soils and the map symbols and capability classification of each are given in the "Guide to Mapping Units and Capability Units" at the end of the report. The approximate acreage and proportionate extent of each mapping unit are given in table 1, and the location and distribution of each are shown on the soil map in the back of the report.

Alluvial Land

Alluvial land (Ad).—This miscellaneous land type is composed of various materials. It occurs along the streams on flats that are subject to overflow. In some places it is flooded several times a year; in others, only once in several years.

Alluvial land has formed on material deposited by streams that flow west to the Delaware River. The streams begin in the gravelly divides and flow through several belts of different kinds of soils and geologic materials. They cross the general soil areas of nearly level to steep, fine sandy soils (WNB); gently to strongly sloping soils from greensand (FCC); and gently sloping, brown clay soils (KLE). Material from each of these areas has been removed and deposited on flood plains to form Alluvial land. In most places the texture of the surface layer is loam, but in some it is sandy loam.

Most areas of Alluvial land have large amounts of organic matter near the surface. Also, ground water is relatively close to the surface in most places. The soils vary from place to place but do not consist of definite horizons.

The native vegetation varies according to the texture of the soil material and the degree of wetness. Red maple

¹ Italic numbers in parentheses refer to Literature Cited, p. 83.

and Atlantic white-cedar are common in some places; sweetgum, yellow-poplar, ash, red oak, boxelder, black walnut, and redcedar grow on others. All of the soil material is extremely acid.

Nearly all the areas are in forest, but some small areas have been cleared for pasture. This land type is in capability unit VIIw-1.

Aura Series

Aura soils have a grayish-brown coarse to medium sandy loam or loamy sand surface layer. The upper subsoil is yellowish brown and is generally sandy loam or loamy sand. The deeper subsoil, beginning generally at depths of 18 to 36 inches, is noticeably reddish and more clayey. It is extremely hard when dry, commonly is firm to very firm when moist, and consists of stratified and crossbedded, coarse, harsh sand and fine gravel coated with clay. In places the clay coatings fill much of the space between the coarser particles. Much of the sand and gravel has been softened by weathering. Pebbles in the upper part of the soil are cleaner and commonly coarser than those in the lower part. The larger pebbles, more than 1 inch in diameter, are most numerous in the upper part of the profile. In the lower part, most of the pebbles are less than half an inch in diameter.

The Aura soils are well drained. They occupy the highest areas of the county. Near Glassboro and Williamstown they are nearly level; in the Richwood area they are more sloping. Further west, Aura soils occupy the tops of knolls.

Native woodland consists of red, white, and black oaks and some pitch pines.

Aura soils occur in association with Sassafras, Downer, and Woodstown soils. The Aura soils are redder and firmer with increasing depth than are the Sassafras and Downer soils. They are free from the mottling that is common in the subsoil of the seasonally wet Woodstown soils.

Representative profile (Aura sandy loam, 0 to 5 percent slopes, in a peach orchard one-eighth mile south of Richwood):

- A_p (Plow layer). 0 to 8 inches, very dark grayish-brown (2.5Y 3/2) coarse sandy loam; weak, fine, granular structure; in places platy in the lower part; very friable; roots abundant; 10 to 15 percent of mass is rounded, clean, quartzose pebbles; worm channels common; pH 6.4; smooth lower boundary.
- A₂ 8 to 14 inches, yellowish-brown (10YR 5/4) coarse sandy loam; weak, fine, granular to medium, platy structure; friable to firm; roots common; worm and root channels common and filled with material from plow layer; few clean pebbles; pH 6.4; gradual, smooth lower boundary; 6 to 10 inches thick.
- B₁ 14 to 24 inches, dark yellowish-brown (10YR 4/4) sandy clay loam; weak, medium, subangular blocky structure; friable; about 10 percent of mass is rounded quartzose pebbles, coated with clay; a few pebbles have been softened by weathering; clay flows abundant; pH 6.2; clear, smooth lower boundary; 8 to 10 inches thick.
- B₂₁ 24 to 36 inches, brown (7.5YR 4/4) coarse sandy clay loam; moderate, medium, subangular blocky structure; firm, very hard when dry; small roots common; coarse fragments make up about 5 percent of mass; all fragments coated with and imbedded in clay; clay flows abundant; pebbles, both round and angular, commonly softened by weathering; ironstone fragments, one-eighth inch thick, in horizontal position at

a depth of about 36 inches; sandy pockets common; pH 5.4.

- B₂₂ 36 to 60 inches, strong-brown (7.5YR 5/8) coarse sandy clay loam decreasing in clay with depth; massive to medium, platy structure or stratified; firm in place, friable when removed; common, sharp, gritty fine gravel imbedded in clay; weathered yellow fragments abundant; pH 4.6.

Micropodzol horizons occur in the upper 4 inches of forested soils. Areas under pitch pine have a slightly grayer surface horizon than those under hardwoods. Under native vegetation, Aura soils rarely contain earthworms.

The deeper soil generally is hard when dry. In small sandy areas, however, the soil remains loose. The depth to the firm horizon averages about 2 feet, but it ranges from about 18 to 36 inches. The subsoil normally is sandy clay loam, and, below a depth of 2 feet, it contains about 5 percent silt. Generally, below a depth of 3 feet, the soil gradually becomes less firm and more friable. Rounded quartzose pebbles are most abundant in the upper 2 feet, and usually they make up about 5 to 10 percent of the soil. In places, however, they make up as much as 30 percent.

As mapped, most areas of Aura soils contain some Sassafras and Downer soils.

Aura soils are moderately or moderately slowly permeable in the subsurface soil. Runoff is rapid, and erosion is a problem, even on gentle slopes. Irrigation water should be applied slowly. Few roots penetrate the firm deeper horizons, which hold little water that is available to plants. In places these soils contain enough pebbles to hinder disking, as well as the planting of small seeds.

The soils are low in content of organic matter and low in natural fertility, but plants grown on them respond to fertilization. They are suited to fruit, flowers, general farm crops, and most vegetables (fig. 3). Special care is needed to maintain organic matter and a good soil structure so that the soil can absorb more water.

Aura loamy sand, 0 to 5 percent slopes (AmB).—This soil has a profile similar to the one described for the series, except that the surface layer is more sandy and a few inches thicker. In uneroded areas the surface layer of this soil is 16 inches thick.

Because the surface layer is sandy, the soil warms early, but it is droughty and is subject to wind erosion



Figure 3.—Irrigated peonies being harvested on Aura sandy loam.

if left bare. This soil is suited to early vegetables and sweetpotatoes. Capability unit IIIs-1.

Aura sandy loam, 0 to 5 percent slopes (ArB).—This is the soil described as having a profile representative of the Aura series. In the eastern part of the county, small areas that have a loam surface layer were mapped with this soil.

Included also are small areas where erosion has removed most of the original surface layer. In these areas the soil contains little organic matter; it is stickier than normal and is, therefore, harder to plow and cultivate.

This soil is suitable for fruit, vegetables, general farm crops, and commercial flowers. It does not warm soon enough for the earliest vegetables and is not well suited to sweetpotatoes. The surface soil becomes hard when dry and, therefore, is not easily cultivated in summer. Unless the content of organic matter is maintained, the soil will crust easily and cause poor germination of seed. Runoff is rapid. Under traffic, the soil packs readily. Capability unit IIs-2.

Aura-Sassafras loamy sands, 0 to 5 percent slopes (AsB).—This complex of soils consists of areas of Aura loamy sand and of Sassafras loamy sand (described under the Sassafras series). The soils are so interspersed that it was impractical to separate them at the scale of mapping used.

The surface layer of both soils is generally grayish brown and very sandy. It is loamy sand in texture and is relatively thick. It commonly extends to a depth of 16 inches and, in places, to a depth of more than 20 inches. The subsoil is finer in texture than the surface layer. Generally the subsoil is sandy loam or sandy clay loam, but in some small areas it has a sandier texture. At depths of about 30 to 40 inches, the Sassafras soil grades to loose loamy sand or sand. At the same depths, the Aura soil grades to coarse sand and fine gravel. This Aura soil material is coated with clay and generally firm to very firm. In places there are clay lenses in the substratum.

The Aura soil is dominant on the more level areas, and the Sassafras soil is dominant on the more sloping areas. On farmed land, erosion ranges from slight to moderate.

These soils are suited to fruit, asparagus, early vegetables, and forests. Capability unit IIIs-1.

Aura-Sassafras loamy sands, 5 to 10 percent slopes (AsC).—Except for steeper slopes, this mapping unit is similar to Aura-Sassafras loamy sands, 0 to 5 percent slopes. Generally, the Aura soil occupies most of the milder slopes, and the Sassafras soil occupies most of the steeper slopes.

In most cultivated fields, erosion generally has been moderate. In small areas most of the original surface layer has been removed by erosion. Because of the clayey subsoil material in the plow layer, these spots are harder to work than areas with a normal surface layer.

These soils are suited to fruit and to asparagus and other vegetables. Wind and water erosion must be controlled on these soils. Capability unit IIIs-2.

Aura-Sassafras sandy loams, 0 to 5 percent slopes (AuB).—These soils occur in such an intricate pattern that it was not practical to separate them at the scale of mapping used. The Sassafras soil is described under the Sassafras series.

The major differences between the Aura and Sassafras soils occur below a depth of about 20 to 36 inches. At this depth, the Aura soil consists of coarse sand and gravel, which is coated with clay and is generally firm to very firm. In contrast, the Sassafras soil, below 20 to 36 inches, is more friable and sandy than at less depth. The Aura soil predominates on the more gently sloping areas, and the Sassafras soil, on the more sloping.

In some farmed areas, slight to moderate erosion has reduced the thickness of the surface layer from about 14 inches to about 8 to 12 inches. Erosion is a constant hazard, and some small areas have lost most of the original surface layer.

These soils are suited to most vegetables, fruits, and general farm crops. Capability unit IIs-2.

Aura-Sassafras sandy loams, 5 to 10 percent slopes (AuC).—For practical purposes, these intricately mixed soils have been mapped as a unit. The Sassafras soil is more extensive than the Aura. The differences in the two soils have been previously described under Aura-Sassafras sandy loams, 0 to 5 percent slopes.

In farmed areas, erosion is slight to moderate. The thickness of the surface layer has been reduced to about 8 to 12 inches. Small areas have lost most of the original surface layer, and, as a result, the plow layer is more clayey than normal. Runoff is rapid on the sloping soils of this complex; consequently, erosion is severe unless carefully controlled.

Because of runoff and the risk of erosion, contour planting is needed for peach orchards and for asparagus. The soils are suited to fruit, vegetables, and general farm crops. Capability unit IIIs-1.

Aura-Sassafras sandy loams, 5 to 10 percent slopes, severely eroded (AuC3).—These soils resemble the other Aura-Sassafras sandy loams. They have steeper slopes, however, and they have been eroded much more. The Sassafras soil is the more extensive.

Erosion has removed most of the original surface layer and exposed the more clayey subsoil. The subsoil is very low in organic matter and is harder to cultivate than the original surface layer. Gullies, 1 to 2 feet deep, occur in places. Runoff is rapid, and the risk of further erosion is severe. Crop yields are low. Capability unit IVe-1.

Barclay Series

Barclay soils have a dark grayish-brown surface soil over a mottled yellowish-brown fine sandy loam subsoil and a gray fine sandy loam substratum. The texture is uniform throughout. There is a little more clay in the subsoil than in the surface layer. The Barclay soils have formed on marine deposits of yellowish-brown, loose fine sand. This fine sand contains some mica and, in places, at least a small amount of glauconite. Prolonged wetness of the subsoil has caused the gray colors and the mottling. In farmed areas, drainage has been improved.

These somewhat poorly drained soils occupy nearly level areas. They receive runoff water and possibly underground drainage water from adjoining higher areas. The Barclay soils are only in the area of fine sandy soils (shown by symbol WNB on the general soil map).

spring on areas where these crops are grown. As a result, the surface layer varies in thickness.

On the stronger slopes—2 to 5 percent—water erosion is also a problem. In most fields with these slopes, the surface layer is now only 6 to 10 inches thick. Capability unit IIs-1.

Colts Neck soils, 5 to 10 percent slopes (CoC).—These soils are generally redder than normal for the series because erosion has removed some of the original brown surface horizon. The surface layer ranges from about 6 to 8 inches in thickness.

Shallow gullies are common in places where water concentrates. In some small areas, most of the surface layer has been removed. The subsoil is mixed with the surface soil when these eroded spots are plowed. The plow layer is, therefore, especially red and is more clayey than normal for the series.

These sloping soils erode easily. If erosion is controlled, they are suitable for fruits, vegetables, and general farm crops. Capability unit IIIe-1.

Downer Series

Downer soils have a grayish-brown plow layer over yellowish-brown, light sandy loam subsoil. The subsoil is underlain by sand or gravelly sand.

The soils have formed on sandy marine or stream sediments. They are most common on the terrace of the Delaware River and in parts of the eastern half of the county. These two areas are shown by symbols DWSK and ASD, respectively, on the general soil map. The Downer soils are nearly level to gently sloping and are well drained.

The native vegetation is a mixed forest of oak and pine.

Downer soils occur primarily in association with Klej, Aura, Sassafras, Woodstown, and Lakeland soils. They lack the firm to very firm, clay-coated sand and gravel that characteristically occur in the Aura soils below depths of 20 to 36 inches. They contain less clay in the subsoil than the Sassafras soils. The Downer soils contain more clay in the subsoil than the Lakeland and Klej soils. A more brightly colored subsoil that lacks mottling distinguishes the Downer from the Woodstown soils.

Representative profile (Downer loamy sand, 0 to 5 percent slopes, in an asparagus field one-half mile north of Hardingville):

- A₀ 0 to 10 inches, dark grayish-brown (10YR 4/2) loamy sand; weak, fine, granular structure; very friable to loose; abrupt lower boundary.
- A₂ 10 to 18 inches, yellowish-brown (10YR 5/4) loamy sand; massive to weak, fine, granular structure; very friable; no coarse fragments; abrupt lower boundary.
- B 18 to 30 inches, dark yellowish-brown (10YR 4/4) sandy loam; very weak, fine, subangular blocky structure; friable; slightly sticky; nonplastic; no coarse fragments.
- C 30 to 40 inches, dark-brown (7.5YR 4/4) loamy sand; very weak, fine, granular structure; friable, nonsticky; few quartzose pebbles.
- D 40 to 50 inches, dark-brown (7.5YR 4/4) sand and gravel; single grained; loose; 30 percent of soil mass consists of coarse fragments.

In forested areas, Downer soils develop micropodzol A₂ and B₂ horizons in the uppermost 4 inches. Areas under pitch pine forest have a grayer surface soil than those under hardwood.

The texture of the subsoil ranges from loamy sand to light sandy loam but is most commonly light sandy loam.

Typically, the subsoil is little or no redder than the surface soil. The subsoil is principally yellowish brown and dark yellowish brown, but it has a faint reddish tinge. In Gloucester County, the Downer series includes soils with a thick surface layer of loamy sand and sand. These soils tend to have a more reddish tone in the subsoil than those with a sandy loam surface layer. In places the subsoil has more clay or is redder than is typical for the series.

The average thickness of the subsoil is about 14 inches, but the range is from 10 to 25 inches. In some areas gravel is scattered through the soil or is in beds generally below a depth of 24 inches.

The Downer soils are low in organic matter, clay, and natural fertility. They respond to fertilization, but, because they are sandy, fertilizer that is added will easily leach from the soils. The soils are well drained and are easily worked. They are moderately droughty, and so they are best suited to deep-rooted perennial vegetables and fruits, sweetpotatoes, and irrigated vegetables. Because of the sandy surface layer, the soils are subject to wind erosion if not protected.

Downer loamy sand, 0 to 5 percent slopes (DoB).—A profile of this soil is described as representative of the series. In some places, however, the B horizon consists of sandy loam bands, 1 inch to 2 inches thick, interspersed in 4 to 6 inches of loamy sand. Spots of Lakeland soil with very sandy subsoil are included in some areas.

Normally, the ground water is well below a depth of 30 inches. In some areas, however, it is higher during winter. Such areas are small in cropland but are large in woodland, where the survey was more generalized. In some small areas, wind or water erosion has reduced the thickness of the surface layer from about 20 inches to 14 inches or less. In other areas, especially along hedge-rows, sand has drifted over the normal soil and is 1 foot or more in depth.

This soil is suited to asparagus and other deep-rooted perennials, fruits, early vegetables, and sweetpotatoes. It is easy to work and warms early in spring, but it is droughty and is easily blown. Capability unit IIs-1.

Downer sandy loam, 0 to 2 percent slopes (DsA).—The surface horizon of this soil averages between 10 and 14 inches in thickness. It is thicker in some places because of deposits from higher adjoining areas. **Ground water generally occurs at depths of 5 to 10 feet.** In some places firm layers, 1 to 2 inches thick, are in the C and D horizons. In places the subsoil is more clayey than normal.

This soil is suitable for many kinds of crops. Capability unit I-1.

Downer sandy loam, 2 to 5 percent slopes (DsB).—Except for stronger slopes, this soil is like Downer sandy loam, 0 to 2 percent slopes. It is suited to many kinds of crops. Capability unit IIe-1.

Dragston Series

Dragston soils have a dark grayish-brown surface layer, mottled in the lower part, that overlies a mottled sandy loam to sandy clay loam subsoil. The substratum is loamy sand and contains various amounts of gravel and, in places, lenses of clay. Its color in most places

TABLE 8.—Estimated suitability of the

Map symbols	Soil groups and soil mapping units	Individual uses			
		Building sites	Septic tanks (percolation of water below a depth of 28 inches)	Landscaping	
				Trees and shrubs	Lawns
FtE	Group 14..... Freehold, Colts Neck, Collington soils, 15 to 25 percent slopes.	Poor because of steep slopes.	Fair, but installation difficult and costly because of steep slopes.	Fair.....	Fair because of erosion hazard on steep slopes.
FtF	Freehold, Colts Neck, Collington soils, 25 to 40 percent slopes.				
SsE	Sassafras soils, 15 to 40 percent slopes.				
WHE	Westphalia soils, 15 to 40 percent slopes.	Poor because of steep slopes.	Poor because of slow permeability.	Fair.....	Fair because of erosion hazard on steep slopes.
MrE	Group 15..... Marlton sandy loam, 15 to 25 percent slopes.				
MrF	Marlton sandy loam, 25 to 40 percent slopes.				

Formation and Classification of Soils

This section consists of three main parts. In the first part, the formation of the soils is discussed; in the second part, the soil series are classified by great soil groups; and in the third part, the results of soil analyses of two soil types are given.

Formation of the Soils

The important factors of the environment that have influenced the formation of the soils of Gloucester County are (1) parent material, (2) climate, (3) topography, (4) biological activity, and (5) time. A discussion of these factors follows.

Parent material

All the soils of Gloucester County have formed on unconsolidated beds of either sand or clay mixed with silt or gravel. These beds were laid down in a succession of ocean or river deposits. At times the water was deep; at other times it was shallow. In addition, the beds were

tilted to the southeast. The elevation of the land increases in a southeasterly direction from the Delaware River (fig. 13).

Following the withdrawal of the ocean at different periods, there was a vast amount of wind and water erosion on the barren land. Although glaciers did not reach as far south as this county, it is believed that water from melting glaciers covered most of the county. Certainly the climate of the area was affected by the great ice sheet that came within 70 miles of the northern border of the county.

The main geologic formations and the soil series developed from them are listed in table 9. This table gives characteristics of the formations and shows the different degrees of drainage under which the soils have developed. Blank spaces on table 9 indicate that a soil of the given drainage class on the formation named is not present in significant areas in this county. Except where the geologic materials are mixed, there is much relationship between geologic formation and the soil that has formed.




Figure 13.—Section from the Delaware River to Blue Bell showing the main geologic formations and their thicknesses. Vertical scale exaggerated. Sketch is based on "Geologic Map of New Jersey" (4) and Bulletin 50, "The Geology of New Jersey" (3).

TABLE 9.—*Geologic formations, some of their characteristics,*

Geologic formations ¹	Thickness	Probable yield of well water	Type of clay	Soils developed
				Excessively drained
Cape May formation.....	Feet 0-30	Gallons per minute (2)		
Pensauken formation.....	0-60	(2)		
Bridgeton formation.....	0-30	(2)		
Cohansey sand.....	100-250	5-100	Kaolinite, some illite.....	Lakewood, Lakeland.....
Kirkwood formation:				
Fine sand.....	100	10-50		
Clay.....			Illite.....	
Vincetown sand.....	25-100	10-200		
Hornerstown marl ²	30			
Navesink marl ²	25-40			
Mt. Laurel sand.....	5-60			
Wenonah sand.....	35-20	20-100		
Marshalltown formation.....	30-40		Illite.....	
Englishtown sand.....	20-140			
Woodbury clay.....	50		Illite.....	
Merchantville clay.....	50-60			
Magothy formation.....	25-175			
Raritan formation.....	150-300	10-1, 400		Not exposed at the surface

¹ Listed in order, from youngest to oldest formation.² In places small, shallow wells provide a moderate supply of water.

Westphalia soils have a distinct subsoil of fine sandy loam, and, under pines, Lakewood soils consist of loose fine sand. Field tests have not shown any significant difference in the acidity of soils developed under hardwoods or pines.

Since most undisturbed soils in upland woodlands contain very few earthworms, there is a minimum of soil mixing before the soil is limed and fertilized. Ants, termites, and, in places, the cicada are probably most active in destroying soil horization. In places ants bring up yellowish-brown subsoil almost as fast as rainfall bleaches the sand grains at the surface.

Time

In most of the soils of the county, including those developed in young material (an estimated 15,000 years old) along the Delaware River, there has been sufficient time and rainfall to leach out of most of the readily soluble bases and thus make the soil strongly acid in reaction. Movement of clay out of the A horizon and into the B horizon has progressed far enough so that the increase of clay is apparent in the subsoil. These processes have had time to occur in all the soils except those developing in very recent alluvium.

The estimated maximum age (about 150 million years) of the oldest geological material is really of little significance to soil-forming processes because of the length of time that this material was covered by water or by other geologic beds.

Classification of Soil Series by Great Soil Groups ⁶

In this section the soil series of the county have been placed in a higher category of classification—the great soil group. A great soil group is a broad group of soils, all of which have the same general chemical and physical properties and sequences of horizons.

Gray-Brown Podzolic soils

This great soil group consists of soils that have a comparatively thin organic covering and organic-mineral layers over a grayish-brown leached layer that rests upon an illuvial brown horizon. The soils appear to have developed under a deciduous forest in a temperate, moist climate.

Gray-Brown Podzolic soils intergrading to Red-Yellow Podzolic soils.—Unplowed areas of these soils have a thin covering of humus, an inch to a few inches thick; an A₁ horizon, stained with organic matter, 2 to 4 inches thick; a yellowish-brown or grayish-brown A₂ horizon that is slightly leached; and a textural B horizon of accumulated clay that is brown, strong brown, or yellowish brown (olive brown or olive in parts of the county where there is a considerable amount of glauconite in the soil). Under natural conditions, these soils have a pH of below 5.0.

⁶ GRANVILLE A. QUAKENBUSH, State soil scientist for New Jersey, helped to prepare this section.

and soils that have developed from them

Soils developed—Continued				
Well drained	Moderately well drained	Somewhat poorly drained	Poorly drained	Very poorly drained
Sassafras, Downer	Klej, Woodstown	Klej, Dragston	Fallsington	Pocomoke.
Sassafras, Aura	Woodstown	Dragston	Fallsington	Pocomoke.
Aura, Sassafras, Downer	Woodstown	Dragston	Fallsington	Pocomoke.
Downer	Lakehurst, Klej, Woodstown	Lakehurst, Klej, Dragston	Leon, Fallsington	St. Johns, Pocomoke.
Westphalia	Nixonton	Barclay	Pasquotank	Bayboro.
Freehold	Keyport	Lenoir	Elkton	
Marlton	Marlton	Kresson	Colemantown	Matlock.
Freehold				
Collington, Colts Neck				
Freehold				
in Gloucester County				

³ This material, called marl, is highly glauconitic.

TABLE 10.—*Soil series arranged according to subsoil texture and natural drainage*

Subsoil texture ¹	Natural drainage classes					
	Excessively drained	Well drained	Moderately well drained	Somewhat poorly drained	Poorly drained	Very poorly drained
	Uniform colors to a depth of 30 inches; loamy sand or sand B horizon	Uniform colors to a depth of 30 inches; sandy loam or more clayey B horizon	Uniform colors to a depth of 20 inches; mottled colors or distinctly paler colors between depths of 20 and 30 inches	Dark grayish-brown surface layer; mottled colors or distinctly paler color between depths of 10 and 20 inches	Dark-gray surface layer; light-gray or olive subsoil, with or without mottling	Nearly black surface layer; light-gray or olive subsoil, with or without mottling
Sand or loamy sand (nonglauconitic).	Lakewood, Lakeland.		Lakehurst, Klej.	Lakehurst, Klej.	Leon	St. Johns.
Sandy loam to sandy clay loam: Nonglauconitic material.		Downer, Sassafras, Aura.	Woodstown	Dragston	Fallsington	Pocomoke.
Glauconitic material: Fine sandy loam.		Westphalia	Nixonton	Barclay	Pasquotank	
Medium sandy loam to sandy clay loam.		Collington, Colts Neck, Freehold.				
Clay: Nonglauconitic material.			Keyport	Lenoir	Elkton	Bayboro.
Glauconitic material.		Marlton	Marlton	Kresson	Colemantown	Matlock.

¹ Subsoil texture listed in order of increasing content of clay.

HYDROGEOLOGIC FRAMEWORK OF THE NEW JERSEY COASTAL PLAIN

REGIONAL AQUIFER-SYSTEM ANALYSIS

U.S. GEOLOGICAL SURVEY
Open-File Report 84-730




Table 2. Geologic and hydrogeologic units in the Coastal Plain of New Jersey.

SYSTEM	SERIES	GEOLOGIC UNIT	LITHOLOGY	HYDROGEOLOGIC UNIT	HYDROLOGIC CHARACTERISTICS
Quaternary	Holocene	Alluvial deposits	Sand, silt, and black mud.	Undifferentiated	Surficial material, often hydraulically connected to underlying aquifers. Locally some units may act as confining beds. Thicker sands are capable of yielding large quantities of water.
		Beach sand and gravel	Sand, quartz, light-colored, medium- to coarse-grained, pebbly.		
	Pleistocene	Cape May Formation			
Tertiary	Miocene	Pensaiken Formation	Sand, quartz, light-colored, heterogeneous, clayey, pebbly.	Kirkwood-Cohansey aquifer system	A major aquifer system. Ground-water occurs generally under water-table conditions. In Cape May County the Cohansey Sand is under artesian conditions.
		Bridgeton Formation			
		Beacon Hill Gravel	Gravel, quartz, light colored, sandy.		
		Cohansey Sand	Sand, quartz, light-colored, medium to coarse-grained, pebbly; local clay beds.		
		Kirkwood Formation	Sand, quartz, gray and tan, very fine- to medium-grained, micaceous, and dark-colored diatomaceous clay.	confining bed	Thick diatomaceous clay bed occurs along coast and for a short distance inland. A thin water-bearing sand occurs within the middle of this unit.
				Rio Grande w-bz	
				confining bed	
				Atlantic City 800-foot sand	A major aquifer along the coast.
					Alloway Clay member or equivalent
				Piney Point aquifer	Yields moderate quantities of water locally.
	Eocene	Piney Point Formation	Sand, quartz and glauconite, fine- to coarse-grained.	Piney Point aquifer	Poorly permeable sediments.
		Shark River Formation	Clay, silty and sandy, glauconitic, green, gray and brown, fined-grained quartz sand.		
		Manasquan Formation			
	Paleocene	Vincentown Formation	Sand, quartz, gray and green, fine- to coarse-grained, glauconitic, and brown clayey, very fossiliferous, glauconite and quartz calcarenite.	Vincentown aquifer	Yields small to moderate quantities of water in and near its outcrop area.
		Hornerstown Sand	Sand, clayey, glauconitic, dark green, fine- to coarse-grained.		
Cretaceous	Upper Cretaceous	Tinton Sand		Composite	Poorly permeable sediments.
		Red Bank Sand	Sand, quartz, and glauconite, brown and gray, fine- to coarse-grained, clayey, micaceous.		
		Navesink Formation	Sand, clayey, silty, glauconitic, green and black, medium- to coarse-grained.		
		Mount Laurel Sand	Sand, quartz, brown and gray, fine- to coarse-grained, slightly glauconitic.		
		Wenonah Formation	Sand, very fine- to fine-grained, gray and brown, silty, slightly glauconitic.		
		Marshalltown Formation	Clay, silty, dark greenish gray, glauconitic quartz sand.		
		Englishtown Formation	Sand, quartz, tan and gray, fine- to medium-grained, local clay beds.		
		Woodbury Clay	Clay, gray and black, micaceous silt.		
		Merchantville Formation	Clay, glauconitic, micaceous, gray and black; locally very fine-grained quartz and glauconitic sand.		
		Magothy Formation	Sand, quartz, light-gray, fine- to coarse-grained; local beds of dark-gray lignitic clay.		
	Lower Cretaceous	Raritan Formation	Sand, quartz, light-gray, fine- to coarse-grained, pebbly, arkosic, red, white, and variegated clay.	Potomac-Raritan Magothy aquifer system	A major aquifer system. In the northern Coastal Plain the upper aquifer is equivalent to the Old Bridge aquifer and the middle aquifer is the equivalent of the Farrington aquifer. In the Dela. River Valley three aquifers are recognized. In the deeper subsurface, units below the upper aquifer are undifferentiated.
		Potomac Group	Alternating clay, silt, sand, and gravel.		
				upper aquifer	
				conf bd	
				middle aquifer	
Pre- Cretaceous		Bedrock	Precambrian and lower Paleozoic crystalline rocks, metamorphic schist and gneiss; locally Triassic basalt, sandstone and shale.	Bedrock confining bed	No wells obtain water from these consolidated rocks, except along Fall Line.

¹ Rio Grande water-bearing zone.

² ----- Minor aquifer not mapped in this report.

Modified from Seaber, 1965, table 3.

and structure contour maps of this unit are not given in this report. Tops and thicknesses of the Rio Grande water-bearing zone can be calculated from the hydrogeologic sections.

The Rio Grande water-bearing zone is utilized mainly in southern Cape May County, where aquifer thicknesses can exceed 100 ft. It is generally less than 40 ft thick throughout much of the coastal areas in southern Ocean and Atlantic Counties. The aquifer is seldom used outside of southern Cape May County and is of minor importance. Therefore, in this report, the Rio Grande water-bearing zone has been included as part of the confining bed overlying the 800-foot sand shown on plate 22.

Kirkwood-Cohansey Aquifer System

The Kirkwood-Cohansey aquifer system is predominantly a water-table aquifer that underlies an area of approximately 3,000 mi² southeast of the updip limit of the outcrop of the Kirkwood Formation. This aquifer system is composed of the Kirkwood Formation, Cohansey Sand, and, depending on location, can include overlying deposits of the Beacon Hill Gravel, Bridgeton Formation, and Cape May Formation (Rhodehamel, 1973). The Kirkwood-Cohansey aquifer system is confined by overlying Pleistocene deposits on the peninsular part of Cape May County.

The lithology of the Kirkwood Formation, as indicated previously, is variable. Along coastal areas thick clay beds are dominant with interbedded zones of sand and gravel. In the subsurface, updip from the coast, fine to medium sand and silty sand are common, and regionally extensive clay beds occur only in the basal part of the formation.

The Cohansey Sand, also of Miocene age, is coarser grained than the underlying Kirkwood Formation. It is predominantly a light-colored quartz sand containing minor amounts of pebbly sand, fine- to coarse-grained sand, silty and clayey sand, and interbedded clay (Rhodehamel, 1973, p. 24). Some local clay beds within the Cohansey Sand are relatively thick. Locally, perched water tables and semiconfined conditions can exist in the Kirkwood-Cohansey aquifer system.

Overlying the Cohansey Sand are the Beacon Hill Gravel and the Bridgeton Formation, both considered to be Miocene fluvial deposits (Owens and Minard, 1979). The Beacon Hill Gravel overlies the Cohansey Sand only in remnant patches on the highest hills between Clarksburg, Monmouth County, and Warren Grove, Ocean County, where it can be as much as 40 ft thick (Owens and Minard, 1979, p. D6). The coarse-grained sand and gravel of the Bridgeton Formation are more widespread and can generally add 30 to 50 ft of thickness to the aquifer system in parts of Camden, Gloucester, Salem, Cumberland, Atlantic, and Cape May Counties (Owens and Minard, 1979, p. D14).

Throughout most of Cape May County, the Pleistocene Cape May Formation directly overlies the Cohansey Sand. Gill (1962, p. 21) divided the Cape May Formation into four distinct environmental facies. In order of deposition they are: estuarine sand, estuarine clay, marine sand, and deltaic sand. Gill (1962, fig. 2) has shown that in the northern half of Cape May County and along the coast as far south as Stone Harbor, the Cohansey Sand is in hydraulic connection with the overlying marine and deltaic sand facies. The marine sand facies of the Cape May Formation adds as much as 100 ft to the thickness of the Kirkwood-Cohansey aquifer system in the northern half of Cape May County. On the peninsular part of Cape May County, the Cohansey Sand is generally in hydraulic connection with the estuarine sand facies but is confined by the overlying estuarine clay facies (Gill, 1962, fig. 2). The estuarine clay facies generally ranges from 25 to 125 ft in thickness (Gill, 1962, p. 27).

The base of the Kirkwood-Cohansey aquifer system is shown on plate 23. The map illustrates two major regional basal surfaces for the water-table aquifer. The two surfaces are differentiated by the double-dashed line representing the approximate westward limit of the major confining bed overlying the Atlantic City 800-foot sand. The basal surface for the Kirkwood-Cohansey aquifer system west of this line is the top of the clay bed lying within the lower part of the Kirkwood Formation. This clay bed, as shown on hydrogeologic sections F-F' (pl. 4) and L-L' (pl. 5), is the updip extension of the confining bed underlying the 800-foot sand, and is probably the equivalent of the Alloway Clay Member of the Kirkwood Formation described by Nemickas and Carswell (1976).

The basal surface east of the double-dashed line is the top of the thick diatomaceous clay bed that overlies the Atlantic City 800-foot sand. The discontinuity in the structure contours on the base of the unconfined system at the double-dashed line is caused by the presence of this clay bed. The base of the aquifer system directly updip from the northwestern limit of the confining bed generally lies more than 350 ft below sea level. At Egg Harbor City, Atlantic County, several miles downdip from the western limit of the confining bed, the base of the water-table aquifer is only 160 ft below sea level. The difference in altitudes of the two basal surfaces of the Kirkwood-Cohansey aquifer system is shown diagrammatically in figure 5.

The thickness of the confining bed underlying the Kirkwood-Cohansey aquifer system west of the double-dashed line is shown on plate 18 as the composite confining bed. If, in more detailed studies, the Vincentown and Piney Point aquifers are considered to be important, the thickness of the confining bed between the base of the unconfined aquifer and these minor aquifers can be calculated by comparing the maps of the tops of the Vincentown (pl. 19) and Piney Point (pl. 20) aquifers with the base of the Kirkwood-Cohansey aquifer system west of the double-dashed line (pl. 23).

It is important to note that the Cohansey Sand is a confined aquifer beneath the peninsular portion of Cape May County. However, on plate 23, structure contours have been extended throughout Cape May County to illustrate the base of the confined Cohansey Sand. Information regarding the water-table system in Cape May County can be found in Gill (1962).

The extent of the confining bed overlying the Atlantic City 800-foot sand partly determines the thickness of the Kirkwood-Cohansey aquifer system. An abrupt change in the thickness of the Kirkwood-Cohansey aquifer system at the double-dashed line is shown on plate 24. The water-table aquifer thickens downdip from less than 50 ft at the Kirkwood outcrop to more than 400 ft near the edge of the upper confining bed of the Atlantic City 800-foot sand. In areas where this clay bed occurs in the subsurface, the aquifer thickness ranges from about 140 ft along the northwestern extent of the clay bed to approximately 400 ft in the Atlantic City area.

The aquifer-thickness map for the Kirkwood-Cohansey aquifer system represents not only the saturated thickness of the water-table aquifer but also the unsaturated section. The thickness of the aquifer at each control point represents the total thickness of the unit calculated by subtracting the depth of the basal confining bed from the altitude of land surface.

SUMMARY AND CONCLUSIONS

The Coastal Plain of New Jersey is a seaward-dipping wedge of unconsolidated sediments that range in age from Cretaceous to Quaternary. These sediments are composed of clay, silt, sand, and gravel and include continental, coastal, and marine-type deposits.

Hydrogeologic units described in this report can differ from formal stratigraphic units because a geologic formation can contain more than one aquifer, a formation may function as an aquifer in one area and as a confining bed in another, or an aquifer or confining bed may be composed of several geologic formations.

The occurrence and configuration of 15 regional hydrogeologic units have been defined within the Coastal Plain of New Jersey based on the interpretation of borehole geophysics data. Structure-contour maps and aquifer thickness maps are provided for nine aquifers listed in ascending order:

1. Lower aquifer of the Potomac-Raritan-Magothy aquifer system
2. Middle aquifer of the Potomac-Raritan-Magothy aquifer system
3. Upper aquifer of the Potomac-Raritan-Magothy aquifer system
4. Englishtown aquifer system
5. Wenonah-Mount Laurel aquifer
6. Vincentown aquifer
7. Piney Point aquifer



endangered & threatened species of new jersey

USDA, Soil Conservation Service - Somerset, N.J.

N.J. Department of
and Wildlife


ATTACHMENT E

BOG TURTLE

Clemmys muhlenbergi

Distinguishing Characteristics: The smallest native North American turtle, the bog turtle ranges in size from 3 to 3½ inches (8 to 9 cm). Its slightly keeled carapace varies in color from a light brown to black. The turtle's limbs and fleshy parts are usually brown and may be flecked with red-orange. The most distinguishing characteristic, however, is the large orange or yellow patches on both sides of the head.


Distribution and Habitat: The secretive bog turtle occurs in disjunct populations of highly specialized habitat. Open sphagnum bogs, swamps, and marshy meadows having clear, slow-moving streams with soft muddy bottoms serve as optimal habitats. Sedge tussocks, skunk cabbage, cattail, jewelweed, and smartweed are common flora of bog turtle habitats. Throughout its range, from southern Massachusetts to Southwestern North Carolina, this species is considered rare. One of the largest concentrations of the turtle is found in New Jersey, specifically in the coastal plain county of Monmouth, and the noncoastal, Warren, Sussex, Morris, Passaic, and Union Counties.



R. Zappalorti

Marshy meadows serve as optimal bog turtle habitat.

Status: Endangered (State). These turtles were probably never numerous; few eggs are laid and juveniles are subject to high mortality. Man's activities have been reclaiming bog turtle habitat for agriculture and urban development and these environmental alterations disrupt the bog turtle's precise semiaquatic requirements. Such alterations include the raising or lowering of the water table within the habitat because of mosquito



Bog Turtle

R. Zappalorti

control and agricultural drainage ditches, construction of roadways, and water impoundments.

Management Techniques and Protective Measures: The bog turtle is protected in New Jersey by its state endangered status. Field surveys are most productive when conducted at times of low vegetative growth. Studies of the known and suspected habitats suggest that all these areas be protected. Bog turtles disappear in an area when the muddy substrate and associated flora are replaced by hardwood trees such as red maples. The result of this natural succession suggests habitat management by harvesting of some of these trees to keep an open canopy.

Recommendations: Projects possibly affecting water levels in bog turtle habitat areas must be carefully considered. Pure unpolluted water is critical for the species' survival in natural bogs and marshes, so wetland ecosystems should be preserved in a healthy state. Because the turtle's habitat is so dependent upon a naturally succeeding environment, normal distribution corridors along effluent streams must be kept open rather than blocked by highways and other construction.

Bog turtle colonies occur in small disjunct populations within the breeding ranges.



MEMO

NEW JERSEY STATE DEPARTMENT OF ENVIRONMENTAL PROTECTION

TO FILE

FROM FRANK FARANCA, HSMS IV, BUREAU OF PLANNING AND ASSESSMENT 4-13-87

SUBJECT MONROE TWP MUNICIPAL WELL #4 & #5

On 4-9-87 and 4-13-87 the writer conducted a site reconnaissance of Monroe Township Municipal Wells #4 & #5.

The writer met with Mr. George Cassabone, Supervisor of Monroe Twp. Municipal Utilities Authority on 4-9-87. Mr. Cassabone and the writer conducted a windshield survey of Wells #4 & #5, of which #4 is not currently in use. He explained that Monroe Township M.U.A. currently has 4670 services and the current population is 26,000 people.

On 4-13-87 the writer investigated several areas within Williamstown as possible sources contributing to the present mercury contamination of the ground water. Two sites are believed to be suspect for further investigation.

1. The Atlantic City Electric Company - Williamstown Substation
This parcel of land is located adjacent to Clayton Road (Franklinville - Williamstown Road) on Block 13301, Lot 14. The owner is located at P.O. Box 1500, Pleasantville, NJ 08232. The site is 2.06 acres and contains several rows of oil circuit breakers, transformers and a capacitor bank. The soil within the substation is void of all vegetation and appears stained in several areas.
2. The Gravel Pit
This parcel of land is also located adjacent to Clayton Road on Block 13301, Lot 11 & 12. The owner is Thomas H. Webb Jr., Rd 7, Box 175, Jackson Road, Williamstown. This site is approximately 10.24 acres which is an inactive gravel pit. The pit itself has had unauthorized dumping of assorted solid waste over many years. A large portion of the gravel pit is devoid of vegetation, and is currently used by the neighbors for the use of recreational all-terrain vehicles. The solid waste is mostly old concrete, asphalt, soil, landscape debris and household trash.

These two sites were in operation prior to the detection of mercury in Well #4 in 1976. An analysis of the USGS Topographic Series Maps reveal that these sites are prime candidates as sources of contamination based upon the hydraulic movement of surface water and ground water to down gradient Wells #4 & #5.

Also suspect is the land on which the Williamstown High School is now located. In the past Mr. Frank Sime1 owned the land and used it as a farm for spinach and lettuce. However, the use of mercury as a fungicide is not usually associated with these two food crops.

FF:mz

ATTACHMENT

F

MEMONEW JERSEY STATE DEPARTMENT OF ENVIRONMENTAL PROTECTION

TO FILE

FROM FRANK FARANCA, HSMS IV, BUREAU OF PLANNING AND ASSESSMENT DATE 4/7/88

SUBJECT TELECON W/MONROE TWP., M.V.A. SUPERINTENDENT

On 3/29/88 the writer held a telephone conversation with George Cassabone, Water Superintendent of Monroe Township Municipal Utilities Authority. Mr. Cassabone explained that the current population in Monroe Township is 28,000 people, the township size is 51 square miles, and the number of M.U.A services are 4800.

FF:ma2

ATTACHMENT G



FRANK FARANCA

Flared End pg 7
Notices - p 13

TECHNICAL MANUAL FOR STREAM ENCROACHMENT



AUGUST, 1984

Prepared by:

Bureau of Flood Plain Management

ATTACHMENT H

APPENDIX E

CLASSIFICATION OF NEW JERSEY WATERS AS RELATED
TO THEIR USE BY ANADROMOUS FISH

Prepared by the Bureau of Freshwater Fisheries
Division of Fish, Game and Wildlife
Department of Environmental Protection

APRIL 1984

ATTACHMENT H

<u>Waterway</u>	<u>Species</u>	<u>Map Ref. No.</u>
Doughty Creek, Atlantic Ocean Drainage, Atlantic County	herring (C)	68
English Creek, Great Egg Harbor - Drainage, Atlantic County	herring (R)	
Fenwick Creek, Salem River Drainage, Salem County	herring (C)	25
Fiddlers Creek, Delaware River Drainage, Mercer County	herring (C)	3
Flat Creek, Tuckahoe River Drainage, Cape May County	herring (C)	53
Forked River, Ocean County	herring (R)	
Fresh Creek, Barnegat Bay Drainage, Ocean County	herring (C)	82
Gibson Creek, Great Egg Harbor Drainage	herring (C)	60
Gravelly Run, Great Egg Harbor Drainage	herring (C)	64
Great Egg Harbor River	herring (C) A. shad (E)	66
Green Creek	A. shad (E)	
Greenies Sandwash, Maurice River Drainage	herring (C)	42
Gunning River, Barnegat Bay Drainage, Ocean County	herring (C)	83
Hackensack River	herring (C) A. shad (E)	132
Halfway Creek, Tuckahoe River Drainage	herring (R)	
Hammonton Creek, Mullica River Drainage	herring (C)	76
Hankins Brook, Maurice River Drainage	herring (C)	43
Hawkins Creek, Great Egg Harbor Drainage	herring (C)	
Haystack Brook, Metedeconk River Drainage	herring (R)	

MONROE TWP MUNICIPAL WELLS #4 & #5
MONROE TWP/GLOUCESTER COUNTY
NEW JERSEY
EPA # NJD980769699

The Monroe Township Municipal Wells #4 & #5 are located respectively on Washington Avenue and Chestnut Street, Williamstown, Gloucester County. These wells have an intervening distance of 1200 feet and are owned and operated by the Monroe Township Municipal Utilities Authority (MTMUA).

A program for sampling raw water sources throughout the state revealed mercury contamination in Monroe Municipal Wells #4 & #5 on June 21, 1976. The levels of mercury that were in the municipal water system were as high as 10.8 ppb. This level is far in excess of the maximum contaminant level for total mercury of 2.0 ppb promulgated by the USEPA pursuant to the Safe Drinking Water Act.

These wells are underlain by the Quarternary Bridgeton Formation which is characterized by gravel and sand in part solidified by iron oxide. The water bearing unit in which Well #4 & #5 are located is the Cohansey Aquifer. The depth of Well #4 and #5 are 106 and 160 feet respectively. There are also two surface water swails leading to the Squankum Branch and the Hospitality Branch of Great Egg Harbor River.


The sampling and analysis of an individual domestic well owned by the Monroe Township Board of Education revealed total mercury as high as 3.6 ppb on July 17, 1986. This well is located in a maintenance building adjacent to the Williamstown High School on Clayton Avenue in Williamstown. This well is also located at the South-West limit of the MTMUA water supply system.

Immediately after the discovery of mercury contamination in the public water system, Well #4 was taken out of service and was retained only for emergency situations. Well #5 was kept in service because levels of mercury experienced at this well were at or slightly below the maximum contaminant level. Since that time the level of mercury has steadily decreased in both wells.

At present it is not known conclusively where the source of the contamination is located. However, there are two potential sources. The first potential source is the Williamstown Substation of the Atlantic City Electric Company. This site is located adjacent to the high school property on Clayton Road. The second, and more probable source of contamination is an inactive gravel pit also located on Clayton Road. This site has had unauthorized dumping of assorted solid waste over many years since its closure.

It is recommended that this site be referred to NJDEP/Division of Water Resources for a comprehensive sampling and analysis of the ground water in Williamstown. This will provide additional information to determine the extent and source of the contamination. All environmental sampling undertaken by the NJDEP should be closely coordinated and integrated with the Gloucester County Health Department which is also aware of this problem.

Submitted by:



Frank Faranca, HSMS IV
NJDEP/DHWM/BPA
MSCA Project

Hours worked: 47

FF:mz



Preliminary Assessment

Monroe Township Municipal Wells #4 & #5

#4 - Washington Avenue

#5 - Chestnut & Water Streets

Monroe Township/Gloucester County

New Jersey

EPA #NJD980769699



POTENTIAL HAZARDOUS WASTE SITE
PRELIMINARY ASSESSMENT
PART 1 - SITE INFORMATION AND ASSESSMENT

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
NJ D9807 69699

II. SITE NAME AND LOCATION

01 SITE NAME (Legal, common, or descriptive name of site) Monroe Township Municipal Wells #4 & #5		02 STREET, ROUTE NO., OR SPECIFIC LOCATION IDENTIFIER Washington Ave; Chestnut & Water St.			
03 CITY Monroe Township	04 STATE NJ	05 ZIP CODE 08094	06 COUNTY Gloucester	07 COUNTY CODE 08	08 CONG DIST
09 COORDINATES LATITUDE 39 38 55		LONGITUDE 75 03 40		Well #4: Block 3202, Lot 17 Well #5: Block 11602, Lot 2	
10 DIRECTIONS TO SITE (Starting from nearest public road) From Trenton, take Route 295 South to Route #42. Follow Route #42 South to Williamstown.					

III. RESPONSIBLE PARTIES

01 OWNER (If known) Monroe Twp. M.U.A.		02 STREET (Business, home, residential) 372 South Main Street			
03 CITY Williamstown	04 STATE NJ	05 ZIP CODE 08094	06 TELEPHONE NUMBER 1609 629-7586	George Cassabone	
07 OPERATOR (If known and different from owner)		08 STREET (Business, home, residential)			
09 CITY	10 STATE	11 ZIP CODE	12 TELEPHONE NUMBER ()		
13 TYPE OF OWNERSHIP (Check one) <input type="checkbox"/> A. PRIVATE <input type="checkbox"/> B. FEDERAL <input type="checkbox"/> C. STATE <input type="checkbox"/> D. COUNTY <input checked="" type="checkbox"/> E. MUNICIPAL <input type="checkbox"/> F. OTHER <input type="checkbox"/> G. UNKNOWN					

14 OWNER OPERATION NOTIFICATION ON FILE (Check one)
☐ A. RCRA 3001 DATE RECEIVED: MONTH DAY YEAR ☒ B. UNCONTROLLED WASTE SITE (RCRA 103(c)) DATE RECEIVED: MONTH DAY YEAR ☐ C. NONE

IV. CHARACTERIZATION OF POTENTIAL HAZARD

01 ON SITE INSPECTION <input checked="" type="checkbox"/> YES DATE 2 8 77 <input type="checkbox"/> NO		BY (Check all that apply) <input type="checkbox"/> A. EPA <input type="checkbox"/> B. EPA CONTRACTOR <input checked="" type="checkbox"/> C. STATE <input type="checkbox"/> D. OTHER CONTRACTOR <input type="checkbox"/> E. LOCAL HEALTH OFFICIAL <input type="checkbox"/> F. OTHER: (Specify) CONTRACTOR NAME(S):			
02 SITE STATUS (Check one) <input checked="" type="checkbox"/> A. ACTIVE <input type="checkbox"/> B. INACTIVE <input type="checkbox"/> C. UNKNOWN		03 YEARS OF OPERATION 1951 1976 <input type="checkbox"/> UNKNOWN BEGINNING YEAR ENDING YEAR			

04 DESCRIPTION OF SUBSTANCES POSSIBLY PRESENT, KNOWN, OR ALLEGED
Inorganic mercury


05 DESCRIPTION OF POTENTIAL HAZARD TO ENVIRONMENT AND/OR POPULATION
Inorganic mercury was detected in public supply wells #4 and #5 as high as 6.4 ppb on 7/19/76. Mercury was also detected in a potable well at the limit of the Monroe MUA Public Water Supply System.

V. PRIORITY ASSESSMENT

01 PRIORITY FOR INSPECTION (Check one: If high or medium is checked, complete Part 2 - Waste Information and Part 3 - Description of Hazardous Conditions and Problems)
☐ A. HIGH ☒ B. MEDIUM ☐ C. LOW ☐ D. NONE
(Inspection required immediately) (Inspection required) (Inspection on site available basis) (No further action needed - complete current inspection form)

VI. INFORMATION AVAILABLE FROM

01 CONTACT George Cassabone, Superintendent Monroe Twp. M.U.A.		02 OF (Agency/Organization)		03 TELEPHONE NUMBER (609) 629-7586	
04 PERSON RESPONSIBLE FOR ASSESSMENT Frank Faranca, HSMS IV		05 AGENCY NJDEP	06 ORGANIZATION DHWM/BPA	07 TELEPHONE NUMBER (609) 633-2219	08 DATE 04 14 87 MONTH DAY YEAR



<input type="checkbox"/> A TOXIC	<input type="checkbox"/> E SOLUBLE	<input type="checkbox"/> I. HIGHLY VOLATILE
<input type="checkbox"/> B CORROSIVE	<input type="checkbox"/> F INFECTIOUS	<input type="checkbox"/> J EXPLOSIVE
<input type="checkbox"/> C RADIOACTIVE	<input type="checkbox"/> G FLAMMABLE	<input type="checkbox"/> K. REACTIVE
<input type="checkbox"/> D PERSISTENT	<input type="checkbox"/> H IGNITABLE	<input type="checkbox"/> L INCOMPATIBLE
		<input type="checkbox"/> M NOT APPLICABLE

EPA FORM 2070-12 (7-81)



POTENTIAL HAZARDOUS WASTE SITE
PRELIMINARY ASSESSMENT

PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

I. IDENTIFICATION

01 STATE NJ 02 SITE NUMBER D980769699

II. HAZARDOUS CONDITIONS AND INCIDENTS

01 ☒ A. GROUNDWATER CONTAMINATION 02 ☒ OBSERVED (DATE 7-19-76) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: 8254 04 NARRATIVE DESCRIPTION

Public supply wells #4 and #5 were sampled in 1976 and mercury was detected as high as 6.4 ppb. More recently, a potable well was found to contain 3.6 ppb on 7/17/86. Attachment B3, B6 and C

01 ☒ B. SURFACE WATER CONTAMINATION 02 ☐ OBSERVED (DATE _____) ☒ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION

Surface and subsurface discharge may have contributed to surface water contamination of the Squankum Branch and the Hospitality Branch of the Great Egg Harbor River.

Map 1

01 ☐ C. CONTAMINATION OF AIR 02 ☐ OBSERVED (DATE _____) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION

No potential exists for the mercury in the ground water to contaminate the air.

01 ☐ D. FIRE/EXPLOSIVE CONDITIONS 02 ☐ OBSERVED (DATE _____) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION

No potential exists for the fire/explosive conditions due to the nature of the contaminant.

01 ☐ E. DIRECT CONTACT 02 ☐ OBSERVED (DATE _____) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION

No potential exists for direct contact with the mercury contaminated ground water.

01 ☒ F. CONTAMINATION OF SOIL 02 ☐ OBSERVED (DATE _____) ☒ POTENTIAL ☐ ALLEGED
03 AREA POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION

A potential for soil contamination exists due to the documented mercury contamination found in the ground water.

Attachment B & C

01 ☒ G. DRINKING WATER CONTAMINATION 02 ☒ OBSERVED (DATE 7-19-76) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION

Public supply wells #4 and #5 were sampled and analysis revealed inorganic mercury in excess of the safe drinking water standards. Well #4 is currently not in use.

Attachment B1-B6

01 ☒ H. WORKER EXPOSURE/INJURY 02 ☐ OBSERVED (DATE _____) ☒ POTENTIAL ☐ ALLEGED
03 WORKERS POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION

A potential exists for worker exposure/injury because well #4 is utilized in emergency situations.

Attachment B, C

01 ☒ I. POPULATION EXPOSURE/INJURY 02 ☐ OBSERVED (DATE _____) ☒ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: 8254 04 NARRATIVE DESCRIPTION

Approximately 32% of Monroe Township is not on public water supply or 8254 people.

Attachment H



POTENTIAL HAZARDOUS WASTE SITE
PRELIMINARY ASSESSMENT
PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

L IDENTIFICATION
01 STATE NJ 02 SITE NUMBER D980769699

II. HAZARDOUS CONDITIONS AND INCIDENTS (Continued)

01 ☒ J. DAMAGE TO FLORA 02 ☐ OBSERVED (DATE: _____) ☒ POTENTIAL ☐ ALLEGED
04 NARRATIVE DESCRIPTION
Surface water drainage and ground water discharge may potentially impact aquatic and terrestrial flora with mercury contamination.

Map 1

01 ☒ K. DAMAGE TO FAUNA 02 ☐ OBSERVED (DATE: _____) ☒ POTENTIAL ☐ ALLEGED
04 NARRATIVE DESCRIPTION (Include number(s) of species)
Surface water drainage and ground water discharge may potentially impact aquatic and terrestrial fauna with mercury contamination.

Map 1

01 ☒ L. CONTAMINATION OF FOOD CHAIN 02 ☐ OBSERVED (DATE: _____) ☒ POTENTIAL ☐ ALLEGED
04 NARRATIVE DESCRIPTION
The mode of action of mercury in organisms is that it is lipid soluble thus making it a potential agent for contaminating the food chain.

Attachment G

01 ☒ M. UNSTABLE CONTAINMENT OF WASTES 02 ☐ OBSERVED (DATE: _____) ☒ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION
A potential exists for unstable mercury waste to be contaminating the ground water.

Attachment B & C

01 ☒ N. DAMAGE TO OFFSITE PROPERTY 02 ☐ OBSERVED (DATE: _____) ☒ POTENTIAL ☐ ALLEGED
04 NARRATIVE DESCRIPTION
Analysis of a potable well owned by the Monroe Twp. Board of Education in July 1986 revealed mercury at 3.6 ppb which is in excess of the maximum contaminant level for safe drinking water.

Attachment C

01 ☐ O. CONTAMINATION OF SEWERS, STORM DRAINS, WWTPs 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
04 NARRATIVE DESCRIPTION
Sampling and analysis of standing water in a storm sewer culvert which accepts well #4 overflow revealed mercury below detectable limits.

Attachment B-30

01 ☒ P. ILLEGAL/UNAUTHORIZED DUMPING 02 ☐ OBSERVED (DATE: _____) ☒ POTENTIAL ☐ ALLEGED
04 NARRATIVE DESCRIPTION
A potential exists for unauthorized dumping of mercury waste to be contributing to the present ground water contamination.

05 DESCRIPTION OF ANY OTHER KNOWN, POTENTIAL, OR ALLEGED HAZARDS

Approximately 8254 people are not hooked up to the Municipal Water Supply and are at risk of being exposed to the contaminated ground water through the use of their domestic wells.

III. TOTAL POPULATION POTENTIALLY AFFECTED: _____

IV. COMMENTS

Sampling and analysis of potable water from the surrounding homes along Clayton and Janvier Roads is recommended.

V. SOURCES OF INFORMATION (See listing requirements on p. 3 of this form before making entries)

See reference sheet for list of attachments.



State of New Jersey
DEPARTMENT OF ENVIRONMENTAL PROTECTION
DIVISION OF HAZARDOUS WASTE MANAGEMENT

John J. Trela, Ph.D., Acting Director

CN 028

Trenton, N.J. 08625

609 - 292 - 1250

MEMORANDUM

APRIL 1987

TO: BARKER HAMMILL, CHIEF
BUREAU OF SAFE DRINKING WATER

THROUGH: STEPHEN A. BORGIANINI, CHIEF
BUREAU OF PLANNING AND ASSESSMENT

FROM: FRANK F. FARANCA, HSMS IV
BUREAU OF PLANNING AND ASSESSMENT

SUBJECT: MONROE TOWNSHIP MUNICIPAL WELLS

The Monroe Township Municipal Wells #4 & #5 are located in Monroe Township, Gloucester County, New Jersey. A Preliminary Assessment was prepared for this site pursuant to the Comprehensive Environmental Response Compensation and Liability Act. This report has revealed that a potential exists for mercury contamination in residential drinking wells outside of the public water supply system. A copy of this assessment is being sent to you to apprise you of the situation. If I can be of any assistance, please feel free to call me at 633-2219. Thank you for your attention in this matter.

FF:mz